Quote: Lee's Summit Fire Department Dispatch First-In Alerting Platform System Revised 2

To: Lee's Summit Fire Department	From: Zulema Perez

Lee's Summit Fire Department

207 SE Douglas Street

Lee's Summit, MO 64063

,

Contact:

Summary

Total Amount:	**$181,399.12**	Quote ID:	Q-09163-B6Y5 Revision: 2
Shipping Method:	Ground	Date:	3/6/2024
Payment Terms:	Net 30	Effective To:	6/5/2024

Description:

This quote is for Lee's Summit Fire Department Dispatch First-In Alerting Platform System including installation and one year of technical support. Quote includes Automated Voice Dispatch System, 1 AVD License, 1 Word Editor, 1 Radio Interface Controller (RIC), 1 Radio Interface Controller Lite (RIC Lite), 1 Server, and 1 Workstation with Client workstation.

The Radio Interface Controller (RIC) provides both automatic and manual activation of the fire station using wireless technology over the digital radio system. The alert information is automatically sent from the Computer Aided Dispatch system (CAD system) or the FiAP to the RIC, which transmits the information to the MCU. In the event the dispatch computer or network is down, the dispatcher uses the RIC's keypad to manually alert the station. Even in the manual backup mode, the RIC provides station and company-specific alerting. The RIC System operates on both analog and digital radio systems, as well as the new P25 radio system.

Client is responsible for all other integration and VPN access for Westnet. The client will need to provide a radio for the First-In Radio Interface Controller, and the installed radio will need an outside antenna with proper grounding. Client to supply and program any radio needed to control traffic lights, warning lights or other interfaces necessary.

The First-In Voice Dispatch (FiAVD) feature of the First-In Fire Station Alerting System provides the fire/rescue department and the dispatch center a quick, consistent means of providing automated, complete dispatch information to the responding emergency personnel. Management of FiAVD is performed by dispatch center personnel utilizing the First-In Voice Editor software. This software allows City personnel to edit the cadence and pronunciation of a particular word.

Clarifying Comments:

Quote assumes installation will occur while Westnet staff is onsite for the Fire Station install project. This quote is based upon installation occurring in 1 trip. If the station is not ready and additional trips are required, customer agrees to pay additional fees. Customer is responsible for all network connectivity between dispatch and station, as well as the CAD interface if network activation is desired. Customer to provide VPN access to Westnet for remote adjustments and support.

Quote was revised 8/27/2023 to add 5 Workstations with Client Software and update pricing.
Quote was revised 2/22/2024 to update the effective to date and pricing.

Shipping Information

Ship To: **Bill To:**

Details

Product ID	Product	QTY	Price	Sub Total
2U-SLT-SH-KIT	2U Slotted Shelf - Kit	2.00	$80.75	$161.50
FiAP-AVD	First-In Automated Voice Dispatch System	1.00	$27,075.00	$27,075.00
FiAP-AVD-AL	First-In Automated Voice Dispatch System - Additional License	1.00	$9,850.00	$9,850.00
FiAP-AVD-EDT	First-In Automated Voice Dispatch Word Editor	1.00	$3,082.75	$3,082.75
FiAP-CLIENT-WS	First-In Alerting Workstation with Client Software	6.00	$1,852.50	$11,115.00
FiAP-CORE-01S	First-In Alerting Platform 1 Station License Package	2.00	$1,315.75	$2,631.50
FiAP-CORE-5S-PKG	First-In Alerting Platform Core Station Alerting Software with up to 5 Station License Package	1.00	$12,207.50	$12,207.50
FiAP-CORE-SVR-SD	First-In Alerting Platform Standard Server	1.00	$3,775.87	$3,775.87
FRIC-LT	Radio Interface Controller (Lite) with 2 Keypads	1.00	$15,078.40	$15,078.40
QRIC-05-IVD	Radio Interface Controller with 5 Alerting Keypads	1.00	$46,312.50	$46,312.50

NOTES:

1. In the event that taxes, other than sales tax apply to the purchase of this equipment, said taxes will be paid by the customer.
2. Quote is based on a properly working and installed CAD, radio system(s), station radio(s) and does not include costs for repair or modifications of the CAD, radio system(s), or station radio(s).
3. Any equipment drawings included with this quote are for quoting purposes only and are not to be used as working drawings unless such drawings are labeled "Installation Drawings". See attached Limited Warranty.

Equipment Total	$131,290.02
Install Supplies	$195.00
Total Tax (%)	$0.00
Shipping and Handling	$1,281.25
FiAP Install, Commissioning, and Testing	$30,525.00
FiAP Training	$2,220.00
One Year Toll Free Technical Support	$13,112.85
Project Coordination	$2,775.00
Total Amount	**$181,399.12**

Manufacturer's warranties apply on all parts. First-In warranty is provided by Westnet and consists of one-year parts and labor. Warranty does not apply to damage resulting from outside agencies or extraneous circumstances. Installation labor for any other items is ninety days. This quote is based on the reasonable assumption that the fire station is prepared to accept the above listed parts and that any existing equipment involved with the fire station alarm be in good working order or that it will be prior to commencement of the First-In installation. Westnet has made reasonable attempts to verify that conditions are satisfactory such that installation may occur.However, should an occurrence arise where further parts, labor and/or engineering are required, the customer may be billed at the Purchase Order rate. Any additional parts, labor and/or engineering exceeding $250 will have prior approval, unless otherwise specified by the customer prior to commencement.

If payment is not received by 30 (thirty) days from the date of invoice, a late charge of 1.5% per month of the unpaid balance will be charged to that particular invoice.