

This is the unofficial bid tabulation and only reflects the reading of the bids and not the evaluation process of bids received.

BID NUMBER: 2019-033

PROJECT: Removal Disposal & Replacement of Tudor Roof

OPENS: 11/9/2018 @ 3:00PM

SPECIFICATION/DESCRIPTION	BIDDER	BIDDER
	Huttinger Construction	Quality Roofing
	Blue Springs, MO	Kansas City, MO
	PRICE	PRICE
Roof replacement Eastern Watershed Pumping Facility 1751 NE Tudor Road - Remove and dispose of the existing perimeter sheet metal, roofing and insulation. - Roof Mounted gas line to be temporarily removed. - Install new R=25 polyisocyanurate roof insulation – in two layers. - Install a vapor retarder (rubberized asphalt/ poly membrane) beneath the insulation. - Install a new 60 mil (white) TPO roof and flashing system. - New roof walkway protection to match the existing layout. - Install new sheet metal flashing and trim, specifically aluminum for exposed pieces including coping and edges. Color to be selected from the manufacturer’s standard colors. - Reset gas line at new height. New gas line supports. - Provide a 20 year manufacturer’s warranty.	\$61,077.00	\$72,475.00
Replacement in kind of gutters and downspouts. Color to be selected from the manufacturer’s standard colors.		
City standard payment terms are Net 30 after receipt of invoice. State any discounts offered.	na	none
Is the pricing provided above tax exempt per the City of Lee’s Summit’s State of Missouri tax exempt status as stated under section 1.0 Instructions to Bidders, paragraph 1.14?	No	Yes
If you answered “No” to the question posed, does the pricing provided above include any and all applicable taxes as stated under section 1.0 Instructions to Bidders, paragraph 1.14?	Yes	na

OPENED BY: ddt

UNOFFICIAL