



QUALITY CUSTOM CONSTRUCTION

9707 S Corn Road
 Lone Jack, MO 64070
 816-697-3232

Estimate

Date	Estimate #
3/6/2019	2450

Name / Address
LEES SUMMIT PUBLIC WORKS ATTN: RON JOHNSON

Item	Description	Qty	Cost	Total
NOTE	THIS PROPOSAL PERTAINS TO LSPW MAINTENANCE FACILITY - 1971 SE HAMBLEN RD			
8" Ext. Slab	REMOVE AND REPLACE BUILDING APRON ON SOUTH SIDE - FROM BUILDING SOUTHWARD TO NEWER RIBBON OF CONCRETE	11,400	6.95	79,230.00
AGGREGATE B...	NEW 4 IN AGGREGATE BASE	11,400	0.41	4,674.00
Misc	ADDITIONAL REMOVAL OF CONCRETE AROUND BALLARDS, EPOXY COATED TIE BARS (BASKET STYLE) SUPPLIED AND INSTALLED, CONSTRUCTION SEALANT IN ALL SAW CUTS, BREAKING OF AREA COMPLETED AFTER HOURS / WEEKEND DUE TO NOISE	1	8,625.32	8,625.32
SEALER	SUPPLY AND APPLY WATER BASE PENETRATING SEALER (SPECIFICALLY TK WB 290, SALT GUARD) BASED ON A QTY. OF 11,400 SQ FT.	11,400	0.24	2,736.00
NOTE	CONCRETE MIX TO BE KCM MB 5K. ALL CONCRETE TESTING TO BE PERFORMED BY SUPPLIER. TEMP, AIR ENTRAINMENT, AND SLUMP WILL BE TESTED. STRENGTH CYLINDER BREAKS WILL BE COMPLETED AT TERRACON LAB. FULL REPORTS WILL BE SUBMITTED TO THE CITY OF LEE'S SUMMIT.			
NOTE	DETAIL OF REINFORCEMENT ATTACHED			
NOTE	FOR QUESTIONS / SCHEDULING PLEASE CONTACT ED LIPOWICZ @ 913-208-8233. THANK YOU!			
We look forward to serving you!			Total	\$95,265.32