



## Lee's Summit Change Order Details

Bailey and Hamblen Signal Project - 71332272

---

|                                 |   |
|---------------------------------|---|
| <b>Description</b>              | <p>Installation of a permanent signal at the intersection of SE Bailey Rd and SE Hamblen Rd with fiber interconnect to the Lee's Summit Water Utilities Building. The new signal will include pedestrian accommodations (actuated push buttons and pedestrian signal indications), overhead vehicular indications, vehicle detection and fiber interconnect. Sidewalk and curb ramps will also be installed.</p> <p>Project Number: 71332272<br/>Purchase Order Number: 126665<br/>Fund Number: 32272750444<br/>Activity Number: 71332272<br/>Testing Lab:</p> <p><b>NOTE:</b> Appia Notice to Proceed date represents the contract Notice of Award. Appia Construction Start Date represents the project Notice to Proceed as defined in the contract.</p> |
| <b>Prime Contractor</b>         | <p>Capital Electric Line Builders, Inc.<br/>4400 NW Mattox Rd.<br/>Riverside, MO 64150</p>  |
| <b>Change Order</b>             | <p>1</p>  |
| <b>Status</b>                   | <p>Pending</p>  |
| <b>Date Created</b>             | <p>12/30/2020</p>   |
| <b>Type</b>                     | <p>City Council Approval</p>  |
| <b>Summary</b>                  | <p>Quantity overruns, Final Change Order</p>  |
| <b>Change Order Description</b> | <p>Final quantities change order.<br/>Curb and Gutter - Design didn't include quantity for gutter at ramps.</p>   |

Sod - Excavated material wasted on site and required additional sod for re-establishment.

NEW ITEM

ADA Detectable Panels - ADA Ramps adjusted on site due to differing field conditions and need to meet ADA Requirements.

**Awarded Project Amount**      \$345,824.50  
**Authorized Project Amount**    \$345,824.50  
**Change Order Amount**          \$26,395.60  
**Revised Project Amount**        \$372,220.10

**Increases/Decreases**

| Line Number                    | Item ID | Unit  | Unit Price | Current   |             | Change    |             | Revised   |             |
|--------------------------------|---------|-------|------------|-----------|-------------|-----------|-------------|-----------|-------------|
|                                |         |       |            | Quantity  | Amount      | Quantity  | Amount      | Quantity  | Amount      |
| <b>Section: 1 - 1 Base Bid</b> |         |       |            |           |             |           |             |           |             |
| 0016                           | 16      | LF    | \$52.800   | 20.000    | \$1,056.00  | 132.000   | \$6,969.60  | 152.000   | \$8,025.60  |
| Curb & Gutter (Type CG-1)      |         |       |            |           |             |           |             |           |             |
| 0044                           | 44      | Sq Yd | \$11.600   | 1,120.000 | \$12,992.00 | 1,610.000 | \$18,676.00 | 2,730.000 | \$31,668.00 |
| Sod                            |         |       |            |           |             |           |             |           |             |
| 2 items                        |         |       | Totals     |           | \$14,048.00 |           | \$25,645.60 |           | \$39,693.60 |

**New Items**

| Line Number                    | Item ID | Unit | Quantity | Unit Price | Extension |
|--------------------------------|---------|------|----------|------------|-----------|
| <b>Section: 1 - 1 Base Bid</b> |         |      |          |            |           |

| Line Number   | Item ID     | Unit | Quantity | Unit Price | Extension       |
|---|-------------|------|----------|------------|-----------------|
| 0060  | New Item(s) | EA   | 2.000    | \$375.000  | \$750.00        |
| New Item: ADA Detectable Panels                       |             |      |          |            |                 |
| <b>Reason:</b> Change in ADA Ramp design in the field |             |      |          |            |                 |
| 1 item  |             |      |          |            | Total: \$750.00 |