



Lee's Summit

Change Order Details

Delta School Road Stormwater Improvements

Description	NE Delta School Road stormwater project – Constructing an enclosed storm drainage system consisting of a box culvert, pipes and inlets, removing existing infrastructure and installing additional stormwater infrastructure on a new alignment, and swale grading to provide positive drainage and overflow conveyance. PO 128848 #576322-5C
Prime Contractor	Infrastructure Solutions, LLC 9801 Renner Boulevard Suite 300 Lenexa, KS 66219
Change Order	1
Status	Pending
Date Created	09/22/2021
Type	City Council Approval
Summary	Change Order 1
Change Order Description	During the course of construction the driveway was damaged severely beyond the scope of work on the plans. There was no way to avoid the damage due to size of the structure being installed. The existing condition of the driveway were very poor as well, which made finding a stopping point a challenge. The existing line item was overran to accommodate this. There was a pipe on the plans which called for removal. We decided to flowfill instead. Line item 33 was overran to accommodate this.
Awarded Project Amount	\$1,093,280.00

Authorized Project Amount \$1,093,280.00
Change Order Amount \$103,163.59
Revised Project Amount \$1,196,443.59

Increases/Decreases

Line Number	Item ID	Unit	Unit Price	Current		Change		Revised	
				Quantity	Amount	Quantity	Amount	Quantity	Amount
Section: 1 - Description									
0033	33	Cu Yd	\$130.000	21.000	\$2,730.00	35.000	\$4,550.00	56.000	\$7,280.00
Grout (Pipe Fill)									
0038	38	Sq Yd	\$85.000	198.000	\$16,830.00	1,250.000	\$106,250.00	1,448.000	\$123,080.00
Private Parking (Concrete) (6" KCM MB w/ Welded Wire Mesh) (4" MoDOT Type 5 Aggregate) (Remove and Replace)									
0039	39	Sq Yd	\$82.000	299.000	\$24,518.00	-299.000	-\$24,518.00	0.000	\$0.00
Private Parking (Asphalt) (6" Type 5-01) (6" MoDOT Type 5 Aggregate) (Geogrid) (Remove and Replace)									
3 items	Totals				\$44,078.00		\$86,282.00		\$130,360.00

New Items

Line Number	Item ID	Unit	Quantity	Unit Price	Extension
Section: 1 - Description					
0060	New Item(s)	LS	1.000	\$6,265.660	\$6,265.66
New Item: Connection to Storm System					

Line Number	Item ID	Unit	Quantity	Unit Price	Extension
-------------	---------	------	----------	------------	-----------

Reason: Two private drain lines that were draining a parking lot and building were found during construction. This item addresses the cost of connecting those pipes to the public storm system.

0070	New Item(s)	LS	1.000	\$10,615.930	\$10,615.93
New Item: Waterline relocation					
Reason: A water line was found to be in conflict with the new 51"x32" RCPA. This item accounts for all work necessary for the relocation of the watermain.					

2 items Total: \$16,881.59

Attachments

Document	Name	Description	Submission Date
Copy_of_Connect_parking_lot_pipes.xlsx	Copy of Connect parking lot pipes.xlsx		09/29/2021 09:01 AM CDT
Waterline_Relocation.pdf	Waterline Relocation.pdf		09/29/2021 09:02 AM CDT

2 attachments