

Traffic Impact Study

150 & Ward Multifamily




LEE'S SUMMIT, MISSOURI

FEBRUARY 2025

Prepared By:

Kimley»Horn



2/7/2025

Contents

1.0 INTRODUCTION.....	5
1.1 REPORT PURPOSE AND OBJECTIVES.....	5
2.0 EXISTING CONDITIONS.....	6
2.1 STUDY AREA.....	6
2.2 STREET NETWORK.....	6
2.3 DATA COLLECTION.....	7
3.0 PROPOSED DEVELOPMENT.....	8
3.1 SITE DESCRIPTION.....	8
3.2 SITE CIRCULATION.....	8
3.3 TRIP GENERATION.....	8
3.4 PROJECT TRIP DISTRIBUTION AND ASSIGNMENT.....	9
4.0 ACCESS MANAGEMENT.....	10
4.1 ACCESS SPACING.....	10
4.2 TURN LANE ANALYSIS.....	10
4.3 DRIVEWAY THROAT LENGTH.....	10
5.0 FUTURE CONDITIONS.....	11
6.0 INTERSECTION CAPACITY ANALYSIS.....	12
6.1 LEVEL OF SERVICE OVERVIEW.....	12
6.2 EXISTING (YEAR 2024) ANALYSIS.....	13
6.3 EXISTING PLUS DEVELOPMENT ANALYSIS.....	15
6.4 FUTURE (YEAR 2044) ANALYSIS.....	17
7.0 TRAFFIC SIGNAL WARRANT ANALYSIS.....	19
8.0 CONCLUSIONS AND RECOMMENDATIONS.....	20
APPENDIX.....	21

TABLES

TABLE 1: TRIP GENERATION8

TABLE 2: TRIP DISTRIBUTION.....9

TABLE 3: ANNUAL GROWTH RATE.....11

TABLE 4: LEVEL OF SERVICE12

TABLE 5: EXISTING (YEAR 2024) PEAK HOUR CONDITIONS14

TABLE 6: EXISTING PLUS DEVELOPMENT PEAK HOUR CONDITIONS16

TABLE 7: FUTURE (YEAR 2044) PEAK HOUR CONDITIONS18

TABLE 8: TRAFFIC SIGNAL WARRANT ANALYSIS.....19

EXHIBITS (SEE APPENDIX A)

- EXHIBIT 1: PROJECT SITE LOCATION AND STUDY AREA
- EXHIBIT 2: EXISTING CONDITIONS (YEAR 2024) PEAK HOUR TRAFFIC VOLUMES
- EXHIBIT 3: EXISTING GEOMETRY AND INTERSECTION CONTROL
- EXHIBIT 4: SITE TRIP DISTRIBUTION
- EXHIBIT 5: TOTAL PROJECT TRAFFIC
- EXHIBIT 6: EXISTING PLUS DEVELOPMENT PEAK HOUR TRAFFIC VOLUMES
- EXHIBIT 7: FUTURE (YEAR 2044) PEAK HOUR TRAFFIC VOLUMES

1.0 INTRODUCTION

This report serves as the traffic analysis for the 150 & Ward Multifamily development, generally located at the northwest corner of the Route 150 and Ward Road intersection in Lee's Summit, Missouri. The location of the development is shown on **Exhibit 1** in **Appendix A**.

1.1 REPORT PURPOSE AND OBJECTIVES

The purpose of this study is to address traffic and transportation impacts of the proposed development on surrounding streets and intersections. This traffic impact study was prepared based on criteria set forth by the City of Lee's Summit *Access Management Code*. The following information is provided.

- A description and map of the existing and proposed street network to be affected by the proposed development. This information includes existing and proposed roadway characteristics and existing traffic volumes.
- Trip generation calculations based on the Institute of Traffic Engineers (ITE) *Trip Generation Manual*, 11th Edition, for the proposed development. In addition, projected trip distributions onto the street network are provided.
- Analysis of impacts of the traffic generated by the proposed development on the street network, including analysis of peak period levels of service (LOS), delay times, and queuing at study area intersections.
- Evaluation of compliance with access management guidelines.
- Discussion of potential improvements and traffic management measures identified to mitigate operational concerns.

In summary, the study is to determine the trip generation of the 150 & Ward Multifamily development, assign new development trips to the street network, analyze various scenarios to determine the impacts of proposed site traffic, and identify potential mitigation measures needed to achieve acceptable operations at the study intersections.

2.0 EXISTING CONDITIONS

2.1 STUDY AREA

The development site is in the southern portion of Lee's Summit, Missouri, and consists of approximately 12 acres of undeveloped land. The land to the north of the site across Arborwalk Boulevard consists of single-family and multifamily neighborhoods. To the west of the site across Arborwalk Boulevard is open area that is part of Arborwalk Park. To the south of the site, there is undeveloped land that is planned to have commercial uses along Route 150. Southeast of the site there are existing commercial uses, including a gas station, at the northeast corner of Route 150 and Arborlake Drive. To the east of the site across Ward Road is a streamway buffer, then a single-family neighborhood.

Through discussion with City staff, three intersections along Route 150 and Ward Road were included within the study area for the traffic analysis. The Arborwalk Boulevard & Arborway Drive intersection will be the main access for the development, therefore it was also included as a study intersection. The list provides the existing intersection control for each of the study intersections.

- Route 150 & Ward Road (Signalized)
- Route 150 & Arborlake Drive/Stoney Creek Drive (Signalized)
- Ward Road & Arborwalk Boulevard (Side Street Stop)
- Arborwalk Boulevard & Arborway Drive (Roundabout)

2.2 STREET NETWORK

The existing street network within the study area includes Route 150, Ward Road, Arborlake Drive/Stoney Creek Drive, Arborwalk Boulevard, and Arborway Drive. The following provides a summary of the existing street network within the study area:

Route 150 (Missouri 150) is an east-west roadway to the south of the proposed development site. Route 150 is a four-lane divided highway with curbs and gutters. There is a sidewalk along the south side of Route 150 and a shared-use path along the north side. According to the Lee's Summit Thoroughfare Master Plan, Route 150 is classified as a Highway. The average annual daily traffic (AADT) on Route 150 is approximately 19,500 vpd according to the Missouri Department of Transportation (MoDOT) traffic volume maps. The posted speed limit is 45 miles per hour (mph). Route 150 provides access to the regional highway system with an interchange at Route 291 one mile to the east, and an interchange with I-49 roughly seven miles to the west of the site

Ward Road is a north-south roadway that runs along the east side of the proposed development. Ward Road is a four-lane, divided roadway with curbs and gutters and a posted speed limit of 45 mph. There is a sidewalk along the east side of Ward Road and a shared-use path along the west side. According to the Lee's Summit Thoroughfare Master Plan, Ward Road is classified as a Major Arterial. The AADT is approximately 7,500 vpd according to MoDOT traffic volume maps.

Arborlake Drive north-south roadway that runs west of the proposed development site. Arborlake Drive is a two-lane, divided roadway to the north of Route 150, with a posted speed limit of 30 mph. To the south of Route 150, the street is a two-lane undivided roadway and the name changes to Stoney Creek Drive. There are sidewalks along both sides of the roadway to the north and south of Route 150. According to the Lee's Summit Thoroughfare Master Plan, Arborlake Drive is classified as a Commercial Collector and Stoney Creek Drive is a Residential Collector.

Arborwalk Boulevard is a two-lane, undivided roadway that runs along the northwestern edge of the proposed development site. The roadway has curbs and gutters with a posted speed limit of 30 mph. There are sections of sidewalk and shared-use paths along the north side of the roadway. There are no sidewalks along the south side adjacent to the development site. According to the Lee's Summit Thoroughfare Master Plan, Arborwalk Boulevard is classified as a Commercial Collector.

2.3 DATA COLLECTION

Turning Movement Counts (TMCs) were collected at the four study intersections on Thursday, November 17, 2022. A 13-hour TMC (6:00 AM to 7:00 PM) was recorded at the Ward Road & Arborwalk Boulevard intersection. At Route 150 & Ward Road, Route 150 & Arborlake Drive/Stoney Creek Drive, and Arborwalk Boulevard & Arbor Park Drive peak hour TMCs were recorded from 7:00 AM to 9:00 AM and 4:00 PM to 6:00 PM. **Appendix B** provides the raw turning movement counts collected.

Turning movement counts are challenging to collect at roundabout intersections. Instead of collecting TMCs at the roundabout intersection, TMCs were collected at Arborwalk Boulevard & Arbor Park Drive. Turning movement volumes at the Arborwalk Boulevard & Arborway Drive roundabout intersection were derived by assigning the turning movement volumes at the roundabout intersection to balance with the counts at the two adjacent intersections.

To adjust the traffic counts to current year conditions, the volumes were increased at a rate of 2% per year for a 2-year period. The Existing Conditions peak hour turning movement volumes are shown on **Exhibit 2**. The existing geometry with lane configurations and intersection control at the study intersections is shown on **Exhibit 3**.

3.0 PROPOSED DEVELOPMENT

3.1 SITE DESCRIPTION

The proposed 150 & Ward Multifamily development consists of eight multifamily apartment buildings. There will be five three- and four-story buildings arranged generally around the perimeter of the site. In the center of the site will be three buildings and an amenity area. The total number of apartment units is 275. Surface parking is provided in the interior of the site. Several garage spaces are also available at several locations in the surface parking lot.

The proposed site plan is included in **Appendix C** for reference.

3.2 SITE CIRCULATION

The proposed development will be accessed from two access points. Access A is a proposed full-access drive along Arborwalk Boulevard located approximately 450 feet south and west of the Arbor Park Drive intersection. Access B is proposed to be the south leg of the existing single-lane roundabout at Arborwalk Boulevard & Arborway Drive.

Vehicles will circulate within the site through the aisles of the surface parking lot. Sidewalks are provided in front of the buildings and at the perimeter of the site along Arborwalk Boulevard.

3.3 TRIP GENERATION

Trip generation estimates were prepared using the *ITE Trip Generation Manual*, 11th Edition. **Table 1** shows the expected trips to be generated by the proposed development. The total trip generation is anticipated to be 1,838 daily trips, 108 trips during the AM peak hour (26 entering and 82 exiting), and 139 trips during the PM peak hour (87 entering and 52 exiting).

TABLE 1: TRIP GENERATION

Land Use Description	ITE Code	Intensity / Units	Daily	AM Peak Hour			PM Peak Hour		
				In	Out	Total	In	Out	Total
Multifamily Housing (Low-Rise)	220	275 Dwelling Units	1,838	26	82	108	87	52	139

The land use category for low-rise multifamily was used even though some of the buildings have more than three stories. The low-rise land use category provides a more conservative estimation of trip generation than the mid-rise category.

Appendix D provides the ITE Trip Generation Manual calculations used to determine the trip generation of the proposed site.

3.4 PROJECT TRIP DISTRIBUTION AND ASSIGNMENT

The estimated trips generated by the proposed development were assigned to the street network based on the trip distributions summarized in **Table 2**. This distribution is based on existing traffic patterns, the surrounding street network, and engineering judgement.

TABLE 2: TRIP DISTRIBUTION

Direction To/From	Percentage
North on Ward Road	35%
East on Route 150	35%
West on Route 150	30%
Total	100%

The detailed residential distribution patterns through the study intersections are shown in **Exhibit 4**.

Exhibit 5 shows the total development trip assignment. The proposed development trip assignments were added to the Existing Conditions traffic volumes. **Exhibit 6** illustrates the Existing plus Development peak hour traffic volumes.

4.0 ACCESS MANAGEMENT

The City of Lee's Summit has access management guidelines in the *Access Management Code* that addresses the location and design of access points. The guidelines were used to review various aspects of the proposed development in the following sections.

4.1 ACCESS SPACING

The *Access Management Code* includes requirements for the minimum allowable spacing between connections, depending on street classification. For an industrial/commercial collector such as Arborwalk Boulevard, the minimum spacing requirement is 300 feet. The distance between proposed Access A and the driveway to the existing gas station is 475 feet, and the distance between Access A and Arbor Park Drive is 450 feet. Therefore, the proposed site driveway on Arborwalk Boulevard is adequately spaced.

4.2 TURN LANE ANALYSIS

The *Access Management Code* also provides standards for left- and right-turn lanes based on traffic volumes and street classification. According to the *Access Management Code*, left-turn lanes are not required on collector streets when the left-turn volume is less than 30 vehicles in an hour. The left-turn volumes are not projected to exceed 10 for any scenario. Therefore, a left-turn lane is not warranted at proposed Access A along Arborwalk Boulevard. Right-turn lanes are not required on collector streets when the right-turn volume is less than 100 vehicles in an hour. The right-turn volumes are not projected to exceed 13 for any scenario and a right-turn lane is not warranted at Access A along Arborwalk Boulevard.

4.3 DRIVEWAY THROAT LENGTH

A driveway's throat length is the distance along a driveway from the intersecting roadway to the first location on site where a driver can make a turn. Adequate throat lengths minimize the potential for inbound traffic to queue onto the public street. The throat length also provides space for outbound traffic to queue without adversely impacting site circulation.

The throat length requirements in the *Access Management Code* are based on the two-way traffic volume on the driveway and the adjacent street classification. Access A is projected to have between 25 and 35 vehicles during the peak hours. As such the minimum required throat length for collector roadways is 50 feet. Access A is proposed to have a throat length of approximately 120 feet, which exceeds the minimum required throat length. Access B is projected to have between 80 and 105 vehicles during the peak hour. The *Access Management Code* states that for driveways with 100 vehicles per hour, the minimum throat length is the greater of 100 feet but may be longer if necessary to accommodate queue storage. Queue storage for Access B is discussed in the Intersection Capacity Analysis section of this study,

5.0 FUTURE CONDITIONS

Historical Annual Average Daily Traffic (AADT) volumes for Route 150 and Ward Road were analyzed to determine the growth rate for the study network. **Table 3** provides AADT volumes from 2016 and projected AADTs for 2050, as well as an annual growth rate for each facility. The AADT volumes are from the Mid-America Regional Council (MARC) Regional Traffic Forecast Map.

TABLE 3: ANNUAL GROWTH RATE

Road	Location	MARC Model AADT		Annual Growth Rate
		2016	2050	
Route 150	East of Ward Road	17,900	34,000	1.9%
	West of Ward Road	15,400	29,000	1.9%
Ward Road	North of Route 150	5,600	13,900	2.7%
	South of Route 150	7,100	12,400	1.7%

The data in the table indicate that the average annual growth rate in the study area is approximately 2%. To evaluate future conditions, the Existing Conditions traffic volumes at the study intersections were increased by 2%, and site trips were added. No adjacent development traffic was included in the future traffic volume projections. **Exhibit 7** illustrates the Future Conditions peak hour traffic volumes.

6.0 INTERSECTION CAPACITY ANALYSIS

6.1 LEVEL OF SERVICE OVERVIEW

Intersection capacity analysis was performed at the study intersections for the following three scenarios:

- Existing Conditions (Year 2024)
- Existing plus Development Conditions
- Future Conditions (Year 2044)

The capacity analysis was performed for the weekday AM and PM peak hours using Synchro or Sidra traffic modeling software to determine intersection delay and level of service (LOS). Calculations were performed based on the methodologies outlined in the *Highway Capacity Manual (HCM)*, 7th Edition, which is published by the Transportation Research Board.

LOS is a qualitative measure used by traffic engineers to describe the operations of an intersection. It ranges from A to F, with A being the best and F being the worst level of operation. LOS A conditions are characterized by minimal vehicle delay and free-flow conditions, while LOS F is characterized by long vehicle delay – usually when demand exceeds available roadway capacity. **Table 4** shows the definition of LOS for unsignalized and signalized intersections.

TABLE 4: LEVEL OF SERVICE

Level of Service	Average Control Delay (seconds/vehicle) at:	
	Unsignalized Intersections	Signalized Intersections
A	0 – 10	0 – 10
B	> 10 – 15	> 10 – 20
C	> 15 – 25	> 20 – 35
D	> 25 – 35	> 35 – 55
E	> 35 – 50	> 55 – 80
F	> 50	> 80

Levels of service are evaluated based on the movement groupings which are required to yield to other traffic. Typically, these are left turns off the major street and the side street approaches for two-way stop-controlled intersections. For signalized intersections each movement grouping is evaluated, and LOS is evaluated for the intersection as a whole.

The City of Lee's Summit has adopted LOS C as the minimum desirable LOS. However, LOS D and E may be considered acceptable for low to moderate traffic volumes, the availability of alternate routes, and the duration of activity resulting in lower LOS.

The decision to install a traffic signal is based on an evaluation of the warrants listed in the 11th Edition of the *Manual on Uniform Traffic Control Devices (MUTCD)*. The warranting criteria are based on traffic volumes, vehicle speeds, pedestrian volumes, crash history, and the adjacent street network. The traffic volume warrants were evaluated for this study.

The volume-to-capacity (v/c) ratio is a secondary measure of intersection performance. The v/c ratio represents the sufficiency of an intersection to accommodate the vehicular demand. A v/c ratio less than 0.85 generally indicates that adequate capacity is available, and vehicles are not expected to experience significant queues and delays. As the v/c ratio approaches 1.0, traffic flow may become unstable, and delay

and queuing conditions may occur. Once the demand exceeds the capacity (a v/c ratio greater than 1.0), traffic flow is unstable and excessive delay and queuing is expected. The v/c ratio is important in understanding low-volume movements that, due to their nature, may experience relatively high delays yet operate will under capacity.

Traffic queues were also evaluated as part of the analyses. Long traffic queues which extend beyond the amount of storage available, either between intersections or within turn lanes, can have significant impacts on operations. The projected vehicular queues were analyzed to ensure the analyses are reflective of the physical constraints of the study intersections and to identify if additional storage is needed for turn lanes.

6.2 EXISTING (YEAR 2024) ANALYSIS

Capacity analysis was conducted for existing traffic conditions at the study intersections to determine baseline conditions for the existing analysis year and to calibrate the models. The analysis was performed for weekday AM and PM peak hours and is based on the lane configurations and traffic volumes shown in **Exhibits 2 and 3**. The Synchro and Sidra reports are provided in **Appendix E**.

Table 5 on the following page provides a summary of the capacity analysis at the study intersections.

Based on the analysis, all intersections currently operate at acceptable LOS. Several individual movements at the signalized intersections operate at LOS D or E in both the AM and PM peak hours. While these are lower levels of service, the 95th percentile queue lengths are relatively short, and the volume-to-capacity ratios indicate that the movements currently operate under capacity.

TABLE 5: EXISTING (YEAR 2024) PEAK HOUR CONDITIONS

Intersection	Control	Movement	Operational Analysis Results							
			AM Peak Hour				PM Peak Hour			
			Delay (sec/veh)	LOS	95% Queue	V/C Ratio	Delay (sec/veh)	LOS	95% Queue	V/C Ratio
Route 150 & Ward Road	Traffic Signal	EBL	57.1	E	82'	0.71	56.4	E	92'	0.71
		EBT	0.2	A	80'	0.16	0.5	A	136'	0.39
		EBR	0.1	A	< 50'	0.04	0.5	A	< 50'	0.19
		WBL	60.0	E	< 50'	0.49	60.3	E	85'	0.71
		WBT	11.8	B	259'	0.36	11.6	B	162'	0.23
		WBR	10.2	B	< 50'	0.17	11.0	B	< 50'	0.15
		NBL	58.9	E	109'	0.75	61.3	E	62'	0.64
		NBT	51.0	D	137'	0.58	50.7	D	109'	0.46
		NBR	52.7	D	53'	0.59	60.2	E	58'	0.79
		SBL	60.6	E	79'	0.70	59.0	E	111'	0.76
		SBT	49.5	D	53'	0.21	47.6	D	143'	0.51
		SBR	61.9	E	57'	0.81	50.7	D	56'	0.63
		Overall	29.9	C	--	--	26.7	C	--	--
Route 150 & Arborlake Drive/Stoney Creek Drive	Traffic Signal	EBL	4.8	A	< 50'	0.05	5.7	A	< 50'	0.10
		EBT/R	6.4	A	87'	0.15	10.7	B	288'	0.44
		WBL	4.4	A	< 50'	0.06	7.2	A	61'	0.34
		WBT	0.4	A	204'	0.40	0.2	A	107'	0.22
		NBL	48.7	D	73'	0.24	46.7	D	< 50'	0.13
		NBT	50.6	D	< 50'	0.11	48.9	D	< 50'	0.12
		NBR	63.5	E	55'	0.80	63.0	E	53'	0.08
		SBL	49.1	D	54'	0.18	46.1	D	70'	0.26
		SBT	51.4	D	< 50'	0.07	47.2	D	< 50'	0.12
		Overall	9.8	A	--	--	13.1	B	--	0.41
Ward Road & Arborwalk Boulevard	Side Street Stop	EBL	15.9	C	< 50'	0.21	20.5	C	< 50'	0.22
		EBR	9.5	A	< 50'	0.03	10.4	B	< 50'	0.06
		NBL	8.5	A	< 50'	0.01	9.0	A	< 50'	0.02
Arborwalk Boulevard & Arborway Drive/Access B	Roundabout	EB	0.4	A	< 50'	0.05	0.3	A	< 50'	0.06
		WB	0.2	A	< 50'	0.03	0.2	A	< 50'	0.09
		NB	2.1	A	< 50'	0.01	2.1	A	< 50'	0.00
		SB	2.7	A	< 50'	0.10	2.8	A	< 50'	0.08
Arborwalk Boulevard & Arbor Park Drive	Side Street Stop	EBL	8.9	A	< 50'	0.03	9.2	A	< 50'	0.01
		NBL	7.3	A	< 50'	0.01	7.4	A	< 50'	0.01

6.3 EXISTING PLUS DEVELOPMENT ANALYSIS

Capacity analysis was conducted for Existing plus Development Conditions at the study intersections to determine the impact of site generated traffic from the proposed development. The analysis was performed for weekday AM and PM peak hours and is based on the traffic volumes shown in **Exhibit 6**. The lane configurations and intersection controls remain the same as the Existing Conditions scenario. All site driveways were analyzed as single-lane approaches. Access A was evaluated to be stop controlled at the intersection with Arborwalk Boulevard. The Synchro and Sidra reports are provided in **Appendix E**.

Table 6 on the next page provides a summary of the capacity analysis at the study intersections.

The analysis results in **Table 6** indicate that the addition of site generated trips from the proposed development is projected to have a minimal impact on the levels of service at the study intersections. All intersections are projected to operate at acceptable levels of service, except for the eastbound left-turn movement at the Ward Road & Arborwalk Boulevard intersection. The delay for this movement is projected to increase by 5.7 seconds, which will result in LOS D. The movement is projected to operate under capacity with minimal queueing even with LOS D conditions.

As in the Existing Conditions scenario, several movements at the signalized intersections are projected to operate at LOS D or E during both peak hours. However, the 95th percentile queue lengths are relatively short, and the volume-to-capacity ratios indicate that the movements are projected to operate under capacity.

The Arborwalk Boulevard & Arborway Drive/Access B intersection is projected to operate acceptably with minimal delays and queueing. The 95th percentile queue for the northbound approach of the roundabout is projected to be less than 50 feet during both peak hours. The provided throat length of approximately 120 feet at Access B will contain the projected 95th percentile queues.

TABLE 6: EXISTING PLUS DEVELOPMENT PEAK HOUR CONDITIONS

Intersection	Control	Movement	Operational Analysis Results							
			AM Peak Hour				PM Peak Hour			
			Delay (sec/veh)	LOS	95% Queue	V/C Ratio	Delay (sec/veh)	LOS	95% Queue	V/C Ratio
Route 150 & Ward Road	Traffic Signal	EBL	57.1	E	84'	0.71	56.4	E	93'	0.72
		EBT	0.2	A	80'	0.16	0.6	A	134'	0.42
		EBR	0.1	A	< 50'	0.04	0.5	A	< 50'	0.20
		WBL	60.0	E	< 50'	0.49	60.3	E	85'	0.72
		WBT	11.8	B	265'	0.36	11.9	B	164'	0.25
		WBR	10.3	B	< 50'	0.18	11.7	B	< 50'	0.19
		NBL	58.9	E	109'	0.75	61.3	E	62'	0.65
		NBT	52.3	D	137'	0.63	50.7	D	111'	0.48
		NBR	54.5	D	53'	0.64	60.2	E	58'	0.80
		SBL	60.1	E	92'	0.74	58.7	E	119'	0.78
		SBT	49.5	D	54'	0.22	47.0	D	143'	0.49
		SBR	61.8	E	56'	0.81	49.7	D	56'	0.61
		Overall	30.4	C	--	--	26.8	C	--	--
Route 150 & Arborlake Drive/Stoney Creek Drive	Traffic Signal	EBL	4.7	A	< 50'	0.07	5.7	A	< 50'	0.13
		EBT/R	6.4	A	90'	0.15	10.7	B	314'	0.41
		WBL	4.4	A	< 50'	0.06	7.2	A	87'	0.32
		WBT	0.4	A	204'	0.40	0.2	A	117'	0.22
		NBL	48.7	D	72'	0.24	46.7	D	< 50'	0.08
		NBT	50.6	D	< 50'	0.11	48.9	D	< 50'	0.09
		NBR	63.5	E	54'	0.80	63.0	E	58'	0.82
		SBL	49.1	D	54'	0.18	46.1	D	71'	0.23
		SBT	51.4	D	< 50'	0.07	47.2	D	< 50'	0.11
		Overall	9.7	A	--	--	13.0	B	--	--
Ward Road & Arborwalk Boulevard	Side Street Stop	EBL	17.6	C	< 50'	0.30	25.7	D	< 50'	0.33
		EBR	9.7	A	< 50'	0.07	10.6	B	< 50'	0.09
		NBL	8.5	A	< 50'	0.02	9.3	A	< 50'	0.06
Arborwalk Boulevard & Arborway Drive/Access B	Roundabout	EB	0.5	A	< 50'	0.06	0.5	A	< 50'	0.08
		WB	0.3	A	< 50'	0.05	0.2	A	< 50'	0.14
		NB	2.4	A	< 50'	0.06	2.4	A	< 50'	0.04
		SB	2.8	A	< 50'	0.12	3.1	A	< 50'	0.08
Arborwalk Boulevard & Arbor Park Drive	Side Street Stop	EBL	9.0	A	< 50'	0.03	9.4	A	< 50'	0.02
		NBL	7.4	A	< 50'	0.01	7.4	A	< 50'	0.01
Arborwalk Boulevard & Access A	Side Street Stop	WBL	7.3	A	< 50'	0.01	7.5	A	< 50'	0.01
		SBL	9.1	A	< 50'	0.02	9.3	A	< 50'	0.02

6.4 FUTURE (YEAR 2044) ANALYSIS

Capacity analysis was conducted for future traffic conditions at the study intersections to determine the need for capacity improvements within the study network in the future. The analysis was performed for weekday AM and PM peak hours and is based on the traffic volumes shown in **Exhibit 7**. The lane configurations and intersection controls remain the same as the Existing plus Development Conditions scenario. The Synchro and Sidra reports are provided in **Appendix E**.

Table 7 provides a summary of the capacity analysis at the study intersections.

Overall, the signalized intersections are projected to operate at acceptable levels of service in the future. The analysis results indicate that several movements are projected to operate at LOS D or E at the signalized intersections. Some longer queues are projected in the eastbound and westbound through lanes of Route 150. Most of these queues do not extend through to adjacent intersections. However, the eastbound through movement at the Route 150 & Arborlake Drive/Stoney Creek Drive intersection is projected to have 95th percentile queue of 756 feet during the PM peak hour. This length of queue would extend through the Granite Lane intersection for a short duration at certain times during the PM peak hour. The signalized intersections were analyzed with a 120-second cycle length. A shorter cycle length would reduce queues and improve operations at the intersections.

All movements at the unsignalized intersections are projected to operate acceptably, except for the eastbound left-turn movement at Ward Road & Arborwalk Boulevard. The eastbound left-turn movement is projected to operate at LOS E in the AM peak hour and LOS F in the PM peak hour. During the PM peak hour, the 95th percentile queue is projected to be six car lengths.

TABLE 7: FUTURE (YEAR 2044) PEAK HOUR CONDITIONS

Intersection	Control	Movement	Operational Analysis Results							
			AM Peak Hour				PM Peak Hour			
			Delay (sec/veh)	LOS	95% Queue	V/C Ratio	Delay (sec/veh)	LOS	95% Queue	V/C Ratio
Route 150 & Ward Road	Traffic Signal	EBL	57.8	E	120'	0.79	55.0	E	122'	0.80
		EBT	0.4	A	140'	0.28	2.8	A	403'	0.78
		EBR	0.1	A	< 50'	0.06	1.5	A	103'	0.38
		WBL	61.9	E	60'	0.65	64.1	E	124'	0.80
		WBT	23.1	C	517'	0.66	21.0	C	291'	0.46
		WBR	17.7	B	78'	0.32	19.7	B	< 50'	0.33
		NBL	61.3	E	160'	0.82	61.5	E	90'	0.72
		NBT	48.0	D	195'	0.65	47.0	D	155'	0.52
		NBR	50.2	D	59'	0.67	72.5	E	87'	0.88
		SBL	63.1	E	129'	0.80	65.1	E	174'	0.85
		SBT	45.1	D	72'	0.23	42.1	D	203'	0.54
		SBR	70.5	E	110'	0.87	47.3	D	62'	0.68
		Overall	34.5	C	--	--	29.7	C	--	--
Route 150 & Arborlake Drive/Stoney Creek Drive	Traffic Signal	EBL	6.7	A	< 50'	0.14	9.8	A	< 50'	0.26
		EBT/R	9.6	A	138'	0.25	25.3	C	756'	0.77
		WBL	6.4	A	< 50'	0.12	34.4	C	236'	0.86
		WBT	1.0	A	334'	0.67	0.5	A	157'	0.40
		NBL	44.2	D	103'	0.29	41.6	D	< 50'	0.10
		NBT	46.6	D	< 50'	0.12	44.3	D	< 50'	0.10
		NBR	65.0	E	66'	0.86	74.3	E	69'	0.89
		SBL	45.2	D	75'	0.23	39.8	D	104'	0.28
		SBT	48.0	D	< 50'	0.08	41.6	D	62'	0.12
		Overall	10.7	B	--	--	22.9	C	--	--
Ward Road & Arborwalk Boulevard	Side Street Stop	EBL	47.1	E	112'	0.69	>100	F	160'	0.97
		EBR	10.5	B	< 50'	0.10	12.7	B	< 50'	0.16
		NBL	9.3	A	< 50'	0.03	11.2	B	< 50'	0.10
Arborwalk Boulevard & Arborway Drive	Roundabout	EB	0.8	A	< 50'	0.10	0.7	A	< 50'	0.12
		WB	0.4	A	< 50'	0.07	0.4	A	< 50'	0.19
		NB	2.9	A	< 50'	0.07	2.7	A	< 50'	0.04
		SB	2.9	A	< 50'	0.17	3.2	A	< 50'	0.13
Arborwalk Boulevard & Arbor Park Drive	Side Street Stop	EBL	9.3	A	< 50'	0.05	9.8	A	< 50'	0.03
		NBL	7.4	A	< 50'	0.01	7.5	A	< 50'	0.01
Arborwalk Boulevard & Access A	Side Street Stop	WBL	9.4	A	< 50'	0.03	9.7	A	< 50'	0.02
		SBL	7.4	A	< 50'	0.01	7.5	A	< 50'	0.01

7.0 TRAFFIC SIGNAL WARRANT ANALYSIS

The need for a traffic signal is evaluated based on the applicable factors contained in the traffic signal warrants of the MUTCD. Given the lower level of service observed at the Ward Road & Arborwalk Boulevard intersection, traffic signal warrant analysis was conducted.

For the warrant analysis hourly traffic count data collected at the intersection from 6:00 AM to 7:00 PM was compared to the minimum volume criteria of the traffic volume warrants (Warrants 1 through 3) of the MUTCD for Existing Conditions. For Existing plus Development Conditions, the hourly variation of daily traffic from the *Trip Generation Manual* was used to project site trips. The site trips were then added to the existing hourly volumes. For future conditions, the existing volumes were increased by 2.0% per year, and the site trips were added. The results of the warrant analysis are summarized in **Table 8**. The traffic signal warrant analysis worksheets are provided in **Appendix F**.

TABLE 8: TRAFFIC SIGNAL WARRANT ANALYSIS

MUTCD Warrant	Existing Conditions	Existing plus Development	Future Conditions
Warrant 1a (Eight-Hour Vehicular Volume, Minimum Vehicular Volume)	NO	NO	NO
Warrant 1b (Eight-Hour Vehicular Volume, Interruption of continuous Traffic)	NO	NO	YES
Warrant 2 (Four-Hour Vehicular Volume)	NO	NO	YES
Warrant 3 (Peak Hour)	NO	NO	YES

The results of the analysis indicate that a traffic signal is projected to be warranted at the intersection in the future, but not for Existing or Existing plus Development conditions. Signalization is expected to improve operations for the eastbound movements at the intersection in the future.

8.0 CONCLUSIONS AND RECOMMENDATIONS

A traffic impact study for the 150 & Ward Multifamily development has been prepared by Kimley-Horn. The proposed site is located near the northwest corner of the Route 150 and Ward Road intersection in Lee's Summit, Missouri. The purpose of this study was to assess the impact of the proposed development on the surrounding transportation system. The following provides a summary of the analysis.

Intersection capacity analysis was performed at the study intersections for the following three scenarios:

- Existing Conditions (Year 2024)
- Existing plus Development Conditions
- Future Conditions (Year 2044)

All study intersections were found to currently be operating at acceptable levels of service.

The proposed development is projected to generate 1,838 daily trips, with 108 trips in the AM peak hour, and 139 trips in the PM peak hour. The site trips were added to the street network and all study intersections are projected to continue to operate at acceptable levels of service with one exception. The eastbound left-turn movement at the intersection of Ward Road & Arborwalk Boulevard is projected to operate at a LOS D during the PM peak hour. However, the movement is projected to operate under capacity in this scenario, and traffic signal installation will not be warranted. Traffic volumes are not projected to satisfy turn lane warrants at the proposed Access A intersection along Arborwalk Boulevard. As such, no improvements are identified to mitigate the addition of site trips for the proposed development.

The Future Conditions scenario includes background traffic growth. All intersections are projected to operate at acceptable levels of service with one exception. The eastbound left-turn movement at the intersection of Ward Road & Arborwalk Boulevard is projected to operate at a LOS E during the AM peak hour and LOS F during the PM peak hour. Traffic signal warrant analysis indicated that a traffic signal is projected to be warranted at Ward Road & Arborwalk Boulevard in the future. Signalization is expected to improve operations for the eastbound movements at the intersection.

APPENDIX

Appendix A: EXHIBITS

Appendix B: TURNING MOVEMENT COUNTS

Appendix C: SITE PLAN

Appendix D: ITE TRIP GENERATION MANUAL SHEETS


Appendix E: CAPACITY ANALYSIS REPORTS

Appendix F: SIGNAL WARRANT ANALYSIS


Appendix A: Exhibits










* South leg of roundabout quickly transitions to a gravel access road.









Appendix B: Turning Movement Counts



1_MO-150 & Ward Road - TMC

Thu Nov 17, 2022

Full Length (6 AM-7 PM)

All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1012132, Location: 38.853263, -94.398718



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US

Leg Direction	MO 150 Eastbound					MO 150 Westbound					Ward Northbound					Ward Southbound					
Time	L	T	R	U	App	L	T	R	U	App	L	T	R	U	App	L	T	R	U	App	Int
2022-11-17 6:00AM	3	18	2	0	23	0	62	2	0	64	16	13	10	0	39	2	5	11	0	18	144
6:15AM	11	38	5	0	54	1	117	8	0	126	27	11	8	0	46	5	7	11	0	23	249
6:30AM	9	54	4	1	68	8	141	15	0	164	25	28	13	0	66	11	9	10	0	30	328
6:45AM	28	70	9	0	107	5	123	52	0	180	26	59	20	0	105	16	6	9	0	31	423
Hourly Total	51	180	20	1	252	14	443	77	0	534	94	111	51	0	256	34	27	41	0	102	1144
7:00AM	47	52	6	0	105	11	124	72	0	207	47	61	21	0	129	36	7	27	0	70	511
7:15AM	32	87	6	0	125	8	183	25	0	216	36	53	29	1	119	34	20	37	1	92	552
7:30AM	21	88	8	1	118	16	203	23	0	242	46	53	32	0	131	22	20	32	0	74	565
7:45AM	21	87	10	0	118	15	174	22	0	211	40	56	20	0	116	20	22	22	0	64	509
Hourly Total	121	314	30	1	466	50	684	142	0	876	169	223	102	1	495	112	69	118	1	300	2137
8:00AM	28	90	11	0	129	11	153	20	0	184	32	51	32	0	115	19	15	15	0	49	477
8:15AM	25	68	8	0	101	14	131	35	0	180	35	45	20	0	100	18	25	17	0	60	441
8:30AM	19	70	12	0	101	7	120	28	0	155	36	45	19	0	100	15	15	13	0	43	399
8:45AM	24	85	18	0	127	14	95	24	0	133	29	48	30	0	107	16	22	21	0	59	426
Hourly Total	96	313	49	0	458	46	499	107	0	652	132	189	101	0	422	68	77	66	0	211	1743
9:00AM	17	83	15	0	115	13	77	24	0	114	28	36	21	0	85	14	19	13	0	46	360
9:15AM	13	50	9	0	72	9	90	19	0	118	23	25	14	0	62	17	17	13	0	47	299
9:30AM	11	69	8	0	88	11	92	21	0	124	27	32	21	0	80	9	17	15	0	41	333
9:45AM	11	74	9	0	94	10	64	14	0	88	13	26	12	0	51	14	14	16	0	44	277
Hourly Total	52	276	41	0	369	43	323	78	0	444	91	119	68	0	278	54	67	57	0	178	1269
10:00AM	14	69	8	0	91	14	64	9	0	87	20	30	10	0	60	20	24	17	0	61	299
10:15AM	13	58	6	0	77	11	74	19	0	104	30	22	13	0	65	13	16	21	0	50	296
10:30AM	11	72	10	0	93	3	90	17	0	110	19	24	12	0	55	20	24	14	0	58	316
10:45AM	15	63	16	0	94	12	70	15	0	97	17	29	17	0	63	18	22	13	0	53	307
Hourly Total	53	262	40	0	355	40	298	60	0	398	86	105	52	0	243	71	86	65	0	222	1218
11:00AM	9	57	7	0	73	13	82	11	0	106	17	37	23	0	77	8	19	10	0	37	293
11:15AM	18	77	18	0	113	14	73	12	0	99	17	41	21	0	79	23	25	17	0	65	356
11:30AM	11	72	20	0	103	12	69	20	0	101	13	27	13	0	53	21	18	19	0	58	315
11:45AM	12	90	16	0	118	14	75	13	0	102	9	19	14	0	42	26	23	10	0	59	321
Hourly Total	50	296	61	0	407	53	299	56	0	408	56	124	71	0	251	78	85	56	0	219	1285
12:00PM	9	71	17	0	97	18	83	23	0	124	16	32	17	0	65	18	35	14	0	67	353
12:15PM	12	70	17	0	99	10	84	16	0	110	15	23	26	0	64	24	34	10	0	68	341
12:30PM	9	84	12	0	105	18	77	14	0	109	24	27	7	0	58	19	21	20	0	60	332
12:45PM	11	82	11	0	104	12	86	18	0	116	22	32	17	0	71	28	19	15	0	62	353
Hourly Total	41	307	57	0	405	58	330	71	0	459	77	114	67	0	258	89	109	59	0	257	1379
1:00PM	12	88	16	0	116	13	64	10	0	87	19	31	16	0	66	17	17	13	0	47	316
1:15PM	12	71	16	0	99	13	60	19	0	92	10	27	20	0	57	16	31	14	0	61	309
1:30PM	7	88	13	0	108	10	62	13	0	85	21	40	15	0	76	31	22	17	0	70	339
1:45PM	20	85	19	0	124	8	81	22	0	111	14	19	23	0	56	24	41	17	0	82	373
Hourly Total	51	332	64	0	447	44	267	64	0	375	64	117	74	0	255	88	111	61	0	260	1337
2:00PM	18	77	22	0	117	16	80	32	0	128	18	26	27	0	71	19	25	12	0	56	372
2:15PM	19	106	15	0	140	27	72	17	0	116	20	32	13	0	65	42	44	33	0	119	440
2:30PM	13	82	21	1	117	18	73	22	0	113	13	42	29	0	84	55	54	45	0	154	468
2:45PM	17	119	21	1	158	27	105	27	0	159	14	39	30	0	83	40	35	26	0	101	501
Hourly Total	67	384	79	2	532	88	330	98	0	516	65	139	99	0	303	156	158	116	0	430	1781
3:00PM	20	112	22	1	155	17	86	30	0	133	27	34	26	0	87	32	46	28	0	106	481
3:15PM	20	123	18	0	161	20	117	29	0	166	20	25	17	0	62	37	42	30	0	109	498
3:30PM	21	129	26	0	176	23	95	31	0	149	15	37	21	0	73	29	60	39	0	128	526
3:45PM	17	132	36	0	185	14	105	27	0	146	16	29	23	0	68	30	55	24	0	109	508
Hourly Total	78	496	102	1	677	74	403	117	0	594	78	125	87	0	290	128	203	121	0	452	2013
4:00PM	18	146	28	0	192	22	84	30	0	136	16	36	24	0	76	29	49	29	0	107	511
4:15PM	26	189	34	0	249	30	87	26	0	143	14	29	21	0	64	34	43	15	0	92	548
4:30PM	24	173	46	0	243	31	87	21	0	139	21	45	31	0	97	33	43	27	0	103	582
4:45PM	32	201	34	1	268	35	106	27	0	168	13	39	33	0	85	34	70	30	0	134	655

Leg Direction	MO 150 Eastbound					MO 150 Westbound					Ward Northbound					Ward Southbound					
Time	L	T	R	U	App	L	T	R	U	App	L	T	R	U	App	L	T	R	U	App	Int
Hourly Total	100	709	142	1	952	118	364	104	0	586	64	149	109	0	322	130	205	101	0	436	2296
5:00PM	27	153	32	0	212	36	94	33	0	163	24	38	26	0	88	38	53	45	0	136	599
5:15PM	31	212	42	0	285	33	134	37	0	204	22	49	40	0	111	58	56	24	0	138	738
5:30PM	34	172	44	0	250	17	105	30	0	152	22	35	24	0	81	40	54	30	0	124	607
5:45PM	27	136	34	1	198	20	82	37	0	139	18	48	34	0	100	38	41	32	0	111	548
Hourly Total	119	673	152	1	945	106	415	137	0	658	86	170	124	0	380	174	204	131	0	509	2492
6:00PM	34	98	32	0	164	30	90	25	0	145	14	26	28	0	68	34	36	22	0	92	469
6:15PM	12	98	18	0	128	23	90	22	0	135	22	27	15	0	64	29	41	30	0	100	427
6:30PM	15	90	19	0	124	28	93	16	0	137	19	24	24	0	67	17	36	17	0	70	398
6:45PM	11	84	17	0	112	33	90	32	1	156	15	16	23	0	54	18	26	16	0	60	382
Hourly Total	72	370	86	0	528	114	363	95	1	573	70	93	90	0	253	98	139	85	0	322	1676
Total	951	4912	923	7	6793	848	5018	1206	1	7073	1132	1778	1095	1	4006	1280	1540	1077	1	3898	21770
% Approach	14.0%	72.3%	13.6%	0.1%	-	12.0%	70.9%	17.1%	0%	-	28.3%	44.4%	27.3%	0%	-	32.8%	39.5%	27.6%	0%	-	-
% Total	4.4%	22.6%	4.2%	0%	31.2%	3.9%	23.1%	5.5%	0%	32.5%	5.2%	8.2%	5.0%	0%	18.4%	5.9%	7.1%	4.9%	0%	17.9%	-
Lights	930	4740	911	7	6588	826	4850	1181	1	6858	1113	1763	1070	1	3947	1237	1529	1048	1	3815	21208
% Lights	97.8%	96.5%	98.7%	100%	97.0%	97.4%	96.7%	97.9%	100%	97.0%	98.3%	99.2%	97.7%	100%	98.5%	96.6%	99.3%	97.3%	100%	97.9%	97.4%
Articulated Trucks	3	40	2	0	45	3	36	0	0	39	3	3	3	0	9	3	1	1	0	5	98
% Articulated Trucks	0.3%	0.8%	0.2%	0%	0.7%	0.4%	0.7%	0%	0%	0.6%	0.3%	0.2%	0.3%	0%	0.2%	0.2%	0.1%	0.1%	0%	0.1%	0.5%
Buses and Single-Unit Trucks	18	132	10	0	160	19	132	25	0	176	16	12	22	0	50	40	10	28	0	78	464
% Buses and Single-Unit Trucks	1.9%	2.7%	1.1%	0%	2.4%	2.2%	2.6%	2.1%	0%	2.5%	1.4%	0.7%	2.0%	0%	1.2%	3.1%	0.6%	2.6%	0%	2.0%	2.1%

*L: Left, R: Right, T: Thru, U: U-Turn

1_MO-150 & Ward Road - TMC

Thu Nov 17, 2022

Full Length (6 AM-7 PM)


All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1012132, Location: 38.853263, -94.398718



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US



1_MO-150 & Ward Road - TMC

Thu Nov 17, 2022

AM Peak (7 AM - 8 AM)

All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1012132, Location: 38.853263, -94.398718



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US

Leg Direction	MO 150 Eastbound					MO 150 Westbound					Ward Northbound					Ward Southbound					
Time	L	T	R	U	App	L	T	R	U	App	L	T	R	U	App	L	T	R	U	App	Int
2022-11-17 7:00AM	47	52	6	0	105	11	124	72	0	207	47	61	21	0	129	36	7	27	0	70	511
7:15AM	32	87	6	0	125	8	183	25	0	216	36	53	29	1	119	34	20	37	1	92	552
7:30AM	21	88	8	1	118	16	203	23	0	242	46	53	32	0	131	22	20	32	0	74	565
7:45AM	21	87	10	0	118	15	174	22	0	211	40	56	20	0	116	20	22	22	0	64	509
Total	121	314	30	1	466	50	684	142	0	876	169	223	102	1	495	112	69	118	1	300	2137
% Approach	26.0%	67.4%	6.4%	0.2%	-	5.7%	78.1%	16.2%	0%	-	34.1%	45.1%	20.6%	0.2%	-	37.3%	23.0%	39.3%	0.3%	-	-
% Total	5.7%	14.7%	1.4%	0%	21.8%	2.3%	32.0%	6.6%	0%	41.0%	7.9%	10.4%	4.8%	0%	23.2%	5.2%	3.2%	5.5%	0%	14.0%	-
PHF	0.644	0.892	0.750	0.250	0.932	0.781	0.842	0.493	-	0.905	0.899	0.914	0.797	0.250	0.945	0.778	0.784	0.797	0.250	0.815	0.946
Lights	120	303	27	1	451	46	656	138	0	840	168	221	100	1	490	101	68	114	1	284	2065
% Lights	99.2%	96.5%	90.0%	100%	96.8%	92.0%	95.9%	97.2%	0%	95.9%	99.4%	99.1%	98.0%	100%	99.0%	90.2%	98.6%	96.6%	100%	94.7%	96.6%
Articulated Trucks	1	1	1	0	3	1	4	0	0	5	1	0	1	0	2	0	0	0	0	0	10
% Articulated Trucks	0.8%	0.3%	3.3%	0%	0.6%	2.0%	0.6%	0%	0%	0.6%	0.6%	0%	1.0%	0%	0.4%	0%	0%	0%	0%	0%	0.5%
Buses and Single-Unit Trucks	0	10	2	0	12	3	24	4	0	31	0	2	1	0	3	11	1	4	0	16	62
% Buses and Single-Unit Trucks	0%	3.2%	6.7%	0%	2.6%	6.0%	3.5%	2.8%	0%	3.5%	0%	0.9%	1.0%	0%	0.6%	9.8%	1.4%	3.4%	0%	5.3%	2.9%

*L: Left, R: Right, T: Thru, U: U-Turn

1_MO-150 & Ward Road - TMC

Thu Nov 17, 2022

AM Peak (7 AM - 8 AM)


All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1012132, Location: 38.853263, -94.398718



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US



1_MO-150 & Ward Road - TMC

Thu Nov 17, 2022

Midday Peak (12 PM - 1 PM)

All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1012132, Location: 38.853263, -94.398718



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US

Leg Direction	MO 150 Eastbound					MO 150 Westbound					Ward Northbound					Ward Southbound					
Time	L	T	R	U	App	L	T	R	U	App	L	T	R	U	App	L	T	R	U	App	Int
2022-11-17 12:00PM	9	71	17	0	97	18	83	23	0	124	16	32	17	0	65	18	35	14	0	67	353
12:15PM	12	70	17	0	99	10	84	16	0	110	15	23	26	0	64	24	34	10	0	68	341
12:30PM	9	84	12	0	105	18	77	14	0	109	24	27	7	0	58	19	21	20	0	60	332
12:45PM	11	82	11	0	104	12	86	18	0	116	22	32	17	0	71	28	19	15	0	62	353
Total	41	307	57	0	405	58	330	71	0	459	77	114	67	0	258	89	109	59	0	257	1379
% Approach	10.1%	75.8%	14.1%	0%	-	12.6%	71.9%	15.5%	0%	-	29.8%	44.2%	26.0%	0%	-	34.6%	42.4%	23.0%	0%	-	-
% Total	3.0%	22.3%	4.1%	0%	29.4%	4.2%	23.9%	5.1%	0%	33.3%	5.6%	8.3%	4.9%	0%	18.7%	6.5%	7.9%	4.3%	0%	18.6%	-
PHF	0.854	0.914	0.838	-	0.964	0.806	0.959	0.772	-	0.925	0.802	0.891	0.644	-	0.908	0.795	0.779	0.738	-	0.945	0.977
Lights	38	294	56	0	388	58	312	66	0	436	75	111	65	0	251	85	108	55	0	248	1323
% Lights	92.7%	95.8%	98.2%	0%	95.8%	100%	94.5%	93.0%	0%	95.0%	97.4%	97.4%	97.0%	0%	97.3%	95.5%	99.1%	93.2%	0%	96.5%	95.9%
Articulated Trucks	0	6	0	0	6	0	3	0	0	3	0	1	0	0	1	2	0	0	0	2	12
% Articulated Trucks	0%	2.0%	0%	0%	1.5%	0%	0.9%	0%	0%	0.7%	0%	0.9%	0%	0%	0.4%	2.2%	0%	0%	0%	0.8%	0.9%
Buses and Single-Unit Trucks	3	7	1	0	11	0	15	5	0	20	2	2	2	0	6	2	1	4	0	7	44
% Buses and Single-Unit Trucks	7.3%	2.3%	1.8%	0%	2.7%	0%	4.5%	7.0%	0%	4.4%	2.6%	1.8%	3.0%	0%	2.3%	2.2%	0.9%	6.8%	0%	2.7%	3.2%

* L: Left, R: Right, T: Thru, U: U-Turn

1_MO-150 & Ward Road - TMC

Thu Nov 17, 2022

Midday Peak (12 PM - 1 PM)


All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1012132, Location: 38.853263, -94.398718



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US



1_MO-150 & Ward Road - TMC

Thu Nov 17, 2022

PM Peak (4:45 PM - 5:45 PM) - Overall Peak Hour

All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1012132, Location: 38.853263, -94.398718



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US

Leg Direction	MO 150 Eastbound					MO 150 Westbound					Ward Northbound					Ward Southbound					
Time	L	T	R	U	App	L	T	R	U	App	L	T	R	U	App	L	T	R	U	App	Int
2022-11-17 4:45PM	32	201	34	1	268	35	106	27	0	168	13	39	33	0	85	34	70	30	0	134	655
5:00PM	27	153	32	0	212	36	94	33	0	163	24	38	26	0	88	38	53	45	0	136	599
5:15PM	31	212	42	0	285	33	134	37	0	204	22	49	40	0	111	58	56	24	0	138	738
5:30PM	34	172	44	0	250	17	105	30	0	152	22	35	24	0	81	40	54	30	0	124	607
Total	124	738	152	1	1015	121	439	127	0	687	81	161	123	0	365	170	233	129	0	532	2599
% Approach	12.2%	72.7%	15.0%	0.1%	-	17.6%	63.9%	18.5%	0%	-	22.2%	44.1%	33.7%	0%	-	32.0%	43.8%	24.2%	0%	-	-
% Total	4.8%	28.4%	5.8%	0%	39.1%	4.7%	16.9%	4.9%	0%	26.4%	3.1%	6.2%	4.7%	0%	14.0%	6.5%	9.0%	5.0%	0%	20.5%	-
PHF	0.912	0.870	0.864	0.250	0.890	0.840	0.819	0.858	-	0.842	0.844	0.821	0.769	-	0.822	0.733	0.832	0.717	-	0.964	0.880
Lights	123	730	152	1	1006	120	434	127	0	681	81	161	123	0	365	169	233	129	0	531	2583
% Lights	99.2%	98.9%	100%	100%	99.1%	99.2%	98.9%	100%	0%	99.1%	100%	100%	100%	0%	100%	99.4%	100%	100%	0%	99.8%	99.4%
Articulated Trucks	0	3	0	0	3	1	2	0	0	3	0	0	0	0	0	0	0	0	0	0	6
% Articulated Trucks	0%	0.4%	0%	0%	0.3%	0.8%	0.5%	0%	0%	0.4%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0.2%
Buses and Single-Unit Trucks	1	5	0	0	6	0	3	0	0	3	0	0	0	0	0	1	0	0	0	1	10
% Buses and Single-Unit Trucks	0.8%	0.7%	0%	0%	0.6%	0%	0.7%	0%	0%	0.4%	0%	0%	0%	0%	0%	0.6%	0%	0%	0%	0.2%	0.4%

*L: Left, R: Right, T: Thru, U: U-Turn

1_MO-150 & Ward Road - TMC

Thu Nov 17, 2022

PM Peak (4:45 PM - 5:45 PM) - Overall Peak Hour


All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1012132, Location: 38.853263, -94.398718



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US



2_MO-150 & Arborlake Drive/Stoney Creek Drive - TMC

Thu Nov 17, 2022

Full Length (7 AM-9 AM, 4 PM-6 PM)

All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1012130, Location: 38.853449, -94.404891



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US

Leg Direction	MO 150 Eastbound					MO 150 Westbound					Stoney Creek Northbound					Arborlake Southbound					
Time	L	T	R	U	App	L	T	R	U	App	L	T	R	U	App	L	T	R	U	App	Int
2022-11-17 7:00AM	5	69	1	0	75	9	185	11	0	205	10	4	33	0	47	3	2	12	0	17	344
7:15AM	4	85	2	0	91	11	227	13	0	251	20	5	22	0	47	11	1	23	0	35	424
7:30AM	4	81	1	2	88	13	253	17	0	283	11	5	23	0	39	9	2	29	0	40	450
7:45AM	7	92	0	1	100	8	212	10	0	230	9	2	21	0	32	11	4	15	0	30	392
Hourly Total	20	327	4	3	354	41	877	51	0	969	50	16	99	0	165	34	9	79	0	122	1610
8:00AM	7	98	1	0	106	15	185	10	0	210	12	3	27	0	42	7	0	16	0	23	381
8:15AM	6	69	2	2	79	12	155	10	0	177	11	2	22	0	35	7	2	12	0	21	312
8:30AM	11	75	4	1	91	13	146	13	1	173	12	5	24	0	41	5	4	10	0	19	324
8:45AM	10	99	2	2	113	10	128	9	0	147	27	4	19	0	50	10	0	19	0	29	339
Hourly Total	34	341	9	5	389	50	614	42	1	707	62	14	92	0	168	29	6	57	0	92	1356
4:00PM	12	183	17	0	212	23	99	9	2	133	8	3	14	0	25	11	3	9	0	23	393
4:15PM	16	230	16	2	264	17	90	12	0	119	3	2	22	0	27	15	2	11	0	28	438
4:30PM	15	211	8	0	234	23	95	17	0	135	2	2	23	0	27	10	2	10	0	22	418
4:45PM	14	217	9	1	241	26	109	9	0	144	6	4	27	0	37	17	3	5	0	25	447
Hourly Total	57	841	50	3	951	89	393	47	2	531	19	11	86	0	116	53	10	35	0	98	1696
5:00PM	13	190	8	0	211	28	128	14	0	170	7	5	31	0	43	10	8	12	0	30	454
5:15PM	17	251	13	0	281	40	122	12	0	174	1	3	33	0	37	11	5	19	0	35	527
5:30PM	13	188	6	0	207	34	113	13	0	160	3	3	25	0	31	11	6	13	0	30	428
5:45PM	11	167	9	2	189	35	83	19	0	137	4	2	24	0	30	8	2	14	0	24	380
Hourly Total	54	796	36	2	888	137	446	58	0	641	15	13	113	0	141	40	21	58	0	119	1789
Total	165	2305	99	13	2582	317	2330	198	3	2848	146	54	390	0	590	156	46	229	0	431	6451
% Approach	6.4%	89.3%	3.8%	0.5%	-	11.1%	81.8%	7.0%	0.1%	-	24.7%	9.2%	66.1%	0%	-	36.2%	10.7%	53.1%	0%	-	-
% Total	2.6%	35.7%	1.5%	0.2%	40.0%	4.9%	36.1%	3.1%	0%	44.1%	2.3%	0.8%	6.0%	0%	9.1%	2.4%	0.7%	3.5%	0%	6.7%	-
Lights	157	2250	96	13	2516	316	2264	192	3	2775	142	53	387	0	582	151	41	218	0	410	6283
% Lights	95.2%	97.6%	97.0%	100%	97.4%	99.7%	97.2%	97.0%	100%	97.4%	97.3%	98.1%	99.2%	0%	98.6%	96.8%	89.1%	95.2%	0%	95.1%	97.4%
Articulated Trucks	0	6	0	0	6	0	14	0	0	14	0	0	1	0	1	1	0	2	0	3	24
% Articulated Trucks	0%	0.3%	0%	0%	0.2%	0%	0.6%	0%	0%	0.5%	0%	0%	0.3%	0%	0.2%	0.6%	0%	0.9%	0%	0.7%	0.4%
Buses and Single-Unit Trucks	8	49	3	0	60	1	52	6	0	59	4	1	2	0	7	4	5	9	0	18	144
% Buses and Single-Unit Trucks	4.8%	2.1%	3.0%	0%	2.3%	0.3%	2.2%	3.0%	0%	2.1%	2.7%	1.9%	0.5%	0%	1.2%	2.6%	10.9%	3.9%	0%	4.2%	2.2%

*L: Left, R: Right, T: Thru, U: U-Turn

2_MO-150 & Arborlake Drive/Stoney Creek Drive - TMC

Thu Nov 17, 2022

Full Length (7 AM-9 AM, 4 PM-6 PM)

All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1012130, Location: 38.853449, -94.404891




Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US

[N] Arborlake

Total: 848

In: 431 Out: 417

229
46
156



2_MO-150 & Arborlake Drive/Stoney Creek Drive - TMC

Thu Nov 17, 2022

AM Peak (7:15 AM - 8:15 AM)

All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1012130, Location: 38.853449, -94.404891



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US

Leg Direction	MO 150 Eastbound						MO 150 Westbound						Stoney Creek Northbound						Arborlake Southbound						
Time	L	T	R	U	App		L	T	R	U	App		L	T	R	U	App		L	T	R	U	App		Int
2022-11-17 7:15AM	4	85	2	0	91		11	227	13	0	251		20	5	22	0	47		11	1	23	0	35		424
7:30AM	4	81	1	2	88		13	253	17	0	283		11	5	23	0	39		9	2	29	0	40		450
7:45AM	7	92	0	1	100		8	212	10	0	230		9	2	21	0	32		11	4	15	0	30		392
8:00AM	7	98	1	0	106		15	185	10	0	210		12	3	27	0	42		7	0	16	0	23		381
Total	22	356	4	3	385		47	877	50	0	974		52	15	93	0	160		38	7	83	0	128		1647
% Approach	5.7%	92.5%	1.0%	0.8%	-		4.8%	90.0%	5.1%	0%	-		32.5%	9.4%	58.1%	0%	-		29.7%	5.5%	64.8%	0%	-		-
% Total	1.3%	21.6%	0.2%	0.2%	23.4%		2.9%	53.2%	3.0%	0%	59.1%		3.2%	0.9%	5.6%	0%	9.7%		2.3%	0.4%	5.0%	0%	7.8%		-
PHF	0.786	0.908	0.500	0.375	0.908		0.783	0.867	0.735	-	0.860		0.650	0.750	0.861	-	0.851		0.864	0.438	0.716	-	0.800		0.915
Lights	18	335	4	3	360		47	852	47	0	946		52	15	93	0	160		36	6	78	0	120		1586
% Lights	81.8%	94.1%	100%	100%	93.5%		100%	97.1%	94.0%	0%	97.1%		100%	100%	100%	0%	100%		94.7%	85.7%	94.0%	0%	93.8%		96.3%
Articulated Trucks	0	3	0	0	3		0	5	0	0	5		0	0	0	0	0		1	0	1	0	2		10
% Articulated Trucks	0%	0.8%	0%	0%	0.8%		0%	0.6%	0%	0%	0.5%		0%	0%	0%	0%	0%		2.6%	0%	1.2%	0%	1.6%		0.6%
Buses and Single-Unit Trucks	4	18	0	0	22		0	20	3	0	23		0	0	0	0	0		1	1	4	0	6		51
% Buses and Single-Unit Trucks	18.2%	5.1%	0%	0%	5.7%		0%	2.3%	6.0%	0%	2.4%		0%	0%	0%	0%	0%		2.6%	14.3%	4.8%	0%	4.7%		3.1%

* L: Left, R: Right, T: Thru, U: U-Turn

2_MO-150 & Arborlake Drive/Stoney Creek Drive - TMC
 Thu Nov 17, 2022
 AM Peak (7:15 AM - 8:15 AM)
 All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)
 All Movements
 ID: 1012130, Location: 38.853449, -94.404891

[N] Arborlake

Total: 215
 In: 128 Out: 87

83 7 38

[W] MO 150
 Total: 1400
 In: 385 Out: 1015

356 4

22 3

50 877 47

Out: 487 In: 974
 Total: 1461
 [E] MO 150

Out: 58 In: 160
 Total: 218
 [S] Stoney Creek

52 15 93

2_MO-150 & Arborlake Drive/Stoney Creek Drive - TMC

Thu Nov 17, 2022

PM Peak (4:45 PM - 5:45 PM) - Overall Peak Hour

All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1012130, Location: 38.853449, -94.404891



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US

Leg Direction	MO 150 Eastbound						MO 150 Westbound						Stoney Creek Northbound						Arborlake Southbound						
Time	L	T	R	U	App		L	T	R	U	App		L	T	R	U	App		L	T	R	U	App		Int
2022-11-17 4:45PM	14	217	9	1	241		26	109	9	0	144		6	4	27	0	37		17	3	5	0	25		447
5:00PM	13	190	8	0	211		28	128	14	0	170		7	5	31	0	43		10	8	12	0	30		454
5:15PM	17	251	13	0	281		40	122	12	0	174		1	3	33	0	37		11	5	19	0	35		527
5:30PM	13	188	6	0	207		34	113	13	0	160		3	3	25	0	31		11	6	13	0	30		428
Total	57	846	36	1	940		128	472	48	0	648		17	15	116	0	148		49	22	49	0	120		1856
% Approach	6.1%	90.0%	3.8%	0.1%	-		19.8%	72.8%	7.4%	0%	-		11.5%	10.1%	78.4%	0%	-		40.8%	18.3%	40.8%	0%	-		-
% Total	3.1%	45.6%	1.9%	0.1%	50.6%		6.9%	25.4%	2.6%	0%	34.9%		0.9%	0.8%	6.3%	0%	8.0%		2.6%	1.2%	2.6%	0%	6.5%		-
PHF	0.838	0.843	0.692	0.250	0.836		0.800	0.922	0.857	-	0.931		0.607	0.750	0.879	-	0.860		0.721	0.688	0.645	-	0.857		0.880
Lights	56	838	36	1	931		128	468	48	0	644		17	15	114	0	146		48	22	48	0	118		1839
% Lights	98.2%	99.1%	100%	100%	99.0%		100%	99.2%	100%	0%	99.4%		100%	100%	98.3%	0%	98.6%		98.0%	100%	98.0%	0%	98.3%		99.1%
Articulated Trucks	0	1	0	0	1		0	2	0	0	2		0	0	1	0	1		0	0	0	0	0		4
% Articulated Trucks	0%	0.1%	0%	0%	0.1%		0%	0.4%	0%	0%	0.3%		0%	0%	0.9%	0%	0.7%		0%	0%	0%	0%	0%		0.2%
Buses and Single-Unit Trucks	1	7	0	0	8		0	2	0	0	2		0	0	1	0	1		1	0	1	0	2		13
% Buses and Single-Unit Trucks	1.8%	0.8%	0%	0%	0.9%		0%	0.4%	0%	0%	0.3%		0%	0%	0.9%	0%	0.7%		2.0%	0%	2.0%	0%	1.7%		0.7%

* L: Left, R: Right, T: Thru, U: U-Turn

2_MO-150 & Arborlake Drive/Stoney Creek Drive - TMC

Thu Nov 17, 2022

PM Peak (4:45 PM - 5:45 PM) - Overall Peak Hour

All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1012130, Location: 38.853449, -94.404891



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US

[N] Arborlake

Total: 240

In: 120 Out: 120

49 22 49

[W] MO 150

Total: 1479

Out: 539

In: 940

1
57
846
36

48
472
128

Out: 1011 In: 648


Total: 1659

[E] MO 150

Out: 186 In: 148
Total: 334

[S] Stoney Creek

17 15 116



3_Ward Road & Arborwalk Boulevard - 13 hour ... - TMC

Thu Nov 17, 2022

Full Length (6 AM-7 PM)

All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1033007, Location: 38.856098, -94.398473



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US

Leg Direction	Arborwalk Eastbound				Ward Northbound				Ward Southbound				
Time	L	R	U	App	L	T	U	App	T	R	U	App	Int
2022-11-17 6:00AM	4	1	0	5	0	16	0	16	15	3	0	18	39
6:15AM	8	2	0	10	1	31	0	32	21	4	0	25	67
6:30AM	17	4	0	21	0	53	0	53	26	2	0	28	102
6:45AM	21	7	0	28	2	136	0	138	25	4	0	29	195
Hourly Total	50	14	0	64	3	236	0	239	87	13	0	100	403
7:00AM	27	3	0	30	2	179	0	181	69	4	0	73	284
7:15AM	17	3	0	20	1	114	0	115	92	10	0	102	237
7:30AM	18	8	0	26	6	92	0	98	65	4	0	69	193
7:45AM	16	7	0	23	2	100	0	102	53	7	0	60	185
Hourly Total	78	21	0	99	11	485	0	496	279	25	0	304	899
8:00AM	14	1	0	15	2	96	0	98	51	3	0	54	167
8:15AM	8	4	0	12	5	104	0	109	48	11	0	59	180
8:30AM	13	5	0	18	4	88	0	92	40	7	0	47	157
8:45AM	13	2	0	15	2	95	0	97	53	5	0	58	170
Hourly Total	48	12	0	60	13	383	0	396	192	26	0	218	674
9:00AM	5	4	0	9	2	77	0	79	45	8	0	53	141
9:15AM	5	5	0	10	3	52	0	55	37	12	0	49	114
9:30AM	9	0	0	9	0	63	0	63	43	6	1	50	122
9:45AM	6	1	0	7	1	59	0	60	44	4	0	48	115
Hourly Total	25	10	0	35	6	251	0	257	169	30	1	200	492
10:00AM	11	6	0	17	4	50	0	54	53	4	0	57	128
10:15AM	6	2	0	8	2	51	0	53	48	6	0	54	115
10:30AM	11	6	0	17	0	52	0	52	51	9	0	60	129
10:45AM	7	5	0	12	1	55	0	56	54	5	1	60	128
Hourly Total	35	19	0	54	7	208	0	215	206	24	1	231	500
11:00AM	1	2	0	3	2	56	0	58	31	8	1	40	101
11:15AM	9	5	0	14	4	61	0	65	60	6	2	68	147
11:30AM	7	7	0	14	2	55	0	57	53	7	0	60	131
11:45AM	10	4	0	14	1	45	0	46	54	10	0	64	124
Hourly Total	27	18	0	45	9	217	0	226	198	31	3	232	503
12:00PM	7	6	0	13	5	60	0	65	61	10	0	71	149
12:15PM	12	7	0	19	2	45	0	47	59	13	0	72	138
12:30PM	12	5	0	17	9	46	0	55	61	7	0	68	140
12:45PM	5	3	0	8	2	60	0	62	57	11	0	68	138
Hourly Total	36	21	0	57	18	211	0	229	238	41	0	279	565
1:00PM	8	4	0	12	4	51	0	55	43	3	0	46	113
1:15PM	6	2	0	8	1	58	0	59	62	9	0	71	138
1:30PM	4	4	0	8	6	57	0	63	67	9	0	76	147
1:45PM	8	5	0	13	4	58	1	63	77	12	0	89	165
Hourly Total	26	15	0	41	15	224	1	240	249	33	0	282	563
2:00PM	6	3	0	9	3	72	0	75	52	14	0	66	150
2:15PM	10	4	0	14	4	63	0	67	123	13	0	136	217
2:30PM	10	2	0	12	2	73	0	75	144	14	0	158	245
2:45PM	8	6	0	14	4	81	0	85	97	11	0	108	207
Hourly Total	34	15	0	49	13	289	0	302	416	52	0	468	819
3:00PM	10	0	0	10	6	82	0	88	104	9	0	113	211
3:15PM	9	8	0	17	7	69	0	76	106	14	0	120	213
3:30PM	10	7	0	17	3	82	0	85	117	11	0	128	230
3:45PM	14	4	0	18	6	70	0	76	105	19	0	124	218
Hourly Total	43	19	0	62	22	303	0	325	432	53	0	485	872
4:00PM	11	4	0	15	5	82	0	87	101	18	0	119	221
4:15PM	13	15	0	28	4	78	0	82	80	22	0	102	212
4:30PM	8	5	0	13	1	97	0	98	95	10	0	105	216
4:45PM	19	7	0	26	3	95	0	98	128	16	0	144	268

Leg Direction	Arborwalk Eastbound				Ward Northbound				Ward Southbound				
Time	L	R	U	App	L	T	U	App	T	R	U	App	Int
Hourly Total	51	31	0	82	13	352	0	365	404	66	0	470	917
5:00PM	18	10	0	28	7	91	0	98	126	18	0	144	270
5:15PM	10	12	0	22	4	109	1	114	130	28	0	158	294
5:30PM	8	9	0	17	2	97	1	100	110	20	0	130	247
5:45PM	3	5	0	8	4	106	0	110	104	21	0	125	243
Hourly Total	39	36	0	75	17	403	2	422	470	87	0	557	1054
6:00PM	13	3	0	16	4	77	0	81	91	12	0	103	200
6:15PM	11	5	0	16	4	60	0	64	90	17	0	107	187
6:30PM	9	4	0	13	2	48	0	50	69	20	0	89	152
6:45PM	10	4	0	14	6	60	1	67	58	15	0	73	154
Hourly Total	43	16	0	59	16	245	1	262	308	64	0	372	693
Total	535	247	0	782	163	3807	4	3974	3648	545	5	4198	8954
% Approach	68.4%	31.6%	0%	-	4.1%	95.8%	0.1%	-	86.9%	13.0%	0.1%	-	-
% Total	6.0%	2.8%	0%	8.7%	1.8%	42.5%	0%	44.4%	40.7%	6.1%	0.1%	46.9%	-
Lights	521	242	0	763	154	3750	4	3908	3576	527	5	4108	8779
% Lights	97.4%	98.0%	0%	97.6%	94.5%	98.5%	100%	98.3%	98.0%	96.7%	100%	97.9%	98.0%
Articulated Trucks	2	0	0	2	2	4	0	6	4	1	0	5	13
% Articulated Trucks	0.4%	0%	0%	0.3%	1.2%	0.1%	0%	0.2%	0.1%	0.2%	0%	0.1%	0.1%
Buses and Single-Unit Trucks	12	5	0	17	7	53	0	60	68	17	0	85	162
% Buses and Single-Unit Trucks	2.2%	2.0%	0%	2.2%	4.3%	1.4%	0%	1.5%	1.9%	3.1%	0%	2.0%	1.8%

*L: Left, R: Right, T: Thru, U: U-Turn

3_Ward Road & Arborwalk Boulevard - 13 hour ... - TMC

Thu Nov 17, 2022

Full Length (6 AM-7 PM)

All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1033007, Location: 38.856098, -94.398473



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US

[N] Ward

Total: 8545

In: 4198

Out: 4347

545

3648

5

[W] Arborwalk

Total: 1490

In: 782 Out: 708

535
247



Out: 3899

In: 3974

Total: 7873

[S] Ward

4
163

3807

3_Ward Road & Arborwalk Boulevard - 13 hour ... - TMC

Thu Nov 17, 2022

AM Peak (6:45 AM - 7:45 AM)

All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1033007, Location: 38.856098, -94.398473



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US


Leg Direction	Arborwalk Eastbound				Ward Northbound				Ward Southbound				
Time	L	R	U	App	L	T	U	App	T	R	U	App	Int
2022-11-17 6:45AM	21	7	0	28	2	136	0	138	25	4	0	29	195
7:00AM	27	3	0	30	2	179	0	181	69	4	0	73	284
7:15AM	17	3	0	20	1	114	0	115	92	10	0	102	237
7:30AM	18	8	0	26	6	92	0	98	65	4	0	69	193
Total	83	21	0	104	11	521	0	532	251	22	0	273	909
% Approach	79.8%	20.2%	0%	-	2.1%	97.9%	0%	-	91.9%	8.1%	0%	-	-
% Total	9.1%	2.3%	0%	11.4%	1.2%	57.3%	0%	58.5%	27.6%	2.4%	0%	30.0%	-
PHF	0.769	0.656	-	0.867	0.458	0.728	-	0.735	0.682	0.550	-	0.669	0.800
Lights	83	19	0	102	7	514	0	521	238	17	0	255	878
% Lights	100%	90.5%	0%	98.1%	63.6%	98.7%	0%	97.9%	94.8%	77.3%	0%	93.4%	96.6%
Articulated Trucks	0	0	0	0	1	0	0	1	0	0	0	0	1
% Articulated Trucks	0%	0%	0%	0%	9.1%	0%	0%	0.2%	0%	0%	0%	0%	0.1%
Buses and Single-Unit Trucks	0	2	0	2	3	7	0	10	13	5	0	18	30
% Buses and Single-Unit Trucks	0%	9.5%	0%	1.9%	27.3%	1.3%	0%	1.9%	5.2%	22.7%	0%	6.6%	3.3%

* L: Left, R: Right, T: Thru, U: U-Turn

3_Ward Road & Arborwalk Boulevard - 13 hour ... - TMC
Thu Nov 17, 2022
AM Peak (6:45 AM - 7:45 AM)
All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)
All Movements
ID: 1033007, Location: 38.856098, -94.398473



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US



3_Ward Road & Arborwalk Boulevard - 13 hour ... - TMC

Thu Nov 17, 2022

Midday Peak (12 PM - 1 PM)

All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1033007, Location: 38.856098, -94.398473




Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US

Leg Direction	Arborwalk Eastbound				Ward Northbound				Ward Southbound				
Time	L	R	U	App	L	T	U	App	T	R	U	App	Int
2022-11-17 12:00PM	7	6	0	13	5	60	0	65	61	10	0	71	149
12:15PM	12	7	0	19	2	45	0	47	59	13	0	72	138
12:30PM	12	5	0	17	9	46	0	55	61	7	0	68	140
12:45PM	5	3	0	8	2	60	0	62	57	11	0	68	138
Total	36	21	0	57	18	211	0	229	238	41	0	279	565
% Approach	63.2%	36.8%	0%	-	7.9%	92.1%	0%	-	85.3%	14.7%	0%	-	-
% Total	6.4%	3.7%	0%	10.1%	3.2%	37.3%	0%	40.5%	42.1%	7.3%	0%	49.4%	-
PHF	0.750	0.750	-	0.750	0.500	0.879	-	0.881	0.975	0.788	-	0.969	0.948
Lights	35	21	0	56	16	202	0	218	229	39	0	268	542
% Lights	97.2%	100%	0%	98.2%	88.9%	95.7%	0%	95.2%	96.2%	95.1%	0%	96.1%	95.9%
Articulated Trucks	0	0	0	0	1	1	0	2	1	1	0	2	4
% Articulated Trucks	0%	0%	0%	0%	5.6%	0.5%	0%	0.9%	0.4%	2.4%	0%	0.7%	0.7%
Buses and Single-Unit Trucks	1	0	0	1	1	8	0	9	8	1	0	9	19
% Buses and Single-Unit Trucks	2.8%	0%	0%	1.8%	5.6%	3.8%	0%	3.9%	3.4%	2.4%	0%	3.2%	3.4%

* L: Left, R: Right, T: Thru, U: U-Turn

3_Ward Road & Arborwalk Boulevard - 13 hour ... - TMC
Thu Nov 17, 2022
Midday Peak (12 PM - 1 PM)
All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)
All Movements
ID: 1033007, Location: 38.856098, -94.398473



3_Ward Road & Arborwalk Boulevard - 13 hour ... - TMC
 Thu Nov 17, 2022
 PM Peak (4:45 PM - 5:45 PM) - Overall Peak Hour
 All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)
 All Movements
 ID: 1033007, Location: 38.856098, -94.398473




Provided by: Gewalt Hamilton Associates Inc.
 625 Forest Edge Drive, Vernon Hills, IL, 60061, US

Leg Direction	Arborwalk Eastbound				Ward Northbound				Ward Southbound				
Time	L	R	U	App	L	T	U	App	T	R	U	App	Int
2022-11-17 4:45PM	19	7	0	26	3	95	0	98	128	16	0	144	268
5:00PM	18	10	0	28	7	91	0	98	126	18	0	144	270
5:15PM	10	12	0	22	4	109	1	114	130	28	0	158	294
5:30PM	8	9	0	17	2	97	1	100	110	20	0	130	247
Total	55	38	0	93	16	392	2	410	494	82	0	576	1079
% Approach	59.1%	40.9%	0%	-	3.9%	95.6%	0.5%	-	85.8%	14.2%	0%	-	-
% Total	5.1%	3.5%	0%	8.6%	1.5%	36.3%	0.2%	38.0%	45.8%	7.6%	0%	53.4%	-
PHF	0.724	0.792	-	0.830	0.571	0.899	0.500	0.899	0.950	0.732	-	0.911	0.918
Lights	55	38	0	93	16	391	2	409	492	82	0	574	1076
% Lights	100%	100%	0%	100%	100%	99.7%	100%	99.8%	99.6%	100%	0%	99.7%	99.7%
Articulated Trucks	0	0	0	0	0	0	0	0	0	0	0	0	0
% Articulated Trucks	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
Buses and Single-Unit Trucks	0	0	0	0	0	1	0	1	2	0	0	2	3
% Buses and Single-Unit Trucks	0%	0%	0%	0%	0%	0.3%	0%	0.2%	0.4%	0%	0%	0.3%	0.3%

* L: Left, R: Right, T: Thru, U: U-Turn

3_Ward Road & Arborwalk Boulevard - 13 hour ... - TMC
Thu Nov 17, 2022
PM Peak (4:45 PM - 5:45 PM) - Overall Peak Hour
All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)
All Movements
ID: 1033007, Location: 38.856098, -94.398473



4_Arborwalk Boulevard & Arbor Park Drive - TMC

Thu Nov 17, 2022

Full Length (7 AM-9 AM, 4 PM-6 PM)

All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1012133, Location: 38.855693, -94.401528



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US

Leg Direction	Arbor Park Eastbound				Arborwalk Northbound				Arborwalk Southbound				
Time	L	R	U	App	L	T	U	App	T	R	U	App	Int
2022-11-17 7:00AM	1	3	0	4	0	16	0	16	9	0	0	9	29
7:15AM	3	4	0	7	1	8	0	9	12	0	0	12	28
7:30AM	4	4	0	8	1	9	0	10	15	0	0	15	33
7:45AM	2	3	0	5	1	12	0	13	10	0	0	10	28
Hourly Total	10	14	0	24	3	45	0	48	46	0	0	46	118
8:00AM	0	6	0	6	1	6	0	7	2	2	0	4	17
8:15AM	0	0	0	0	1	8	0	9	9	2	0	11	20
8:30AM	2	1	0	3	1	10	0	11	8	2	0	10	24
8:45AM	1	3	0	4	0	8	0	8	8	2	0	10	22
Hourly Total	3	10	0	13	3	32	0	35	27	8	0	35	83
4:00PM	1	2	0	3	2	9	0	11	13	3	0	16	30
4:15PM	0	3	0	3	1	18	0	19	12	1	0	13	35
4:30PM	1	0	0	1	2	13	0	15	9	2	0	11	27
4:45PM	2	2	0	4	6	15	0	21	7	0	0	7	32
Hourly Total	4	7	0	11	11	55	0	66	41	6	0	47	124
5:00PM	3	0	0	3	1	18	0	19	12	1	0	13	35
5:15PM	2	0	0	2	1	20	0	21	14	5	0	19	42
5:30PM	1	1	0	2	1	8	0	9	13	2	0	15	26
5:45PM	0	2	0	2	1	7	0	8	20	2	0	22	32
Hourly Total	6	3	0	9	4	53	0	57	59	10	0	69	135
Total	23	34	0	57	21	185	0	206	173	24	0	197	460
% Approach	40.4%	59.6%	0%	-	10.2%	89.8%	0%	-	87.8%	12.2%	0%	-	-
% Total	5.0%	7.4%	0%	12.4%	4.6%	40.2%	0%	44.8%	37.6%	5.2%	0%	42.8%	-
Lights	23	34	0	57	18	182	0	200	163	24	0	187	444
% Lights	100%	100%	0%	100%	85.7%	98.4%	0%	97.1%	94.2%	100%	0%	94.9%	96.5%
Articulated Trucks	0	0	0	0	0	0	0	0	0	0	0	0	0
% Articulated Trucks	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
Buses and Single-Unit Trucks	0	0	0	0	3	3	0	6	10	0	0	10	16
% Buses and Single-Unit Trucks	0%	0%	0%	0%	14.3%	1.6%	0%	2.9%	5.8%	0%	0%	5.1%	3.5%

*L: Left, R: Right, T: Thru, U: U-Turn

4_Arborwalk Boulevard & Arbor Park Drive - TMC

Thu Nov 17, 2022

Full Length (7 AM-9 AM, 4 PM-6 PM)


All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1012133, Location: 38.855693, -94.401528



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US



4_Arborwalk Boulevard & Arbor Park Drive - TMC

Thu Nov 17, 2022

AM Peak (7 AM - 8 AM)

All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1012133, Location: 38.855693, -94.401528



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US

Leg Direction	Arbor Park Eastbound				Arborwalk Northbound				Arborwalk Southbound				
Time	L	R	U	App	L	T	U	App	T	R	U	App	Int
2022-11-17 7:00AM	1	3	0	4	0	16	0	16	9	0	0	9	29
7:15AM	3	4	0	7	1	8	0	9	12	0	0	12	28
7:30AM	4	4	0	8	1	9	0	10	15	0	0	15	33
7:45AM	2	3	0	5	1	12	0	13	10	0	0	10	28
Total	10	14	0	24	3	45	0	48	46	0	0	46	118
% Approach	41.7%	58.3%	0%	-	6.3%	93.8%	0%	-	100%	0%	0%	-	-
% Total	8.5%	11.9%	0%	20.3%	2.5%	38.1%	0%	40.7%	39.0%	0%	0%	39.0%	-
PHF	0.625	0.875	-	0.750	0.750	0.703	-	0.750	0.767	-	-	0.767	0.894
Lights	10	14	0	24	2	43	0	45	40	0	0	40	109
% Lights	100%	100%	0%	100%	66.7%	95.6%	0%	93.8%	87.0%	0%	0%	87.0%	92.4%
Articulated Trucks	0	0	0	0	0	0	0	0	0	0	0	0	0
% Articulated Trucks	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
Buses and Single-Unit Trucks	0	0	0	0	1	2	0	3	6	0	0	6	9
% Buses and Single-Unit Trucks	0%	0%	0%	0%	33.3%	4.4%	0%	6.3%	13.0%	0%	0%	13.0%	7.6%

* L: Left, R: Right, T: Thru, U: U-Turn

4_Arborwalk Boulevard & Arbor Park Drive - TMC

Thu Nov 17, 2022

AM Peak (7 AM - 8 AM)


All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1012133, Location: 38.855693, -94.401528



Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US



4_Arborwalk Boulevard & Arbor Park Drive - TMC

Thu Nov 17, 2022

PM Peak (4:30 PM - 5:30 PM) - Overall Peak Hour

All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)

All Movements

ID: 1012133, Location: 38.855693, -94.401528




Provided by: Gewalt Hamilton Associates Inc.
625 Forest Edge Drive, Vernon Hills, IL, 60061, US

Leg Direction	Arbor Park Eastbound				Arborwalk Northbound				Arborwalk Southbound				
Time	L	R	U	App	L	T	U	App	T	R	U	App	Int
2022-11-17 4:30PM	1	0	0	1	2	13	0	15	9	2	0	11	27
4:45PM	2	2	0	4	6	15	0	21	7	0	0	7	32
5:00PM	3	0	0	3	1	18	0	19	12	1	0	13	35
5:15PM	2	0	0	2	1	20	0	21	14	5	0	19	42
Total	8	2	0	10	10	66	0	76	42	8	0	50	136
% Approach	80.0%	20.0%	0%	-	13.2%	86.8%	0%	-	84.0%	16.0%	0%	-	-
% Total	5.9%	1.5%	0%	7.4%	7.4%	48.5%	0%	55.9%	30.9%	5.9%	0%	36.8%	-
PHF	0.667	0.250	-	0.625	0.417	0.825	-	0.905	0.750	0.400	-	0.658	0.810
Lights	8	2	0	10	10	66	0	76	42	8	0	50	136
% Lights	100%	100%	0%	100%	100%	100%	0%	100%	100%	100%	0%	100%	100%
Articulated Trucks	0	0	0	0	0	0	0	0	0	0	0	0	0
% Articulated Trucks	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
Buses and Single-Unit Trucks	0	0	0	0	0	0	0	0	0	0	0	0	0
% Buses and Single-Unit Trucks	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%

* L: Left, R: Right, T: Thru, U: U-Turn

4_Arborwalk Boulevard & Arbor Park Drive - TMC
Thu Nov 17, 2022
PM Peak (4:30 PM - 5:30 PM) - Overall Peak Hour
All Classes (Lights, Articulated Trucks, Buses and Single-Unit Trucks)
All Movements
ID: 1012133, Location: 38.855693, -94.401528



Appendix C: Site Plan



Drawing name: K:\K4C_LIE\208277000_150 & Ward Multi-Family\2 Design\CAD\Plan\SheetC2 - SITE PLAN.dwg C200 SITE PLAN Dec 03, 2024 11:56am by: logan green
This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.

PARKING SUMMARY




SURFACE STALLS PROVIDED	455
GARAGE STALLS PROVIDED	20
TOTAL STALLS PROVIDED	475
UNITS PROVIDED	275
SURFACE PARKING RATIO (STALLS/UNIT)	1.65
GARAGE PARKING RATIO (STALLS/UNIT)	0.07
TOTAL PARKING RATIO (STALLS/UNIT)	1.73

SITE PLAN LEGEND

	HEAVY DUTY CONCRETE PAVEMENT
	STANDARD DUTY ASPHALT PAVEMENT
	CONCRETE SIDEWALK
	BUILDING
	CG-1 CURB AND GUTTER

SITE PLAN NOTES

- ALL SIGNS MUST COMPLY WITH THE SIGN REQUIREMENTS AS OUTLINE IN THE SIGN SECTION OF THE UNIFIED DEVELOPMENT ORDINANCE.
- ALL FIRE LANES SHALL BE MARKED AND POSTED WHERE REQUIRED BY THE FIRE CODE OFFICIAL.



Kimley»Horn

© 2024 KIMLEY-HORN AND ASSOCIATES, INC.
1501 W. 15TH AVENUE, SUITE 150
KANSAS CITY, MO 64105
PHONE: 816.603.0580
FAX: 816.603.0581
MO. CERTIFICATE OF AUTHORITY #001912
EXPIRES: 12/31/24

SCALE: AS NOTED
DESIGNED BY: LLG
DRAWN BY: LLG
CHECKED BY: PUJ

PRELIMINARY
NOT FOR
CONSTRUCTION



SITE PLAN

150 & WARD
MULTIFAMILY
DEVELOPMENT
150 HIGHWAY & SW WARD ROAD
LEE'S SUMMIT, MISSOURI 64082

ORIGINAL ISSUE:
12/17/2024
KHA PROJECT NO.
268277000
SHEET NUMBER

C200

Appendix D: ITE Trip Generation Manual Sheets



Land Use: 220

Multifamily Housing (Low-Rise)

Description

Low-rise multifamily housing includes apartments, townhouses, and condominiums located within the same building with at least three other dwelling units and that have two or three floors (levels). Various configurations fit this description, including walkup apartment, mansion apartment, and stacked townhouse.

- A walkup apartment typically is two or three floors in height with dwelling units that are accessed by a single or multiple entrances with stairways and hallways.
- A mansion apartment is a single structure that contains several apartments within what appears to be a single-family dwelling unit.
- A fourplex is a single two-story structure with two matching dwelling units on the ground and second floors. Access to the individual units is typically internal to the structure and provided through a central entry and stairway.
- A stacked townhouse is designed to match the external appearance of a townhouse. But, unlike a townhouse dwelling unit that only shares walls with an adjoining unit, the stacked townhouse units share both floors and walls. Access to the individual units is typically internal to the structure and provided through a central entry and stairway.

Multifamily housing (mid-rise) (Land Use 221), multifamily housing (high-rise) (Land Use 222), affordable housing (Land Use 223), and off-campus student apartment (low-rise) (Land Use 225) are related land uses.

Land Use Subcategory

Data are presented for two subcategories for this land use: (1) not close to rail transit and (2) close to rail transit. A site is considered close to rail transit if the walking distance between the residential site entrance and the closest rail transit station entrance is ½ mile or less.

Additional Data

For the three sites for which both the number of residents and the number of occupied dwelling units were available, there were an average of 2.72 residents per occupied dwelling unit.

For the two sites for which the numbers of both total dwelling units and occupied dwelling units were available, an average of 96.2 percent of the total dwelling units were occupied.

The technical appendices provide supporting information on time-of-day distributions for this land use. The appendices can be accessed through either the ITETripGen web app or the trip

generation resource page on the ITE website (<https://www.ite.org/technical-resources/topics/trip-and-parking-generation/>).

For the three sites for which data were provided for both occupied dwelling units and residents, there was an average of 2.72 residents per occupied dwelling unit.

It is expected that the number of bedrooms and number of residents are likely correlated to the trips generated by a residential site. To assist in future analysis, trip generation studies of all multifamily housing should attempt to obtain information on occupancy rate and on the mix of residential unit sizes (i.e., number of units by number of bedrooms at the site complex).

The sites were surveyed in the 1980s, the 1990s, the 2000s, the 2010s, and the 2020s in British Columbia (CAN), California, Delaware, Florida, Georgia, Illinois, Indiana, Maine, Maryland, Massachusetts, Minnesota, New Jersey, Ontario (CAN), Oregon, Pennsylvania, South Carolina, South Dakota, Tennessee, Texas, Utah, and Washington.

Source Numbers

188, 204, 237, 300, 305, 306, 320, 321, 357, 390, 412, 525, 530, 579, 583, 638, 864, 866, 896, 901, 903, 904, 936, 939, 944, 946, 947, 948, 963, 964, 966, 967, 1012, 1013, 1014, 1036, 1047, 1056, 1071, 1076

Multifamily Housing (Low-Rise) Not Close to Rail Transit (220)


Vehicle Trip Ends vs: Dwelling Units
On a: Weekday

Setting/Location: General Urban/Suburban
Number of Studies: 22
Avg. Num. of Dwelling Units: 229
Directional Distribution: 50% entering, 50% exiting

Vehicle Trip Generation per Dwelling Unit

Average Rate	Range of Rates	Standard Deviation
6.74	2.46 - 12.50	1.79

Data Plot and Equation



Multifamily Housing (Low-Rise) Not Close to Rail Transit (220)

Vehicle Trip Ends vs: Dwelling Units

On a: Weekday,
Peak Hour of Adjacent Street Traffic,
One Hour Between 7 and 9 a.m.

Setting/Location: General Urban/Suburban

Number of Studies: 49


Avg. Num. of Dwelling Units: 249

Directional Distribution: 24% entering, 76% exiting

Vehicle Trip Generation per Dwelling Unit

Average Rate	Range of Rates	Standard Deviation
0.40	0.13 - 0.73	0.12

Data Plot and Equation



Multifamily Housing (Low-Rise) Not Close to Rail Transit (220)

Vehicle Trip Ends vs: Dwelling Units

On a: Weekday,
Peak Hour of Adjacent Street Traffic,
One Hour Between 4 and 6 p.m.

Setting/Location: General Urban/Suburban

Number of Studies: 59


Avg. Num. of Dwelling Units: 241

Directional Distribution: 63% entering, 37% exiting

Vehicle Trip Generation per Dwelling Unit

Average Rate	Range of Rates	Standard Deviation
0.51	0.08 - 1.04	0.15

Data Plot and Equation



Appendix E: Capacity Analysis Reports



Queues

Existing (Year 2024) Traffic Volumes

1: Ward Road & MO-150

AM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	137	355	34	57	774	161	191	252	115	127	78	134
v/c Ratio	0.47	0.17	0.04	0.28	0.40	0.17	0.56	0.61	0.40	0.48	0.22	0.48
Control Delay (s/veh)	63.9	10.2	0.2	56.7	16.5	2.9	57.5	56.4	12.6	57.9	50.0	14.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay (s/veh)	63.9	10.2	0.2	56.7	16.5	2.9	57.5	56.4	12.6	57.9	50.0	14.0
Queue Length 50th (ft)	57	49	0	22	167	0	73	99	0	48	30	0
Queue Length 95th (ft)	82	80	0	43	259	36	109	137	53	79	53	57
Internal Link Dist (ft)	1672				696				640			
Turn Bay Length (ft)	210		205	220		220	170		135	260		120
Base Capacity (vph)	359	2093	923	234	1959	955	472	752	426	358	663	402
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.38	0.17	0.04	0.24	0.40	0.17	0.40	0.34	0.27	0.35	0.12	0.33
Intersection Summary												

HCM 7th Signalized Intersection Summary

1: Ward Road & MO-150

Existing (Year 2024) Traffic Volumes

AM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	126	327	31	52	712	148	176	232	106	117	72	123
Future Volume (veh/h)	126	327	31	52	712	148	176	232	106	117	72	123
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Lane Width Adj.	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1870	1841	1752	1781	1841	1856	1870	1870	1870	1752	1870	1856
Adj Flow Rate, veh/h	137	355	34	57	774	161	191	252	115	127	78	134
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	4	10	8	4	3	2	2	2	10	2	3
Cap, veh/h	193	2225	945	117	2154	969	254	435	194	181	372	165
Arrive On Green	0.11	1.00	1.00	0.04	0.62	0.62	0.07	0.12	0.12	0.06	0.10	0.10
Sat Flow, veh/h	3456	3497	1485	3291	3497	1572	3456	3554	1585	3237	3554	1572
Grp Volume(v), veh/h	137	355	34	57	774	161	191	252	115	127	78	134
Grp Sat Flow(s),veh/h/ln	1728	1749	1485	1646	1749	1572	1728	1777	1585	1618	1777	1572
Q Serve(g_s), s	4.6	0.0	0.0	2.0	13.1	5.3	6.5	8.0	8.2	4.6	2.4	10.0
Cycle Q Clear(g_c), s	4.6	0.0	0.0	2.0	13.1	5.3	6.5	8.0	8.2	4.6	2.4	10.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	193	2225	945	117	2154	969	254	435	194	181	372	165
V/C Ratio(X)	0.71	0.16	0.04	0.49	0.36	0.17	0.75	0.58	0.59	0.70	0.21	0.81
Avail Cap(c_a), veh/h	360	2225	945	233	2154	969	475	755	337	364	666	295
HCM Platoon Ratio	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	0.98	0.98	0.98	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	52.4	0.0	0.0	56.8	11.4	9.9	54.5	49.7	49.8	55.7	49.2	52.6
Incr Delay (d2), s/veh	4.7	0.2	0.1	3.1	0.5	0.4	4.4	1.2	2.9	4.9	0.3	9.3
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	2.0	0.0	0.0	0.9	4.7	1.7	2.9	3.6	3.3	2.0	1.1	4.3
Unsig. Movement Delay, s/veh												
LnGrp Delay(d), s/veh	57.1	0.2	0.1	60.0	11.8	10.2	58.9	51.0	52.7	60.6	49.5	61.9
LnGrp LOS	E	A	A	E	B	B	E	D	D	E	D	E
Approach Vol, veh/h	526			992			558			339		
Approach Delay, s/veh	15.0			14.3			54.0			58.5		
Approach LOS	B			B			D			E		
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	11.2	19.2	8.8	80.9	13.3	17.1	11.2	78.4				
Change Period (Y+Rc), s	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5				
Max Green Setting (Gmax), s	13.5	25.5	8.5	54.5	16.5	22.5	12.5	50.5				
Max Q Clear Time (g_c+I1), s	6.6	10.2	4.0	2.0	8.5	12.0	6.6	15.1				
Green Ext Time (p_c), s	0.2	1.5	0.0	2.4	0.3	0.6	0.2	6.1				
Intersection Summary												
HCM 7th Control Delay, s/veh	29.9											
HCM 7th LOS	C											

Queues

Existing (Year 2024) Traffic Volumes

2: Stoney Creek Drive/Arborlake Drive & MO-150

AM Peak Hour

											
Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	23	374	47	991	58	57	18	112	38	10	89
v/c Ratio	0.06	0.16	0.06	0.39	0.05	0.29	0.11	0.47	0.22	0.10	0.50
Control Delay (s/veh)	5.0	7.7	3.7	7.4	0.8	45.2	52.2	16.1	43.7	54.6	19.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay (s/veh)	5.0	7.7	3.7	7.4	0.8	45.2	52.2	16.1	43.7	54.6	19.4
Queue Length 50th (ft)	4	51	6	163	0	39	14	0	26	8	0
Queue Length 95th (ft)	13	87	14	204	4	73	36	55	54	25	46
Internal Link Dist (ft)	1287		1672		122		245				
Turn Bay Length (ft)	200	215		190		75	100		210	200	
Base Capacity (vph)	378	2377	780	2520	1122	206	364	400	181	312	362
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.06	0.16	0.06	0.39	0.05	0.28	0.05	0.28	0.21	0.03	0.25
Intersection Summary											

HCM 7th Signalized Intersection Summary

2: Stoney Creek Drive/Arborlake Drive & MO-150

Existing (Year 2024) Traffic Volumes

AM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	21	340	4	43	912	53	52	17	103	35	9	82
Future Volume (veh/h)	21	340	4	43	912	53	52	17	103	35	9	82
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Lane Width Adj.	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1633	1811	1870	1870	1856	1811	1870	1870	1870	1811	1693	1811
Adj Flow Rate, veh/h	23	370	4	47	991	0	57	18	112	38	10	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	18	6	2	2	3	6	2	2	2	6	14	6
Cap, veh/h	441	2436	26	787	2500		233	166	140	208	134	
Arrive On Green	0.02	0.70	0.70	0.07	1.00	0.00	0.04	0.09	0.09	0.03	0.08	0.00
Sat Flow, veh/h	1555	3487	38	1781	3526	1535	1781	1870	1585	1725	1693	1535
Grp Volume(v), veh/h	23	182	192	47	991	0	57	18	112	38	10	0
Grp Sat Flow(s),veh/h/ln	1555	1721	1804	1781	1763	1535	1781	1870	1585	1725	1693	1535
Q Serve(g_s), s	0.5	4.3	4.3	0.9	0.0	0.0	3.5	1.1	8.3	2.4	0.7	0.0
Cycle Q Clear(g_c), s	0.5	4.3	4.3	0.9	0.0	0.0	3.5	1.1	8.3	2.4	0.7	0.0
Prop In Lane	1.00		0.02	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	441	1202	1260	787	2500		233	166	140	208	134	
V/C Ratio(X)	0.05	0.15	0.15	0.06	0.40		0.24	0.11	0.80	0.18	0.07	
Avail Cap(c_a), veh/h	504	1202	1260	840	2500		290	366	310	265	317	
HCM Platoon Ratio	1.00	1.00	1.00	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	0.90	0.90	0.00	1.00	1.00	1.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	4.7	6.1	6.1	4.4	0.0	0.0	48.2	50.3	53.6	48.7	51.2	0.0
Incr Delay (d2), s/veh	0.0	0.3	0.3	0.0	0.4	0.0	0.5	0.3	9.9	0.4	0.2	0.0
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.1	1.4	1.5	0.3	0.1	0.0	1.6	0.5	3.6	1.1	0.3	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d), s/veh	4.8	6.4	6.4	4.4	0.4	0.0	48.7	50.6	63.5	49.1	51.4	0.0
LnGrp LOS	A	A	A	A	A		D	D	E	D	D	
Approach Vol, veh/h	397			1038			187			48		
Approach Delay, s/veh	6.3			0.6			57.8			49.6		
Approach LOS	A			A			E			D		
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	8.1	15.1	8.5	88.3	9.2	14.0	7.2	89.6				
Change Period (Y+Rc), s	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5				
Max Green Setting (Gmax), s	7.5	23.5	7.5	63.5	8.5	22.5	7.5	63.5				
Max Q Clear Time (g_c+I1), s	4.4	10.3	2.9	6.3	5.5	2.7	2.5	2.0				
Green Ext Time (p_c), s	0.0	0.3	0.0	2.1	0.0	0.0	0.0	8.0				

Intersection Summary

HCM 7th Control Delay, s/veh	9.8
HCM 7th LOS	A

Notes

Unsignalized Delay for [WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

HCM 7th TWSC
3: Ward Road & Arborwalk Boulevard

Existing (Year 2024) Traffic Volumes
AM Peak Hour

Intersection							
Int Delay, s/veh	1.7						
Movement	EBL	EBR	NBL	NBT	SBT	SBR	
Lane Configurations							
Traffic Vol, veh/h	81	22	11	505	290	26	
Future Vol, veh/h	81	22	11	505	290	26	
Conflicting Peds, #/hr	0	0	0	0	0	0	
Sign Control	Stop	Stop	Free	Free	Free	Free	
RT Channelized	-	None	-	None	-	None	
Storage Length	200	-	250	-	-	150	
Veh in Median Storage, #	0	-	-	0	0	-	
Grade, %	0	-	-	0	0	-	
Peak Hour Factor	92	92	92	92	92	92	
Heavy Vehicles, %	2	14	27	2	5	16	
Mvmt Flow	88	24	12	549	315	28	
Major/Minor	Minor2		Major1		Major2		
Conflicting Flow All	614	158	343	0	-	0	
Stage 1	315	-	-	-	-	-	
Stage 2	298	-	-	-	-	-	
Critical Hdwy	6.84	7.18	4.64	-	-	-	
Critical Hdwy Stg 1	5.84	-	-	-	-	-	
Critical Hdwy Stg 2	5.84	-	-	-	-	-	
Follow-up Hdwy	3.52	3.44	2.47	-	-	-	
Pot Cap-1 Maneuver	424	823	1051	-	-	-	
Stage 1	713	-	-	-	-	-	
Stage 2	727	-	-	-	-	-	
Platoon blocked, %				-	-	-	
Mov Cap-1 Maneuver	419	823	1051	-	-	-	
Mov Cap-2 Maneuver	419	-	-	-	-	-	
Stage 1	705	-	-	-	-	-	
Stage 2	727	-	-	-	-	-	
Approach	EB		NB		SB		
HCM Control Delay, s/v	14.5		0.18		0		
HCM LOS	B						
Minor Lane/Major Mvmt	NBL		NBT	EBLn1	EBLn2	SBT	SBR
Capacity (veh/h)	1051		-	419	823	-	-
HCM Lane V/C Ratio	0.011		-	0.21	0.029	-	-
HCM Control Delay (s/veh)	8.5		-	15.9	9.5	-	-
HCM Lane LOS	A		-	C	A	-	-
HCM 95th %tile Q(veh)	0		-	0.8	0.1	-	-

LANE SUMMARY

 **Site: 4 [Arborwalk Boulevard & Arborway Drive (Site Folder: General)]**

AM Peak Hour
Site Category: Existing Conditions
Roundabout

Lane Use and Performance													
	DEMAND FLOWS		Cap.	Deg. Satn	Lane Util.	Aver. Delay	Level of Service	95% BACK OF QUEUE		Lane Config	Lane Length	Cap. Adj.	Prob. Block.
	[Total veh/h	HV] %						[Veh	Dist] ft				
South: Access B													
Lane 1 ^d	3	2.0	1147	0.003	100	2.1	LOS A	0.0	0.3	Full	1600	0.0	0.0
Approach	3	2.0		0.003		2.1	LOS A	0.0	0.3				
East: Arborwalk Boulevard													
Lane 1 ^d	41	2.0	1280	0.032	100	0.2	LOS A	0.1	3.4	Full	1600	0.0	0.0
Approach	41	2.0		0.032		0.2	LOS A	0.1	3.4				
North: Arborway Drive													
Lane 1 ^d	138	2.0	1335	0.103	100	2.7	LOS A	0.5	12.0	Full	1600	0.0	0.0
Approach	138	2.0		0.103		2.7	LOS A	0.5	12.0				
West: Arborwalk Boulevard													
Lane 1 ^d	63	2.0	1221	0.052	100	0.4	LOS A	0.2	5.6	Full	1600	0.0	0.0
Approach	63	2.0		0.052		0.4	LOS A	0.2	5.6				
Intersection	246	2.0		0.103		1.7	LOS A	0.5	12.0				

Site Level of Service (LOS) Method: Delay & v/c (HCM 6). Site LOS Method is specified in the Parameter Settings dialog (Site tab).
Roundabout LOS Method: Same as Sign Control.

Lane LOS values are based on average delay and v/c ratio (degree of saturation) per lane.

LOS F will result if v/c > 1 irrespective of lane delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all lanes (v/c not used as specified in HCM 6).

Roundabout Capacity Model: US HCM 6.

Delay Model: SIDRA Standard (Geometric Delay is included).

Queue Model: HCM Queue Formula.

Gap-Acceptance Capacity: Traditional M1.

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

^d Dominant lane on roundabout approach

Approach Lane Flows (veh/h)											
South: Access B											
Mov.	L2	T1	R2	Total	%HV						
From S						Cap.	Deg.	Lane	Prob.	Ov.	
To Exit:	W	N	E			veh/h	satn	Util.	SL Ov.	Lane	No.
							v/c	%	%	No.	
Lane 1	1	1	1	3	2.0	1147	0.003	100	NA	NA	
Approach	1	1	1	3	2.0		0.003				
East: Arborwalk Boulevard											
Mov.	L2	T1	R2	Total	%HV						
From E						Cap.	Deg.	Lane	Prob.	Ov.	
To Exit:	S	W	N			veh/h	satn	Util.	SL Ov.	Lane	No.
							v/c	%	%	No.	
Lane 1	1	11	29	41	2.0	1280	0.032	100	NA	NA	
Approach	1	11	29	41	2.0		0.032				
North: Arborway Drive											
Mov.	L2	T1	R2	Total	%HV						
From N						Cap.	Deg.	Lane	Prob.	Ov.	
							satn	Util.	SL Ov.	Lane	No.

To Exit:	E	S	W			veh/h	v/c	%	%	No.
Lane 1	97	1	40	138	2.0	1335	0.103	100	NA	NA
Approach	97	1	40	138	2.0		0.103			
West: Arborwalk Boulevard										
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL Ov.	Ov. Lane No.
From W To Exit:	N	E	S			Cap. veh/h	v/c	%	%	No.
Lane 1	51	11	1	63	2.0	1221	0.052	100	NA	NA
Approach	51	11	1	63	2.0		0.052			
Total %HV Deg. Satn (v/c)										
Intersection	246	2.0					0.103			

Lane flow rates given in this report are based on the arrival flow rates subject to upstream capacity constraint where applicable.

Merge Analysis												
	Exit Lane Number	Short Lane Length ft	Percent Opng in Lane %	Opposing Flow Rate veh/h	Critical Gap sec	Follow-up Headway sec	Lane Flow Rate veh/h	Capacity veh/h	Deg. Satn v/c	Min. Delay sec	Merge Delay sec	
South Exit: Access B Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.
East Exit: Arborwalk Boulevard Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.
North Exit: Arborway Drive Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.
West Exit: Arborwalk Boulevard Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.

HCM 7th TWSC
5: Arborwalk Boulevard & Arbor Park Drive

Existing (Year 2024) Traffic Volumes
AM Peak Hour

Intersection						
Int Delay, s/veh	2					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W			4	4	
Traffic Vol, veh/h	10	15	3	47	48	0
Future Vol, veh/h	10	15	3	47	48	0
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	89	89	89	89	89	89
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	11	17	3	53	54	0
Major/Minor	Minor2	Major1		Major2		
Conflicting Flow All	113	54	54	0	-	0
Stage 1	54	-	-	-	-	-
Stage 2	60	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	883	1013	1551	-	-	-
Stage 1	969	-	-	-	-	-
Stage 2	963	-	-	-	-	-
Platoon blocked, %				-	-	-
Mov Cap-1 Maneuver	881	1013	1551	-	-	-
Mov Cap-2 Maneuver	881	-	-	-	-	-
Stage 1	966	-	-	-	-	-
Stage 2	963	-	-	-	-	-
Approach	EB	NB		SB		
HCM Control Delay, s/v	8.88	0.44		0		
HCM LOS	A					
Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR	
Capacity (veh/h)	108	-	956	-	-	
HCM Lane V/C Ratio	0.002	-	0.029	-	-	
HCM Control Delay (s/veh)	7.3	0	8.9	-	-	
HCM Lane LOS	A	A	A	-	-	
HCM 95th %tile Q(veh)	0	-	0.1	-	-	

Queues

Existing (Year 2024) Traffic Volumes

1: Ward Road & MO-150

PM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	145	863	178	142	513	148	94	189	144	199	272	151
v/c Ratio	0.49	0.45	0.20	0.50	0.26	0.16	0.38	0.55	0.51	0.59	0.58	0.45
Control Delay (s/veh)	64.6	11.8	1.0	57.8	15.2	3.0	57.1	57.3	14.4	58.0	53.6	11.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay (s/veh)	64.6	11.8	1.0	57.8	15.2	3.0	57.1	57.3	14.4	58.0	53.6	11.3
Queue Length 50th (ft)	61	105	0	55	103	0	36	74	0	76	105	0
Queue Length 95th (ft)	92	136	9	85	162	34	62	109	58	111	143	56
Internal Link Dist (ft)	1672				696				640			
Turn Bay Length (ft)	210		205	220		220	170		135	260		120
Base Capacity (vph)	362	1935	897	343	1940	941	280	634	401	437	840	487
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.40	0.45	0.20	0.41	0.26	0.16	0.34	0.30	0.36	0.46	0.32	0.31
Intersection Summary												

HCM 7th Signalized Intersection Summary

1: Ward Road & MO-150

Existing (Year 2024) Traffic Volumes

PM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	129	768	158	126	457	132	84	168	128	177	242	134
Future Volume (veh/h)	129	768	158	126	457	132	84	168	128	177	242	134
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Lane Width Adj.	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1870	1841	1752	1781	1841	1856	1870	1870	1870	1752	1870	1856
Adj Flow Rate, veh/h	145	863	178	142	513	148	94	189	144	199	272	151
Peak Hour Factor	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89
Percent Heavy Veh, %	2	4	10	8	4	3	2	2	2	10	2	3
Cap, veh/h	201	2088	886	197	2094	941	146	403	180	258	537	237
Arrive On Green	0.12	1.00	1.00	0.06	0.60	0.60	0.04	0.11	0.11	0.08	0.15	0.15
Sat Flow, veh/h	3456	3497	1485	3291	3497	1572	3456	3554	1585	3237	3554	1572
Grp Volume(v), veh/h	145	863	178	142	513	148	94	189	144	199	272	151
Grp Sat Flow(s),veh/h/ln	1728	1749	1485	1646	1749	1572	1728	1777	1585	1618	1777	1572
Q Serve(g_s), s	4.9	0.0	0.0	5.1	8.3	5.0	3.2	6.0	10.6	7.2	8.4	10.8
Cycle Q Clear(g_c), s	4.9	0.0	0.0	5.1	8.3	5.0	3.2	6.0	10.6	7.2	8.4	10.8
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	201	2088	886	197	2094	941	146	403	180	258	537	237
V/C Ratio(X)	0.72	0.41	0.20	0.72	0.25	0.16	0.65	0.47	0.80	0.77	0.51	0.64
Avail Cap(c_a), veh/h	360	2088	886	343	2094	941	274	637	284	445	844	373
HCM Platoon Ratio	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	0.89	0.89	0.89	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	52.1	0.0	0.0	55.4	11.3	10.7	56.6	49.8	51.9	54.1	46.8	47.8
Incr Delay (d2), s/veh	4.3	0.5	0.5	4.9	0.3	0.4	4.7	0.8	8.4	4.9	0.7	2.8
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	2.1	0.2	0.1	2.2	3.0	1.7	1.5	2.6	4.5	3.1	3.7	4.3
Unsig. Movement Delay, s/veh												
LnGrp Delay(d), s/veh	56.4	0.5	0.5	60.3	11.6	11.0	61.3	50.7	60.2	59.0	47.6	50.7
LnGrp LOS	E	A	A	E	B	B	E	D	E	E	D	D
Approach Vol, veh/h	1186			803			427			622		
Approach Delay, s/veh	7.4			20.1			56.2			52.0		
Approach LOS	A			C			E			D		
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	14.1	18.1	11.7	76.1	9.6	22.6	11.5	76.3				
Change Period (Y+Rc), s	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5				
Max Green Setting (Gmax), s	16.5	21.5	12.5	51.5	9.5	28.5	12.5	51.5				
Max Q Clear Time (g_c+I1), s	9.2	12.6	7.1	2.0	5.2	12.8	6.9	10.3				
Green Ext Time (p_c), s	0.3	1.0	0.2	7.4	0.1	1.8	0.2	3.9				
Intersection Summary												
HCM 7th Control Delay, s/veh	26.7											
HCM 7th LOS	C											

Queues

Existing (Year 2024) Traffic Volumes

2: Stoney Creek Drive/Arborlake Drive & MO-150

PM Peak Hour

											
Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	66	1031	149	552	56	20	18	136	57	26	57
v/c Ratio	0.10	0.45	0.36	0.22	0.05	0.12	0.15	0.60	0.28	0.12	0.19
Control Delay (s/veh)	5.2	12.6	10.7	7.5	0.7	40.8	54.4	20.0	44.6	48.5	1.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay (s/veh)	5.2	12.6	10.7	7.5	0.7	40.8	54.4	20.0	44.6	48.5	1.4
Queue Length 50th (ft)	11	196	22	84	0	13	14	0	39	17	0
Queue Length 95th (ft)	29	314	86	113	0	33	36	58	71	46	0
Internal Link Dist (ft)		1287		1672			122			245	
Turn Bay Length (ft)	200		215		190	75		100	210		200
Base Capacity (vph)	643	2290	480	2454	1127	178	333	395	205	349	407
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.10	0.45	0.31	0.22	0.05	0.11	0.05	0.34	0.28	0.07	0.14
Intersection Summary											

HCM 7th Signalized Intersection Summary

2: Stoney Creek Drive/Arborlake Drive & MO-150

Existing (Year 2024) Traffic Volumes

PM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	59	880	37	133	491	50	18	16	121	51	23	51
Future Volume (veh/h)	59	880	37	133	491	50	18	16	121	51	23	51
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Lane Width Adj.	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	66	989	42	149	552	0	20	18	136	57	26	0
Peak Hour Factor	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	693	2299	98	431	2385		239	193	164	245	227	
Arrive On Green	0.04	0.66	0.66	0.09	1.00	0.00	0.02	0.10	0.10	0.04	0.12	0.00
Sat Flow, veh/h	1781	3473	147	1781	3554	1585	1781	1870	1585	1781	1870	1585
Grp Volume(v), veh/h	66	506	525	149	552	0	20	18	136	57	26	0
Grp Sat Flow(s),veh/h/ln	1781	1777	1844	1781	1777	1585	1781	1870	1585	1781	1870	1585
Q Serve(g_s), s	1.4	16.2	16.2	3.3	0.0	0.0	1.2	1.0	10.1	3.4	1.5	0.0
Cycle Q Clear(g_c), s	1.4	16.2	16.2	3.3	0.0	0.0	1.2	1.0	10.1	3.4	1.5	0.0
Prop In Lane	1.00		0.08	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	693	1176	1220	431	2385		239	193	164	245	227	
V/C Ratio(X)	0.10	0.43	0.43	0.35	0.23		0.08	0.09	0.83	0.23	0.11	
Avail Cap(c_a), veh/h	723	1176	1220	579	2385		300	335	284	288	351	
HCM Platoon Ratio	1.00	1.00	1.00	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	0.96	0.96	0.00	1.00	1.00	1.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	5.6	9.6	9.6	6.7	0.0	0.0	46.6	48.7	52.8	45.7	47.0	0.0
Incr Delay (d2), s/veh	0.1	1.2	1.1	0.5	0.2	0.0	0.1	0.2	10.2	0.5	0.2	0.0
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.5	5.8	6.0	1.0	0.1	0.0	0.5	0.5	4.4	1.5	0.7	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d), s/veh	5.7	10.7	10.7	7.2	0.2	0.0	46.7	48.9	63.0	46.1	47.2	0.0
LnGrp LOS	A	B	B	A	A		D	D	E	D	D	
Approach Vol, veh/h	1097			701			174			83		
Approach Delay, s/veh	10.4			1.7			59.7			46.5		
Approach LOS	B			A			E			D		
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	9.1	16.9	10.1	83.9	6.9	19.1	8.9	85.0				
Change Period (Y+Rc), s	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5				
Max Green Setting (Gmax), s	7.5	21.5	15.5	57.5	6.5	22.5	6.5	66.5				
Max Q Clear Time (g_c+I1), s	5.4	12.1	5.3	18.2	3.2	3.5	3.4	2.0				
Green Ext Time (p_c), s	0.0	0.3	0.2	7.2	0.0	0.1	0.0	3.8				

Intersection Summary

HCM 7th Control Delay, s/veh	13.1
HCM 7th LOS	B

Notes

Unsignalized Delay for [WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

HCM 7th TWSC
3: Ward Road & Arborwalk Boulevard

Existing (Year 2024) Traffic Volumes
PM Peak Hour

Intersection						
Int Delay, s/veh	1.6					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Vol, veh/h	57	40	17	408	514	85
Future Vol, veh/h	57	40	17	408	514	85
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	200	-	250	-	-	150
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	89	89	89	89	89	89
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	64	45	19	458	578	96

Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	845	289	673	0	-	0
Stage 1	578	-	-	-	-	-
Stage 2	267	-	-	-	-	-
Critical Hdwy	6.84	6.94	4.14	-	-	-
Critical Hdwy Stg 1	5.84	-	-	-	-	-
Critical Hdwy Stg 2	5.84	-	-	-	-	-
Follow-up Hdwy	3.52	3.32	2.22	-	-	-
Pot Cap-1 Maneuver	302	708	914	-	-	-
Stage 1	524	-	-	-	-	-
Stage 2	753	-	-	-	-	-
Platoon blocked, %				-	-	-
Mov Cap-1 Maneuver	295	708	914	-	-	-
Mov Cap-2 Maneuver	295	-	-	-	-	-
Stage 1	514	-	-	-	-	-
Stage 2	753	-	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s/v16.36		0.36	0
HCM LOS	C		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	EBLn2	SBT	SBR
Capacity (veh/h)	914	-	295	708	-	-
HCM Lane V/C Ratio	0.021	-	0.217	0.063	-	-
HCM Control Delay (s/veh)	9	-	20.5	10.4	-	-
HCM Lane LOS	A	-	C	B	-	-
HCM 95th %tile Q(veh)	0.1	-	0.8	0.2	-	-

LANE SUMMARY

 **Site: 4 [Arborwalk Boulevard & Arborway Drive (Site Folder: General)]**

PM Peak Hour
Site Category: Existing Conditions
Roundabout

Lane Use and Performance													
	DEMAND FLOWS		Cap.	Deg. Satn	Lane Util.	Aver. Delay	Level of Service	95% BACK OF QUEUE		Lane Config	Lane Length	Cap. Adj.	Prob. Block.
	[Total veh/h	HV] %						[Veh	Dist] ft				
South: Access B													
Lane 1 ^d	3	1.7	1168	0.003	100	2.1	LOS A	0.0	0.3	Full	1600	0.0	0.0
Approach	3	1.7		0.003		2.1	LOS A	0.0	0.3				
East: Arborwalk Boulevard													
Lane 1 ^d	112	2.0	1295	0.086	100	0.2	LOS A	0.4	9.8	Full	1600	0.0	0.0
Approach	112	2.0		0.086		0.2	LOS A	0.4	9.8				
North: Arborway Drive													
Lane 1 ^d	98	2.0	1306	0.075	100	2.8	LOS A	0.3	8.4	Full	1600	0.0	0.0
Approach	98	2.0		0.075		2.8	LOS A	0.3	8.4				
West: Arborwalk Boulevard													
Lane 1 ^d	78	2.0	1258	0.062	100	0.3	LOS A	0.3	6.8	Full	1600	0.0	0.0
Approach	78	2.0		0.062		0.3	LOS A	0.3	6.8				
Intersection	291	2.0		0.086		1.1	LOS A	0.4	9.8				

Site Level of Service (LOS) Method: Delay & v/c (HCM 6). Site LOS Method is specified in the Parameter Settings dialog (Site tab).
Roundabout LOS Method: Same as Sign Control.

Lane LOS values are based on average delay and v/c ratio (degree of saturation) per lane.

LOS F will result if v/c > 1 irrespective of lane delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all lanes (v/c not used as specified in HCM 6).

Roundabout Capacity Model: US HCM 6.

Delay Model: SIDRA Standard (Geometric Delay is included).

Queue Model: HCM Queue Formula.

Gap-Acceptance Capacity: Traditional M1.

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

^d Dominant lane on roundabout approach

Approach Lane Flows (veh/h)											
South: Access B											
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL	Ov. Lane	
From S To Exit:	W	N	E			Cap. veh/h	v/c	%	%	No.	
Lane 1	1	1	1	3	1.7	1168	0.003	100	NA	NA	
Approach	1	1	1	3	1.7		0.003				
East: Arborwalk Boulevard											
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL	Ov. Lane	
From E To Exit:	S	W	N			Cap. veh/h	v/c	%	%	No.	
Lane 1	1	32	79	112	2.0	1295	0.086	100	NA	NA	
Approach	1	32	79	112	2.0		0.086				
North: Arborway Drive											
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL	Ov. Lane	
From N						Cap.	Satn	Util.	SL	Ov.	Lane

To Exit:	E	S	W			veh/h	v/c	%	%	No.
Lane 1	67	1	29	98	2.0	1306	0.075	100	NA	NA
Approach	67	1	29	98	2.0		0.075			
West: Arborwalk Boulevard										
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL Ov.	Ov. Lane No.
From W To Exit:	N	E	S			Cap. veh/h	v/c	%	%	No.
Lane 1	40	37	1	78	2.0	1258	0.062	100	NA	NA
Approach	40	37	1	78	2.0		0.062			
Total %HV Deg. Satn (v/c)										
Intersection	291	2.0			0.086					

Lane flow rates given in this report are based on the arrival flow rates subject to upstream capacity constraint where applicable.

Merge Analysis												
	Exit Lane Number	Short Lane Length ft	Percent Opng in Lane %	Opposing Flow Rate veh/h	Critical Gap sec	Follow-up Headway sec	Lane Flow Rate veh/h	Capacity veh/h	Deg. Satn v/c	Min. Delay sec	Merge Delay sec	
South Exit: Access B Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.
East Exit: Arborwalk Boulevard Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.
North Exit: Arborway Drive Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.
West Exit: Arborwalk Boulevard Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.

HCM 7th TWSC
5: Arborwalk Boulevard & Arbor Park Drive

Existing (Year 2024) Traffic Volumes
PM Peak Hour

Intersection						
Int Delay, s/veh	1.2					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W			W	W	
Traffic Vol, veh/h	8	3	9	63	48	8
Future Vol, veh/h	8	3	9	63	48	8
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	89	89	89	89	89	89
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	9	3	10	71	54	9

Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	149	58	63	0	-	0
Stage 1	58	-	-	-	-	-
Stage 2	91	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	843	1007	1540	-	-	-
Stage 1	964	-	-	-	-	-
Stage 2	933	-	-	-	-	-
Platoon blocked, %				-	-	-
Mov Cap-1 Maneuver	837	1007	1540	-	-	-
Mov Cap-2 Maneuver	837	-	-	-	-	-
Stage 1	958	-	-	-	-	-
Stage 2	933	-	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s/v	9.16	0.92	0
HCM LOS	A		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR
Capacity (veh/h)	225	-	877	-	-
HCM Lane V/C Ratio	0.007	-	0.014	-	-
HCM Control Delay (s/veh)	7.4	0	9.2	-	-
HCM Lane LOS	A	A	A	-	-
HCM 95th %tile Q(veh)	0	-	0	-	-

Queues

Existing plus Development Traffic Volumes

1: Ward Road & MO-150

AM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	137	355	34	57	774	170	191	253	115	154	83	134
v/c Ratio	0.47	0.17	0.04	0.28	0.40	0.18	0.56	0.61	0.40	0.52	0.21	0.46
Control Delay (s/veh)	64.0	10.5	0.2	56.7	17.1	3.0	57.5	56.5	12.6	58.0	48.9	13.1
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay (s/veh)	64.0	10.5	0.2	56.7	17.1	3.0	57.5	56.5	12.6	58.0	48.9	13.1
Queue Length 50th (ft)	57	49	0	22	171	0	73	99	0	59	31	0
Queue Length 95th (ft)	84	80	0	43	265	37	109	137	53	92	54	56
Internal Link Dist (ft)	1672				696				640			
Turn Bay Length (ft)	210		205	220		220	170		135	260		120
Base Capacity (vph)	359	2064	911	234	1930	947	472	752	426	362	663	402
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.38	0.17	0.04	0.24	0.40	0.18	0.40	0.34	0.27	0.43	0.13	0.33
Intersection Summary												

HCM 7th Signalized Intersection Summary

Existing plus Development Traffic Volumes

1: Ward Road & MO-150

AM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	126	327	31	52	712	156	176	233	106	142	76	123
Future Volume (veh/h)	126	327	31	52	712	156	176	233	106	142	76	123
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Lane Width Adj.	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1870	1841	1752	1781	1841	1856	1870	1870	1870	1752	1870	1856
Adj Flow Rate, veh/h	137	355	34	57	774	170	191	253	115	154	83	134
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	4	10	8	4	3	2	2	2	10	2	3
Cap, veh/h	193	2225	944	117	2154	968	254	404	180	210	373	165
Arrive On Green	0.11	1.00	1.00	0.04	0.62	0.62	0.07	0.11	0.11	0.06	0.10	0.10
Sat Flow, veh/h	3456	3497	1485	3291	3497	1572	3456	3554	1585	3237	3554	1572
Grp Volume(v), veh/h	137	355	34	57	774	170	191	253	115	154	83	134
Grp Sat Flow(s),veh/h/ln	1728	1749	1485	1646	1749	1572	1728	1777	1585	1618	1777	1572
Q Serve(g_s), s	4.6	0.0	0.0	2.0	13.1	5.6	6.5	8.2	8.3	5.6	2.6	10.0
Cycle Q Clear(g_c), s	4.6	0.0	0.0	2.0	13.1	5.6	6.5	8.2	8.3	5.6	2.6	10.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	193	2225	944	117	2154	968	254	404	180	210	373	165
V/C Ratio(X)	0.71	0.16	0.04	0.49	0.36	0.18	0.75	0.63	0.64	0.74	0.22	0.81
Avail Cap(c_a), veh/h	360	2225	944	233	2154	968	475	755	337	364	666	295
HCM Platoon Ratio	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	0.98	0.98	0.98	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	52.4	0.0	0.0	56.8	11.4	9.9	54.5	50.7	50.8	55.1	49.2	52.6
Incr Delay (d2), s/veh	4.7	0.2	0.1	3.1	0.5	0.4	4.4	1.6	3.7	4.9	0.3	9.2
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	2.0	0.0	0.0	0.9	4.7	1.9	2.9	3.6	3.4	2.4	1.1	4.3
Unsig. Movement Delay, s/veh												
LnGrp Delay(d), s/veh	57.1	0.2	0.1	60.0	11.8	10.3	58.9	52.3	54.5	60.1	49.5	61.8
LnGrp LOS	E	A	A	E	B	B	E	D	D	E	D	E
Approach Vol, veh/h	526			1001			559			371		
Approach Delay, s/veh	15.0			14.3			55.0			58.3		
Approach LOS	B			B			E			E		
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	12.3	18.1	8.8	80.8	13.3	17.1	11.2	78.4				
Change Period (Y+Rc), s	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5				
Max Green Setting (Gmax), s	13.5	25.5	8.5	54.5	16.5	22.5	12.5	50.5				
Max Q Clear Time (g_c+I1), s	7.6	10.3	4.0	2.0	8.5	12.0	6.6	15.1				
Green Ext Time (p_c), s	0.2	1.5	0.0	2.4	0.3	0.6	0.2	6.2				
Intersection Summary												
HCM 7th Control Delay, s/veh	30.4											
HCM 7th LOS	C											

Queues

Existing plus Development Traffic Volumes

2: Stoney Creek Drive/Arborlake Drive & MO-150

AM Peak Hour

											
Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	32	374	47	991	58	57	18	112	38	10	115
v/c Ratio	0.09	0.16	0.06	0.40	0.05	0.28	0.11	0.46	0.21	0.10	0.57
Control Delay (s/veh)	5.3	8.0	4.0	7.7	0.8	44.4	51.3	15.5	42.9	53.4	20.9
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay (s/veh)	5.3	8.0	4.0	7.7	0.8	44.4	51.3	15.5	42.9	53.4	20.9
Queue Length 50th (ft)	5	51	6	164	0	39	14	0	26	8	0
Queue Length 95th (ft)	17	90	17	204	4	72	36	54	54	25	57
Internal Link Dist (ft)	1287		1672		122		245				
Turn Bay Length (ft)	200		215		190	75		100	210		200
Base Capacity (vph)	376	2365	776	2501	1115	211	364	400	186	312	379
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.09	0.16	0.06	0.40	0.05	0.27	0.05	0.28	0.20	0.03	0.30
Intersection Summary											

HCM 7th Signalized Intersection Summary

2: Stoney Creek Drive/Arborlake Drive & MO-150

Existing plus Development Traffic Volumes

AM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	29	340	4	43	912	53	52	17	103	35	9	106
Future Volume (veh/h)	29	340	4	43	912	53	52	17	103	35	9	106
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Lane Width Adj.	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1633	1811	1870	1870	1856	1811	1870	1870	1870	1811	1693	1811
Adj Flow Rate, veh/h	32	370	4	47	991	0	57	18	112	38	10	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	18	6	2	2	3	6	2	2	2	6	14	6
Cap, veh/h	449	2436	26	787	2483		233	166	140	208	134	
Arrive On Green	0.03	0.70	0.70	0.07	1.00	0.00	0.04	0.09	0.09	0.03	0.08	0.00
Sat Flow, veh/h	1555	3487	38	1781	3526	1535	1781	1870	1585	1725	1693	1535
Grp Volume(v), veh/h	32	182	192	47	991	0	57	18	112	38	10	0
Grp Sat Flow(s),veh/h/ln	1555	1721	1804	1781	1763	1535	1781	1870	1585	1725	1693	1535
Q Serve(g_s), s	0.7	4.3	4.3	0.9	0.0	0.0	3.5	1.1	8.3	2.4	0.7	0.0
Cycle Q Clear(g_c), s	0.7	4.3	4.3	0.9	0.0	0.0	3.5	1.1	8.3	2.4	0.7	0.0
Prop In Lane	1.00		0.02	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	449	1202	1260	787	2483		233	166	140	208	134	
V/C Ratio(X)	0.07	0.15	0.15	0.06	0.40		0.24	0.11	0.80	0.18	0.07	
Avail Cap(c_a), veh/h	504	1202	1260	840	2483		290	366	310	265	317	
HCM Platoon Ratio	1.00	1.00	1.00	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	0.90	0.90	0.00	1.00	1.00	1.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	4.6	6.1	6.1	4.4	0.0	0.0	48.2	50.3	53.6	48.7	51.2	0.0
Incr Delay (d2), s/veh	0.1	0.3	0.3	0.0	0.4	0.0	0.5	0.3	9.9	0.4	0.2	0.0
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.2	1.4	1.5	0.3	0.1	0.0	1.6	0.5	3.6	1.1	0.3	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d), s/veh	4.7	6.4	6.4	4.4	0.4	0.0	48.7	50.6	63.5	49.1	51.4	0.0
LnGrp LOS	A	A	A	A	A		D	D	E	D	D	
Approach Vol, veh/h	406			1038			187			48		
Approach Delay, s/veh	6.2			0.6			57.8			49.6		
Approach LOS	A			A			E			D		
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	8.1	15.1	8.5	88.3	9.2	14.0	7.8	89.0				
Change Period (Y+Rc), s	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5				
Max Green Setting (Gmax), s	7.5	23.5	7.5	63.5	8.5	22.5	7.5	63.5				
Max Q Clear Time (g_c+I1), s	4.4	10.3	2.9	6.3	5.5	2.7	2.7	2.0				
Green Ext Time (p_c), s	0.0	0.3	0.0	2.1	0.0	0.0	0.0	8.0				

Intersection Summary

HCM 7th Control Delay, s/veh	9.7
HCM 7th LOS	A

Notes

Unsignalized Delay for [WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

HCM 7th TWSC
3: Ward Road & Arborwalk Boulevard

Existing plus Development Traffic Volumes
AM Peak Hour

Intersection						
Int Delay, s/veh	2.6					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Vol, veh/h	110	51	20	505	290	35
Future Vol, veh/h	110	51	20	505	290	35
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	200	-	250	-	-	150
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	92	92	92	92	92	92
Heavy Vehicles, %	2	14	27	2	5	16
Mvmt Flow	120	55	22	549	315	38

Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	633	158	353	0	-	0
Stage 1	315	-	-	-	-	-
Stage 2	318	-	-	-	-	-
Critical Hdwy	6.84	7.18	4.64	-	-	-
Critical Hdwy Stg 1	5.84	-	-	-	-	-
Critical Hdwy Stg 2	5.84	-	-	-	-	-
Follow-up Hdwy	3.52	3.44	2.47	-	-	-
Pot Cap-1 Maneuver	412	823	1041	-	-	-
Stage 1	713	-	-	-	-	-
Stage 2	710	-	-	-	-	-
Platoon blocked, %				-	-	-
Mov Cap-1 Maneuver	403	823	1041	-	-	-
Mov Cap-2 Maneuver	403	-	-	-	-	-
Stage 1	698	-	-	-	-	-
Stage 2	710	-	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s/v15.12		0.33	0
HCM LOS	C		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	EBLn2	SBT	SBR
Capacity (veh/h)	1041	-	403	823	-	-
HCM Lane V/C Ratio	0.021	-	0.296	0.067	-	-
HCM Control Delay (s/veh)	8.5	-	17.6	9.7	-	-
HCM Lane LOS	A	-	C	A	-	-
HCM 95th %tile Q(veh)	0.1	-	1.2	0.2	-	-

LANE SUMMARY

 **Site: 4 [Arborwalk Boulevard & Arborway Drive (Site Folder: General)]**

AM Peak Hour

Site Category: Existing plus Development Conditions

Roundabout

Lane Use and Performance													
	DEMAND FLOWS		Cap.	Deg. Satn	Lane Util.	Aver. Delay	Level of Service	95% BACK OF QUEUE		Lane Config	Lane Length	Cap. Adj.	Prob. Block.
	[Total veh/h	HV] %						[Veh	Dist] ft				
South: Access B													
Lane 1 ^d	68	2.0	1137	0.060	100	2.4	LOS A	0.3	6.5	Full	1600	0.0	0.0
Approach	68	2.0		0.060		2.4	LOS A	0.3	6.5				
East: Arborwalk Boulevard													
Lane 1 ^d	60	2.0	1264	0.047	100	0.3	LOS A	0.2	5.1	Full	1600	0.0	0.0
Approach	60	2.0		0.047		0.3	LOS A	0.2	5.1				
North: Arborway Drive													
Lane 1 ^d	138	2.0	1293	0.107	100	2.8	LOS A	0.5	12.3	Full	1600	0.0	0.0
Approach	138	2.0		0.107		2.8	LOS A	0.5	12.3				
West: Arborwalk Boulevard													
Lane 1 ^d	75	2.0	1201	0.062	100	0.5	LOS A	0.3	6.8	Full	1600	0.0	0.0
Approach	75	2.0		0.062		0.5	LOS A	0.3	6.8				
Intersection	341	2.0		0.107		1.8	LOS A	0.5	12.3				

Site Level of Service (LOS) Method: Delay & v/c (HCM 6). Site LOS Method is specified in the Parameter Settings dialog (Site tab).

Roundabout LOS Method: Same as Sign Control.

Lane LOS values are based on average delay and v/c ratio (degree of saturation) per lane.

LOS F will result if v/c > 1 irrespective of lane delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all lanes (v/c not used as specified in HCM 6).

Roundabout Capacity Model: US HCM 6.

Delay Model: SIDRA Standard (Geometric Delay is included).

Queue Model: HCM Queue Formula.

Gap-Acceptance Capacity: Traditional M1.

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

^d Dominant lane on roundabout approach

Approach Lane Flows (veh/h)											
South: Access B											
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL	Ov. Lane	
From S To Exit:	W	N	E			Cap. veh/h	v/c	%	%	No.	
Lane 1	13	1	54	68	2.0	1137	0.060	100	NA	NA	
Approach	13	1	54	68	2.0		0.060				
East: Arborwalk Boulevard											
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL	Ov. Lane	
From E To Exit:	S	W	N			Cap. veh/h	v/c	%	%	No.	
Lane 1	16	14	29	60	2.0	1264	0.047	100	NA	NA	
Approach	16	14	29	60	2.0		0.047				
North: Arborway Drive											
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL	Ov. Lane	
From N						Cap.	Satn	Util.	SL	OV.	Lane

To Exit:	E	S	W			veh/h	v/c	%	%	No.
Lane 1	97	1	40	138	2.0	1293	0.107	100	NA	NA
Approach	97	1	40	138	2.0		0.107			
West: Arborwalk Boulevard										
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL Ov.	Ov. Lane No.
From W To Exit:	N	E	S			Cap. veh/h	v/c	%	%	No.
Lane 1	51	20	4	75	2.0	1201	0.062	100	NA	NA
Approach	51	20	4	75	2.0		0.062			
Total %HV Deg. Satn (v/c)										
Intersection	341	2.0			0.107					

Lane flow rates given in this report are based on the arrival flow rates subject to upstream capacity constraint where applicable.

Merge Analysis												
	Exit Lane Number	Short Lane Length ft	Percent Opng in Lane %	Opposing Flow Rate veh/h	Critical Gap sec	Follow-up Headway sec	Lane Flow Rate veh/h	Capacity veh/h	Deg. Satn v/c	Min. Delay sec	Merge Delay sec	
South Exit: Access B Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.
East Exit: Arborwalk Boulevard Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.
North Exit: Arborway Drive Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.
West Exit: Arborwalk Boulevard Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.

HCM 7th TWSC
5: Arborwalk Boulevard & Arbor Park Drive

Existing plus Development Traffic Volumes
AM Peak Hour

Intersection						
Int Delay, s/veh	1.6					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W			4	4	
Traffic Vol, veh/h	10	15	3	59	63	0
Future Vol, veh/h	10	15	3	59	63	0
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	11	16	3	64	68	0
Major/Minor	Minor2	Major1		Major2		
Conflicting Flow All	139	68	68	0	-	0
Stage 1	68	-	-	-	-	-
Stage 2	71	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	854	995	1533	-	-	-
Stage 1	954	-	-	-	-	-
Stage 2	952	-	-	-	-	-
Platoon blocked, %				-	-	-
Mov Cap-1 Maneuver	852	995	1533	-	-	-
Mov Cap-2 Maneuver	852	-	-	-	-	-
Stage 1	952	-	-	-	-	-
Stage 2	952	-	-	-	-	-
Approach	EB	NB		SB		
HCM Control Delay, s/v	8.98	0.36		0		
HCM LOS	A					
Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR	
Capacity (veh/h)	87	-	932	-	-	
HCM Lane V/C Ratio	0.002	-	0.029	-	-	
HCM Control Delay (s/veh)	7.4	0	9	-	-	
HCM Lane LOS	A	A	A	-	-	
HCM 95th %tile Q(veh)	0	-	0.1	-	-	

HCM 7th TWSC
6: Arborwalk Boulevard & Access A

Existing plus Development Traffic Volumes
AM Peak Hour

Intersection						
Int Delay, s/veh	1.3					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	W		T			A
Traffic Vol, veh/h	12	8	54	4	3	74
Future Vol, veh/h	12	8	54	4	3	74
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	13	9	59	4	3	80

Major/Minor	Minor1	Major1	Major2
Conflicting Flow All	148	61	0
Stage 1	61	-	-
Stage 2	87	-	-
Critical Hdwy	6.42	6.22	-
Critical Hdwy Stg 1	5.42	-	-
Critical Hdwy Stg 2	5.42	-	-
Follow-up Hdwy	3.518	3.318	-
Pot Cap-1 Maneuver	844	1004	-
Stage 1	962	-	-
Stage 2	936	-	-
Platoon blocked, %		-	-
Mov Cap-1 Maneuver	842	1004	-
Mov Cap-2 Maneuver	842	-	-
Stage 1	962	-	-
Stage 2	934	-	-

Approach	WB	NB	SB
HCM Control Delay, s/v	9.1	0	0.29
HCM LOS	A		

Minor Lane/Major Mvmt	NBT	NBRWBLn1	SBL	SBT
Capacity (veh/h)	-	-	901	70
HCM Lane V/C Ratio	-	-	0.024	0.002
HCM Control Delay (s/veh)	-	-	9.1	7.3
HCM Lane LOS	-	-	A	A
HCM 95th %tile Q(veh)	-	-	0.1	0

Queues

Existing plus Development Traffic Volumes

1: Ward Road & MO-150

PM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	145	863	178	142	513	178	94	193	144	216	275	151
v/c Ratio	0.49	0.45	0.20	0.50	0.27	0.19	0.38	0.55	0.50	0.61	0.56	0.44
Control Delay (s/veh)	65.6	12.0	1.0	57.8	15.7	3.0	57.1	57.3	14.3	57.9	52.4	10.9
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay (s/veh)	65.6	12.0	1.0	57.8	15.7	3.0	57.1	57.3	14.3	57.9	52.4	10.9
Queue Length 50th (ft)	61	104	0	55	105	0	36	76	0	83	106	0
Queue Length 95th (ft)	93	134	9	85	164	37	62	111	58	119	143	56
Internal Link Dist (ft)	1672				696				640			
Turn Bay Length (ft)	210		205	220		220	170		135	260		120
Base Capacity (vph)	362	1913	889	343	1918	946	280	634	401	441	840	487
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.40	0.45	0.20	0.41	0.27	0.19	0.34	0.30	0.36	0.49	0.33	0.31
Intersection Summary												

HCM 7th Signalized Intersection Summary

Existing plus Development Traffic Volumes

1: Ward Road & MO-150

PM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	129	768	158	126	457	158	84	172	128	192	245	134
Future Volume (veh/h)	129	768	158	126	457	158	84	172	128	192	245	134
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Lane Width Adj.	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1870	1841	1752	1781	1841	1856	1870	1870	1870	1752	1870	1856
Adj Flow Rate, veh/h	145	863	178	142	513	178	94	193	144	216	275	151
Peak Hour Factor	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89
Percent Heavy Veh, %	2	4	10	8	4	3	2	2	2	10	2	3
Cap, veh/h	201	2068	878	197	2075	933	146	404	180	275	556	246
Arrive On Green	0.12	1.00	1.00	0.06	0.59	0.59	0.04	0.11	0.11	0.09	0.16	0.16
Sat Flow, veh/h	3456	3497	1485	3291	3497	1572	3456	3554	1585	3237	3554	1572
Grp Volume(v), veh/h	145	863	178	142	513	178	94	193	144	216	275	151
Grp Sat Flow(s),veh/h/ln	1728	1749	1485	1646	1749	1572	1728	1777	1585	1618	1777	1572
Q Serve(g_s), s	4.9	0.0	0.0	5.1	8.4	6.2	3.2	6.1	10.6	7.9	8.5	10.8
Cycle Q Clear(g_c), s	4.9	0.0	0.0	5.1	8.4	6.2	3.2	6.1	10.6	7.9	8.5	10.8
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	201	2068	878	197	2075	933	146	404	180	275	556	246
V/C Ratio(X)	0.72	0.42	0.20	0.72	0.25	0.19	0.65	0.48	0.80	0.78	0.49	0.61
Avail Cap(c_a), veh/h	360	2068	878	343	2075	933	274	637	284	445	844	373
HCM Platoon Ratio	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	0.89	0.89	0.89	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	52.1	0.0	0.0	55.4	11.6	11.2	56.6	49.9	51.9	53.8	46.3	47.2
Incr Delay (d2), s/veh	4.3	0.6	0.5	4.9	0.3	0.5	4.7	0.9	8.3	4.9	0.7	2.5
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	2.1	0.2	0.1	2.2	3.1	2.1	1.5	2.7	4.5	3.3	3.7	4.3
Unsig. Movement Delay, s/veh												
LnGrp Delay(d), s/veh	56.4	0.6	0.5	60.3	11.9	11.7	61.3	50.7	60.2	58.7	47.0	49.7
LnGrp LOS	E	A	A	E	B	B	E	D	E	E	D	D
Approach Vol, veh/h	1186			833			431			642		
Approach Delay, s/veh	7.4			20.1			56.2			51.6		
Approach LOS	A			C			E			D		
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	14.7	18.1	11.7	75.5	9.6	23.3	11.5	75.7				
Change Period (Y+Rc), s	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5				
Max Green Setting (Gmax), s	16.5	21.5	12.5	51.5	9.5	28.5	12.5	51.5				
Max Q Clear Time (g_c+I1), s	9.9	12.6	7.1	2.0	5.2	12.8	6.9	10.4				
Green Ext Time (p_c), s	0.4	1.0	0.2	7.4	0.1	1.8	0.2	4.0				
Intersection Summary												
HCM 7th Control Delay, s/veh	26.8											
HCM 7th LOS	C											

Queues

Existing plus Development Traffic Volumes

2: Stoney Creek Drive/Arborlake Drive & MO-150

PM Peak Hour

											
Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	96	1031	149	552	56	20	18	136	57	26	75
v/c Ratio	0.15	0.45	0.36	0.23	0.05	0.12	0.15	0.60	0.28	0.12	0.25
Control Delay (s/veh)	5.3	12.6	10.6	7.9	0.7	40.8	54.4	20.0	44.6	48.5	2.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay (s/veh)	5.3	12.6	10.6	7.9	0.7	40.8	54.4	20.0	44.6	48.5	2.0
Queue Length 50th (ft)	16	196	22	84	0	13	14	0	39	17	0
Queue Length 95th (ft)	39	314	87	117	0	33	36	58	71	46	0
Internal Link Dist (ft)		1287		1672			122			245	
Turn Bay Length (ft)	200		215		190	75		100	210		200
Base Capacity (vph)	642	2290	486	2379	1095	178	333	395	205	349	407
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.15	0.45	0.31	0.23	0.05	0.11	0.05	0.34	0.28	0.07	0.18
Intersection Summary											

HCM 7th Signalized Intersection Summary

2: Stoney Creek Drive/Arborlake Drive & MO-150

Existing plus Development Traffic Volumes

PM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	85	880	37	133	491	50	18	16	121	51	23	67
Future Volume (veh/h)	85	880	37	133	491	50	18	16	121	51	23	67
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Lane Width Adj.	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	96	989	42	149	552	0	20	18	136	57	26	0
Peak Hour Factor	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	698	2299	98	431	2375		239	193	164	245	227	
Arrive On Green	0.04	0.66	0.66	0.09	1.00	0.00	0.02	0.10	0.10	0.04	0.12	0.00
Sat Flow, veh/h	1781	3473	147	1781	3554	1585	1781	1870	1585	1781	1870	1585
Grp Volume(v), veh/h	96	506	525	149	552	0	20	18	136	57	26	0
Grp Sat Flow(s),veh/h/ln	1781	1777	1844	1781	1777	1585	1781	1870	1585	1781	1870	1585
Q Serve(g_s), s	2.0	16.2	16.2	3.3	0.0	0.0	1.2	1.0	10.1	3.4	1.5	0.0
Cycle Q Clear(g_c), s	2.0	16.2	16.2	3.3	0.0	0.0	1.2	1.0	10.1	3.4	1.5	0.0
Prop In Lane	1.00		0.08	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	698	1176	1220	431	2375		239	193	164	245	227	
V/C Ratio(X)	0.14	0.43	0.43	0.35	0.23		0.08	0.09	0.83	0.23	0.11	
Avail Cap(c_a), veh/h	723	1176	1220	579	2375		300	335	284	288	351	
HCM Platoon Ratio	1.00	1.00	1.00	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	0.96	0.96	0.00	1.00	1.00	1.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	5.6	9.6	9.6	6.7	0.0	0.0	46.6	48.7	52.8	45.7	47.0	0.0
Incr Delay (d2), s/veh	0.1	1.2	1.1	0.5	0.2	0.0	0.1	0.2	10.2	0.5	0.2	0.0
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.7	5.8	6.0	1.0	0.1	0.0	0.5	0.5	4.4	1.5	0.7	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d), s/veh	5.7	10.7	10.7	7.2	0.2	0.0	46.7	48.9	63.0	46.1	47.2	0.0
LnGrp LOS	A	B	B	A	A		D	D	E	D	D	
Approach Vol, veh/h	1127			701			174			83		
Approach Delay, s/veh	10.3			1.7			59.7			46.5		
Approach LOS	B			A			E			D		
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	9.1	16.9	10.1	83.9	6.9	19.1	9.3	84.7				
Change Period (Y+Rc), s	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5				
Max Green Setting (Gmax), s	7.5	21.5	15.5	57.5	6.5	22.5	6.5	66.5				
Max Q Clear Time (g_c+I1), s	5.4	12.1	5.3	18.2	3.2	3.5	4.0	2.0				
Green Ext Time (p_c), s	0.0	0.3	0.2	7.2	0.0	0.1	0.0	3.8				

Intersection Summary

HCM 7th Control Delay, s/veh	13.0
HCM 7th LOS	B

Notes

Unsignalized Delay for [WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

HCM 7th TWSC
3: Ward Road & Arborwalk Boulevard

Existing plus Development Traffic Volumes
PM Peak Hour

Intersection						
Int Delay, s/veh	2.4					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Vol, veh/h	75	58	47	408	514	116
Future Vol, veh/h	75	58	47	408	514	116
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	200	-	250	-	-	150
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	89	89	89	89	89	89
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	84	65	53	458	578	130
Major/Minor	Minor2	Major1		Major2		
Conflicting Flow All	912	289	708	0	-	0
Stage 1	578	-	-	-	-	-
Stage 2	335	-	-	-	-	-
Critical Hdwy	6.84	6.94	4.14	-	-	-
Critical Hdwy Stg 1	5.84	-	-	-	-	-
Critical Hdwy Stg 2	5.84	-	-	-	-	-
Follow-up Hdwy	3.52	3.32	2.22	-	-	-
Pot Cap-1 Maneuver	273	708	887	-	-	-
Stage 1	524	-	-	-	-	-
Stage 2	697	-	-	-	-	-
Platoon blocked, %				-	-	-
Mov Cap-1 Maneuver	257	708	887	-	-	-
Mov Cap-2 Maneuver	257	-	-	-	-	-
Stage 1	493	-	-	-	-	-
Stage 2	697	-	-	-	-	-
Approach	EB	NB		SB		
HCM Control Delay, s/v19.12		0.96		0		
HCM LOS	C					
Minor Lane/Major Mvmt	NBL	NBT	EBLn1	EBLn2	SBT	SBR
Capacity (veh/h)	887	-	257	708	-	-
HCM Lane V/C Ratio	0.06	-	0.328	0.092	-	-
HCM Control Delay (s/veh)	9.3	-	25.7	10.6	-	-
HCM Lane LOS	A	-	D	B	-	-
HCM 95th %tile Q(veh)	0.2	-	1.4	0.3	-	-

LANE SUMMARY

 **Site: 4 [Arborwalk Boulevard & Arborway Drive (Site Folder: General)]**

PM Peak Hour

Site Category: Existing plus Development Conditions

Roundabout

Lane Use and Performance													
	DEMAND FLOWS		Cap. veh/h	Deg. Satn v/c	Lane Util. %	Aver. Delay sec	Level of Service	95% BACK OF QUEUE		Lane Config	Lane Length ft	Cap. Adj. %	Prob. Block. %
	[Total veh/h	HV] %						[Veh	Dist] ft				
South: Access B													
Lane 1 ^d	43	2.0	1157	0.038	100	2.4	LOS A	0.2	4.0	Full	1600	0.0	0.0
Approach	43	2.0		0.038		2.4	LOS A	0.2	4.0				
East: Arborwalk Boulevard													
Lane 1 ^d	177	2.0	1284	0.138	100	0.2	LOS A	0.6	16.4	Full	1600	0.0	0.0
Approach	177	2.0		0.138		0.2	LOS A	0.6	16.4				
North: Arborway Drive													
Lane 1 ^d	98	2.0	1211	0.081	100	3.1	LOS A	0.4	8.9	Full	1600	0.0	0.0
Approach	98	2.0		0.081		3.1	LOS A	0.4	8.9				
West: Arborwalk Boulevard													
Lane 1 ^d	97	2.0	1188	0.081	100	0.5	LOS A	0.4	9.0	Full	1600	0.0	0.0
Approach	97	2.0		0.081		0.5	LOS A	0.4	9.0				
Intersection	415	2.0		0.138		1.2	LOS A	0.6	16.4				

Site Level of Service (LOS) Method: Delay & v/c (HCM 6). Site LOS Method is specified in the Parameter Settings dialog (Site tab).

Roundabout LOS Method: Same as Sign Control.

Lane LOS values are based on average delay and v/c ratio (degree of saturation) per lane.

LOS F will result if v/c > 1 irrespective of lane delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all lanes (v/c not used as specified in HCM 6).

Roundabout Capacity Model: US HCM 6.

Delay Model: SIDRA Standard (Geometric Delay is included).

Queue Model: HCM Queue Formula.

Gap-Acceptance Capacity: Traditional M1.

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

^d Dominant lane on roundabout approach

Approach Lane Flows (veh/h)											
South: Access B											
Mov.	L2	T1	R2	Total	%HV						
From S						Cap.	Deg.	Lane	Prob.	Ov.	
To Exit:	W	N	E			veh/h	satn	Util.	SL Ov.	Lane	
							v/c	%	%	No.	
Lane 1	9	1	34	43	2.0	1157	0.038	100	NA	NA	
Approach	9	1	34	43	2.0		0.038				
East: Arborwalk Boulevard											
Mov.	L2	T1	R2	Total	%HV						
From E						Cap.	Deg.	Lane	Prob.	Ov.	
To Exit:	S	W	N			veh/h	satn	Util.	SL Ov.	Lane	
							v/c	%	%	No.	
Lane 1	57	41	79	177	2.0	1284	0.138	100	NA	NA	
Approach	57	41	79	177	2.0		0.138				
North: Arborway Drive											
Mov.	L2	T1	R2	Total	%HV						
From N						Cap.	Deg.	Lane	Prob.	Ov.	
							satn	Util.	SL Ov.	Lane	

To Exit:	E	S	W			veh/h	v/c	%	%	No.
Lane 1	67	1	29	98	2.0	1211	0.081	100	NA	NA
Approach	67	1	29	98	2.0		0.081			
West: Arborwalk Boulevard										
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL Ov.	Ov. Lane No.
From W To Exit:	N	E	S			Cap. veh/h	v/c	%	%	No.
Lane 1	40	42	14	97	2.0	1188	0.081	100	NA	NA
Approach	40	42	14	97	2.0		0.081			
Total %HV Deg. Satn (v/c)										
Intersection	415	2.0		0.138						

Lane flow rates given in this report are based on the arrival flow rates subject to upstream capacity constraint where applicable.

Merge Analysis												
	Exit Lane Number	Short Lane Length ft	Percent Opng in Lane %	Opposing Flow Rate veh/h	Critical Gap sec	Follow-up Headway sec	Lane Flow Rate veh/h	Capacity veh/h	Deg. Satn v/c	Min. Delay sec	Merge Delay sec	
South Exit: Access B Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.
East Exit: Arborwalk Boulevard Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.
North Exit: Arborway Drive Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.
West Exit: Arborwalk Boulevard Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.

HCM 7th TWSC
5: Arborwalk Boulevard & Arbor Park Drive

Existing plus Development Traffic Volumes

PM Peak Hour

Intersection						
Int Delay, s/veh	1					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W			4	4	
Traffic Vol, veh/h	8	3	9	81	65	8
Future Vol, veh/h	8	3	9	81	65	8
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	89	89	89	89	89	89
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	9	3	10	91	73	9
Major/Minor	Minor2	Major1		Major2		
Conflicting Flow All	189	78	82	0	-	0
Stage 1	78	-	-	-	-	-
Stage 2	111	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	800	983	1515	-	-	-
Stage 1	946	-	-	-	-	-
Stage 2	913	-	-	-	-	-
Platoon blocked, %				-	-	-
Mov Cap-1 Maneuver	795	983	1515	-	-	-
Mov Cap-2 Maneuver	795	-	-	-	-	-
Stage 1	939	-	-	-	-	-
Stage 2	913	-	-	-	-	-
Approach	EB	NB		SB		
HCM Control Delay, s/v	9.36	0.74		0		
HCM LOS	A					
Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR	
Capacity (veh/h)	180	-	839	-	-	
HCM Lane V/C Ratio	0.007	-	0.015	-	-	
HCM Control Delay (s/veh)	7.4	0	9.4	-	-	
HCM Lane LOS	A	A	A	-	-	
HCM 95th %tile Q(veh)	0	-	0	-	-	

HCM 7th TWSC
6: Arborwalk Boulevard & Access A

Existing plus Development Traffic Volumes
PM Peak Hour

Intersection						
Int Delay, s/veh	1					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	W		T			A
Traffic Vol, veh/h	8	5	86	13	9	59
Future Vol, veh/h	8	5	86	13	9	59
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	89	89	89	89	89	89
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	9	6	97	15	10	66
Major/Minor	Minor1	Major1	Major2			
Conflicting Flow All	190	104	0	0	111	0
Stage 1	104	-	-	-	-	-
Stage 2	87	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218	-
Pot Cap-1 Maneuver	799	951	-	-	1479	-
Stage 1	920	-	-	-	-	-
Stage 2	937	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	793	951	-	-	1479	-
Mov Cap-2 Maneuver	793	-	-	-	-	-
Stage 1	920	-	-	-	-	-
Stage 2	930	-	-	-	-	-
Approach	WB	NB	SB			
HCM Control Delay, s/v	9.33	0	0.99			
HCM LOS	A					
Minor Lane/Major Mvmt	NBT	NBRWBLn1	SBL	SBT		
Capacity (veh/h)	-	-	847	238	-	
HCM Lane V/C Ratio	-	-	0.017	0.007	-	
HCM Control Delay (s/veh)	-	-	9.3	7.5	0	
HCM Lane LOS	-	-	A	A	A	
HCM 95th %tile Q(veh)	-	-	0.1	0	-	

Queues

1: Ward Road & MO-150

Future (Year 2044) Traffic Volumes

AM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	212	550	52	87	1197	258	296	391	178	224	125	207
v/c Ratio	0.61	0.31	0.06	0.39	0.71	0.30	0.70	0.69	0.44	0.67	0.25	0.58
Control Delay (s/veh)	66.2	14.7	0.3	58.4	28.6	6.0	59.8	53.9	9.6	62.3	46.2	20.5
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay (s/veh)	66.2	14.7	0.3	58.4	28.6	6.0	59.8	53.9	9.6	62.3	46.2	20.5
Queue Length 50th (ft)	88	83	1	33	386	21	114	152	0	86	45	36
Queue Length 95th (ft)	120	140	1	60	517	78	160	195	59	129	72	110
Internal Link Dist (ft)	1672				696				640			
Turn Bay Length (ft)	210		205	220		220	170		135	260		120
Base Capacity (vph)	372	1795	804	240	1683	867	472	752	476	359	663	419
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.57	0.31	0.06	0.36	0.71	0.30	0.63	0.52	0.37	0.62	0.19	0.49
Intersection Summary												

HCM 7th Signalized Intersection Summary

1: Ward Road & MO-150

Future (Year 2044) Traffic Volumes

AM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	195	506	48	80	1101	237	272	360	164	206	115	190
Future Volume (veh/h)	195	506	48	80	1101	237	272	360	164	206	115	190
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Lane Width Adj.	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1870	1841	1752	1781	1841	1856	1870	1870	1870	1752	1870	1856
Adj Flow Rate, veh/h	212	550	52	87	1197	258	296	391	178	224	125	207
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	4	10	8	4	3	2	2	2	10	2	3
Cap, veh/h	268	1940	824	134	1812	815	359	597	266	280	535	237
Arrive On Green	0.15	1.00	1.00	0.04	0.52	0.52	0.10	0.17	0.17	0.09	0.15	0.15
Sat Flow, veh/h	3456	3497	1485	3291	3497	1572	3456	3554	1585	3237	3554	1572
Grp Volume(v), veh/h	212	550	52	87	1197	258	296	391	178	224	125	207
Grp Sat Flow(s),veh/h/ln	1728	1749	1485	1646	1749	1572	1728	1777	1585	1618	1777	1572
Q Serve(g_s), s	7.1	0.0	0.0	3.1	30.1	11.4	10.1	12.3	12.6	8.2	3.7	15.5
Cycle Q Clear(g_c), s	7.1	0.0	0.0	3.1	30.1	11.4	10.1	12.3	12.6	8.2	3.7	15.5
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	268	1940	824	134	1812	815	359	597	266	280	535	237
V/C Ratio(X)	0.79	0.28	0.06	0.65	0.66	0.32	0.82	0.65	0.67	0.80	0.23	0.87
Avail Cap(c_a), veh/h	360	1940	824	233	1812	815	475	755	337	364	666	295
HCM Platoon Ratio	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	0.96	0.96	0.96	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	49.8	0.0	0.0	56.7	21.2	16.7	52.7	46.7	46.8	53.8	44.9	49.9
Incr Delay (d2), s/veh	8.1	0.4	0.1	5.2	1.9	1.0	8.6	1.4	3.5	9.3	0.2	20.7
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	3.1	0.1	0.0	1.4	11.9	4.1	4.7	5.4	5.1	3.6	1.6	7.3
Unsig. Movement Delay, s/veh												
LnGrp Delay(d), s/veh	57.8	0.4	0.1	61.9	23.1	17.7	61.3	48.0	50.2	63.1	45.1	70.5
LnGrp LOS	E	A	A	E	C	B	E	D	D	E	D	E
Approach Vol, veh/h	814		1542				865		556			
Approach Delay, s/veh	15.3		24.4				53.0		61.8			
Approach LOS	B		C				D		E			
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	14.9	24.7	9.4	71.1	17.0	22.6	13.8	66.7				
Change Period (Y+Rc), s	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5				
Max Green Setting (Gmax), s	13.5	25.5	8.5	54.5	16.5	22.5	12.5	50.5				
Max Q Clear Time (g_c+I1), s	10.2	14.6	5.1	2.0	12.1	17.5	9.1	32.1				
Green Ext Time (p_c), s	0.2	2.2	0.1	3.9	0.4	0.6	0.2	8.7				
Intersection Summary												
HCM 7th Control Delay, s/veh			34.5									
HCM 7th LOS			C									

Queues

2: Stoney Creek Drive/Arborlake Drive & MO-150

Future (Year 2044) Traffic Volumes

AM Peak Hour

											
Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	43	579	72	1533	89	87	28	173	59	15	164
v/c Ratio	0.22	0.26	0.12	0.65	0.08	0.38	0.16	0.56	0.30	0.14	0.65
Control Delay (s/veh)	7.7	9.4	6.3	13.3	3.5	46.1	52.2	14.8	44.4	53.6	20.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay (s/veh)	7.7	9.4	6.3	13.3	3.5	46.1	52.2	14.8	44.4	53.6	20.2
Queue Length 50th (ft)	8	91	12	290	3	59	21	0	39	11	0
Queue Length 95th (ft)	20	138	m32	334	m13	103	49	66	75	32	65
Internal Link Dist (ft)	1287		1672		122		245				
Turn Bay Length (ft)	200	215		190		75	100		210	200	
Base Capacity (vph)	207	2263	613	2343	1050	230	364	449	203	312	419
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.21	0.26	0.12	0.65	0.08	0.38	0.08	0.39	0.29	0.05	0.39
Intersection Summary											
m Volume for 95th percentile queue is metered by upstream signal.											

HCM 7th Signalized Intersection Summary

2: Stoney Creek Drive/Arborlake Drive & MO-150

Future (Year 2044) Traffic Volumes

AM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	40	526	6	66	1410	82	80	26	159	54	14	151
Future Volume (veh/h)	40	526	6	66	1410	82	80	26	159	54	14	151
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Lane Width Adj.	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No				No				No			
Adj Sat Flow, veh/h/ln	1633	1811	1870	1870	1856	1811	1870	1870	1870	1811	1693	1811
Adj Flow Rate, veh/h	43	572	7	72	1533	0	87	28	173	59	15	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	18	6	2	2	3	6	2	2	2	6	14	6
Cap, veh/h	300	2244	27	607	2295		305	238	202	257	188	
Arrive On Green	0.03	0.64	0.64	0.08	1.00	0.00	0.06	0.13	0.13	0.04	0.11	0.00
Sat Flow, veh/h	1555	3481	43	1781	3526	1535	1781	1870	1585	1725	1693	1535
Grp Volume(v), veh/h	43	283	296	72	1533	0	87	28	173	59	15	0
Grp Sat Flow(s),veh/h/ln	1555	1721	1803	1781	1763	1535	1781	1870	1585	1725	1693	1535
Q Serve(g_s), s	1.1	8.4	8.4	1.6	0.0	0.0	5.1	1.6	12.8	3.6	1.0	0.0
Cycle Q Clear(g_c), s	1.1	8.4	8.4	1.6	0.0	0.0	5.1	1.6	12.8	3.6	1.0	0.0
Prop In Lane	1.00		0.02	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	300	1109	1163	607	2295		305	238	202	257	188	
V/C Ratio(X)	0.14	0.25	0.25	0.12	0.67		0.29	0.12	0.86	0.23	0.08	
Avail Cap(c_a), veh/h	348	1109	1163	651	2295		330	366	310	295	317	
HCM Platoon Ratio	1.00	1.00	1.00	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	0.66	0.66	0.00	1.00	1.00	1.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	6.5	9.1	9.1	6.4	0.0	0.0	43.7	46.4	51.3	44.7	47.8	0.0
Incr Delay (d2), s/veh	0.2	0.6	0.5	0.1	1.0	0.0	0.5	0.2	13.6	0.5	0.2	0.0
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.3	3.0	3.1	0.5	0.3	0.0	2.3	0.8	5.7	1.6	0.4	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d), s/veh	6.7	9.6	9.6	6.4	1.0	0.0	44.2	46.6	65.0	45.2	48.0	0.0
LnGrp LOS	A	A	A	A	A		D	D	E	D	D	
Approach Vol, veh/h	622				1605				288			
Approach Delay, s/veh	9.4				1.3				56.9			
Approach LOS	A				A				E			
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	9.3	19.8	9.0	81.9	11.3	17.8	8.3	82.6				
Change Period (Y+Rc), s	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5				
Max Green Setting (Gmax), s	7.5	23.5	7.5	63.5	8.5	22.5	7.5	63.5				
Max Q Clear Time (g_c+I1), s	5.6	14.8	3.6	10.4	7.1	3.0	3.1	2.0				
Green Ext Time (p_c), s	0.0	0.4	0.0	3.4	0.0	0.0	0.0	16.9				

Intersection Summary

HCM 7th Control Delay, s/veh	10.7
HCM 7th LOS	B

Notes

Unsignalized Delay for [WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

HCM 7th TWSC
3: Ward Road & Arborwalk Boulevard

Future (Year 2044) Traffic Volumes
AM Peak Hour

Intersection							
Int Delay, s/veh	5.4						
Movement	EBL	EBR	NBL	NBT	SBT	SBR	
Lane Configurations							
Traffic Vol, veh/h	154	63	26	781	448	49	
Future Vol, veh/h	154	63	26	781	448	49	
Conflicting Peds, #/hr	0	0	0	0	0	0	
Sign Control	Stop	Stop	Free	Free	Free	Free	
RT Channelized	-	None	-	None	-	None	
Storage Length	200	-	250	-	-	150	
Veh in Median Storage, #	0	-	-	0	0	-	
Grade, %	0	-	-	0	0	-	
Peak Hour Factor	92	92	92	92	92	92	
Heavy Vehicles, %	2	14	27	2	5	16	
Mvmt Flow	167	68	28	849	487	53	
Major/Minor	Minor2		Major1		Major2		
Conflicting Flow All	968	243	540	0	-	0	
Stage 1	487	-	-	-	-	-	
Stage 2	481	-	-	-	-	-	
Critical Hdwy	6.84	7.18	4.64	-	-	-	
Critical Hdwy Stg 1	5.84	-	-	-	-	-	
Critical Hdwy Stg 2	5.84	-	-	-	-	-	
Follow-up Hdwy	3.52	3.44	2.47	-	-	-	
Pot Cap-1 Maneuver	251	722	869	-	-	-	
Stage 1	583	-	-	-	-	-	
Stage 2	588	-	-	-	-	-	
Platoon blocked, %				-	-	-	
Mov Cap-1 Maneuver	243	722	869	-	-	-	
Mov Cap-2 Maneuver	243	-	-	-	-	-	
Stage 1	564	-	-	-	-	-	
Stage 2	588	-	-	-	-	-	
Approach	EB		NB		SB		
HCM Control Delay, s/v36.49			0.3		0		
HCM LOS	E						
Minor Lane/Major Mvmt	NBL		NBT	EBLn1	EBLn2	SBT	SBR
Capacity (veh/h)	869		-	243	722	-	-
HCM Lane V/C Ratio	0.033		-	0.688	0.095	-	-
HCM Control Delay (s/veh)	9.3		-	47.1	10.5	-	-
HCM Lane LOS	A		-	E	B	-	-
HCM 95th %tile Q(veh)	0.1		-	4.5	0.3	-	-

LANE SUMMARY

 **Site: 4 [Arborwalk Boulevard & Arborway Drive (Site Folder: General)]**

AM Peak Hour
Site Category: Future Conditions
Roundabout

Lane Use and Performance													
	DEMAND FLOWS		Cap.	Deg. Satn	Lane Util.	Aver. Delay	Level of Service	95% BACK OF QUEUE		Lane Config	Lane Length	Cap. Adj.	Prob. Block.
	[Total veh/h	HV] %						[Veh	Dist] ft				
South: Access B													
Lane 1 ^d	68	2.0	1038	0.066	100	2.9	LOS A	0.3	7.0	Full	1600	0.0	0.0
Approach	68	2.0		0.066		2.9	LOS A	0.3	7.0				
East: Arborwalk Boulevard													
Lane 1 ^d	82	2.0	1228	0.066	100	0.4	LOS A	0.3	7.3	Full	1600	0.0	0.0
Approach	82	2.0		0.066		0.4	LOS A	0.3	7.3				
North: Arborway Drive													
Lane 1 ^d	213	2.0	1286	0.166	100	2.9	LOS A	0.8	20.3	Full	1600	0.0	0.0
Approach	213	2.0		0.166		2.9	LOS A	0.8	20.3				
West: Arborwalk Boulevard													
Lane 1 ^d	109	2.0	1137	0.096	100	0.8	LOS A	0.4	10.6	Full	1600	0.0	0.0
Approach	109	2.0		0.096		0.8	LOS A	0.4	10.6				
Intersection	472	2.0		0.166		2.0	LOS A	0.8	20.3				

Site Level of Service (LOS) Method: Delay & v/c (HCM 6). Site LOS Method is specified in the Parameter Settings dialog (Site tab).
Roundabout LOS Method: Same as Sign Control.

Lane LOS values are based on average delay and v/c ratio (degree of saturation) per lane.

LOS F will result if v/c > 1 irrespective of lane delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all lanes (v/c not used as specified in HCM 6).

Roundabout Capacity Model: US HCM 6.

Delay Model: SIDRA Standard (Geometric Delay is included).

Queue Model: HCM Queue Formula.

Gap-Acceptance Capacity: Traditional M1.

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

^d Dominant lane on roundabout approach

Approach Lane Flows (veh/h)											
South: Access B											
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL	Ov. Lane	
From S To Exit:	W	N	E			Cap. veh/h	v/c	%	%	No.	
Lane 1	13	1	54	68	2.0	1038	0.066	100	NA	NA	
Approach	13	1	54	68	2.0		0.066				
East: Arborwalk Boulevard											
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL	Ov. Lane	
From E To Exit:	S	W	N			Cap. veh/h	v/c	%	%	No.	
Lane 1	16	20	46	82	2.0	1228	0.066	100	NA	NA	
Approach	16	20	46	82	2.0		0.066				
North: Arborway Drive											
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL	Ov. Lane	
From N						Cap.					

To Exit:	E	S	W			veh/h	v/c	%	%	No.
Lane 1	150	1	62	213	2.0	1286	0.166	100	NA	NA
Approach	150	1	62	213	2.0		0.166			
West: Arborwalk Boulevard										
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL Ov.	Ov. Lane No.
From W To Exit:	N	E	S			Cap. veh/h	v/c	%	%	No.
Lane 1	79	25	4	109	2.0	1137	0.096	100	NA	NA
Approach	79	25	4	109	2.0		0.096			
Total %HV Deg. Satn (v/c)										
Intersection	472	2.0					0.166			

Lane flow rates given in this report are based on the arrival flow rates subject to upstream capacity constraint where applicable.

Merge Analysis												
	Exit Lane Number	Short Lane Length ft	Percent Opng in Lane %	Opposing Flow Rate veh/h	Critical Gap sec	Follow-up Headway sec	Lane Capacity veh/h	Deg. Satn v/c	Min. Delay sec	Merge Delay sec		
South Exit: Access B Merge Type: Not Applied												
Full Length Lane	1											
East Exit: Arborwalk Boulevard Merge Type: Not Applied												
Full Length Lane	1											
North Exit: Arborway Drive Merge Type: Not Applied												
Full Length Lane	1											
West Exit: Arborwalk Boulevard Merge Type: Not Applied												
Full Length Lane	1											

HCM 7th TWSC
5: Arborwalk Boulevard & Arbor Park Drive

Future (Year 2044) Traffic Volumes
AM Peak Hour

Intersection						
Int Delay, s/veh	1.8					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W			4	4	
Traffic Vol, veh/h	15	23	5	85	89	0
Future Vol, veh/h	15	23	5	85	89	0
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	16	25	5	92	97	0
Major/Minor	Minor2	Major1		Major2		
Conflicting Flow All	200	97	97	0	-	0
Stage 1	97	-	-	-	-	-
Stage 2	103	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	789	960	1497	-	-	-
Stage 1	927	-	-	-	-	-
Stage 2	921	-	-	-	-	-
Platoon blocked, %				-	-	-
Mov Cap-1 Maneuver	786	960	1497	-	-	-
Mov Cap-2 Maneuver	786	-	-	-	-	-
Stage 1	924	-	-	-	-	-
Stage 2	921	-	-	-	-	-
Approach	EB	NB		SB		
HCM Control Delay, s/v	9.28	0.41		0		
HCM LOS	A					
Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR	
Capacity (veh/h)	100	-	882	-	-	
HCM Lane V/C Ratio	0.004	-	0.047	-	-	
HCM Control Delay (s/veh)	7.4	0	9.3	-	-	
HCM Lane LOS	A	A	A	-	-	
HCM 95th %tile Q(veh)	0	-	0.1	-	-	

HCM 7th TWSC
6: Arborwalk Boulevard & Access A

Future (Year 2044) Traffic Volumes
AM Peak Hour

Intersection						
Int Delay, s/veh	1					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	W		T			L
Traffic Vol, veh/h	12	8	81	4	3	108
Future Vol, veh/h	12	8	81	4	3	108
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	13	9	88	4	3	117
Major/Minor	Minor1	Major1	Major2			
Conflicting Flow All	214	90	0	0	92	0
Stage 1	90	-	-	-	-	-
Stage 2	124	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218	-
Pot Cap-1 Maneuver	774	968	-	-	1502	-
Stage 1	933	-	-	-	-	-
Stage 2	902	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	772	968	-	-	1502	-
Mov Cap-2 Maneuver	772	-	-	-	-	-
Stage 1	933	-	-	-	-	-
Stage 2	900	-	-	-	-	-
Approach	WB	NB		SB		
HCM Control Delay, s/v	9.4	0		0.2		
HCM LOS	A					
Minor Lane/Major Mvmt	NBT	NBRWBLn1	SBL	SBT		
Capacity (veh/h)	-	-	840	49	-	
HCM Lane V/C Ratio	-	-	0.026	0.002	-	
HCM Control Delay (s/veh)	-	-	9.4	7.4	0	
HCM Lane LOS	-	-	A	A	A	
HCM 95th %tile Q(veh)	-	-	0.1	0	-	

Queues

1: Ward Road & MO-150

Future (Year 2044) Traffic Volumes

PM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	224	1334	274	219	794	258	146	297	222	325	424	233
v/c Ratio	0.63	0.79	0.34	0.64	0.47	0.29	0.57	0.64	0.59	0.79	0.65	0.49
Control Delay (s/veh)	58.1	26.8	10.1	60.2	22.8	3.4	62.4	55.7	15.8	64.7	49.6	8.5
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay (s/veh)	58.1	26.8	10.1	60.2	22.8	3.4	62.4	55.7	15.8	64.7	49.6	8.5
Queue Length 50th (ft)	94	218	20	84	214	0	57	116	17	126	161	0
Queue Length 95th (ft)	m122	403	m103	124	291	47	90	155	87	174	203	62
Internal Link Dist (ft)		1672			696			640			959	
Turn Bay Length (ft)	210		205	220		220	170		135	260		120
Base Capacity (vph)	379	1678	807	362	1683	893	271	634	445	437	840	550
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.59	0.79	0.34	0.60	0.47	0.29	0.54	0.47	0.50	0.74	0.50	0.42

Intersection Summary

m Volume for 95th percentile queue is metered by upstream signal.

HCM 7th Signalized Intersection Summary

1: Ward Road & MO-150

Future (Year 2044) Traffic Volumes

PM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	199	1187	244	195	707	230	130	264	198	289	377	207
Future Volume (veh/h)	199	1187	244	195	707	230	130	264	198	289	377	207
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Lane Width Adj.	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1870	1841	1752	1781	1841	1856	1870	1870	1870	1752	1870	1856
Adj Flow Rate, veh/h	224	1334	274	219	794	258	146	297	222	325	424	233
Peak Hour Factor	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89
Percent Heavy Veh, %	2	4	10	8	4	3	2	2	2	10	2	3
Cap, veh/h	279	1710	726	275	1719	773	202	568	254	381	779	345
Arrive On Green	0.16	0.98	0.98	0.08	0.49	0.49	0.06	0.16	0.16	0.12	0.22	0.22
Sat Flow, veh/h	3456	3497	1485	3291	3497	1572	3456	3554	1585	3237	3554	1572
Grp Volume(v), veh/h	224	1334	274	219	794	258	146	297	222	325	424	233
Grp Sat Flow(s),veh/h/ln	1728	1749	1485	1646	1749	1572	1728	1777	1585	1618	1777	1572
Q Serve(g_s), s	7.5	4.3	0.8	7.8	17.9	12.0	5.0	9.2	16.4	11.8	12.7	16.3
Cycle Q Clear(g_c), s	7.5	4.3	0.8	7.8	17.9	12.0	5.0	9.2	16.4	11.8	12.7	16.3
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	279	1710	726	275	1719	773	202	568	254	381	779	345
V/C Ratio(X)	0.80	0.78	0.38	0.80	0.46	0.33	0.72	0.52	0.88	0.85	0.54	0.68
Avail Cap(c_a), veh/h	360	1710	726	343	1719	773	274	637	284	445	844	373
HCM Platoon Ratio	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	0.56	0.56	0.56	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	49.4	0.7	0.7	54.0	20.1	18.6	55.5	46.2	49.2	51.9	41.5	42.9
Incr Delay (d2), s/veh	5.6	2.0	0.8	10.1	0.9	1.2	5.9	0.7	23.2	13.2	0.6	4.3
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	3.2	0.9	0.3	3.6	7.1	4.4	2.3	4.0	7.9	5.4	5.5	6.6
Unsig. Movement Delay, s/veh												
LnGrp Delay(d), s/veh	55.0	2.8	1.5	64.1	21.0	19.7	61.5	47.0	72.5	65.1	42.1	47.3
LnGrp LOS	E	A	A	E	C	B	E	D	E	E	D	D
Approach Vol, veh/h	1832			1271			665			982		
Approach Delay, s/veh	9.0			28.1			58.7			51.0		
Approach LOS	A			C			E			D		
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	18.6	23.7	14.5	63.2	11.5	30.8	14.2	63.5				
Change Period (Y+Rc), s	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5				
Max Green Setting (Gmax), s	16.5	21.5	12.5	51.5	9.5	28.5	12.5	51.5				
Max Q Clear Time (g_c+I1), s	13.8	18.4	9.8	6.3	7.0	18.3	9.5	19.9				
Green Ext Time (p_c), s	0.3	0.8	0.2	14.3	0.1	2.4	0.2	6.7				
Intersection Summary												
HCM 7th Control Delay, s/veh	29.7											
HCM 7th LOS	C											

Queues

2: Stoney Creek Drive/Arborlake Drive & MO-150

Future (Year 2044) Traffic Volumes

PM Peak Hour

											
Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	131	1592	231	853	87	31	28	210	89	40	107
v/c Ratio	0.28	0.79	0.73	0.37	0.08	0.16	0.22	0.69	0.44	0.19	0.35
Control Delay (s/veh)	7.2	24.9	46.5	9.1	1.5	42.6	54.8	18.9	49.7	51.4	7.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay (s/veh)	7.2	24.9	46.5	9.1	1.5	42.6	54.8	18.9	49.7	51.4	7.2
Queue Length 50th (ft)	22	462	150	116	0	21	21	0	62	30	0
Queue Length 95th (ft)	48	#756	236	157	4	46	49	69	104	62	30
Internal Link Dist (ft)		1287		1672			122			245	
Turn Bay Length (ft)	200		215		190	75		100	210		200
Base Capacity (vph)	467	2022	330	2300	1062	191	333	455	204	349	407
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.28	0.79	0.70	0.37	0.08	0.16	0.08	0.46	0.44	0.11	0.26

Intersection Summary

95th percentile volume exceeds capacity, queue may be longer.
Queue shown is maximum after two cycles.

HCM 7th Signalized Intersection Summary

2: Stoney Creek Drive/Arborlake Drive & MO-150

Future (Year 2044) Traffic Volumes

PM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	117	1360	57	206	759	77	28	25	187	79	36	95
Future Volume (veh/h)	117	1360	57	206	759	77	28	25	187	79	36	95
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Lane Width Adj.	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	131	1528	64	231	853	0	31	28	210	89	40	0
Peak Hour Factor	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.89
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	512	1983	83	268	2129		312	279	236	314	332	
Arrive On Green	0.05	0.57	0.57	0.15	1.00	0.00	0.03	0.15	0.15	0.06	0.18	0.00
Sat Flow, veh/h	1781	3476	145	1781	3554	1585	1781	1870	1585	1781	1870	1585
Grp Volume(v), veh/h	131	779	813	231	853	0	31	28	210	89	40	0
Grp Sat Flow(s),veh/h/ln	1781	1777	1844	1781	1777	1585	1781	1870	1585	1781	1870	1585
Q Serve(g_s), s	3.6	40.2	40.6	6.7	0.0	0.0	1.8	1.6	15.6	5.0	2.2	0.0
Cycle Q Clear(g_c), s	3.6	40.2	40.6	6.7	0.0	0.0	1.8	1.6	15.6	5.0	2.2	0.0
Prop In Lane	1.00		0.08	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	512	1014	1052	268	2129		312	279	236	314	332	
V/C Ratio(X)	0.26	0.77	0.77	0.86	0.40		0.10	0.10	0.89	0.28	0.12	
Avail Cap(c_a), veh/h	525	1014	1052	364	2129		360	335	284	327	351	
HCM Platoon Ratio	1.00	1.00	1.00	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	0.87	0.87	0.00	1.00	1.00	1.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	9.5	19.7	19.8	21.6	0.0	0.0	41.5	44.1	50.1	39.3	41.5	0.0
Incr Delay (d2), s/veh	0.3	5.6	5.5	12.8	0.5	0.0	0.1	0.2	24.2	0.5	0.2	0.0
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	1.3	16.5	17.2	4.3	0.1	0.0	0.8	0.7	7.6	2.2	1.0	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d), s/veh	9.8	25.3	25.3	34.4	0.5	0.0	41.6	44.3	74.3	39.8	41.6	0.0
LnGrp LOS	A	C	C	C	A		D	D	E	D	D	
Approach Vol, veh/h	1723			1084			269			129		
Approach Delay, s/veh	24.1			7.7			67.4			40.3		
Approach LOS	C			A			E			D		
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	11.1	22.4	13.5	73.0	7.7	25.8	10.1	76.4				
Change Period (Y+Rc), s	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5				
Max Green Setting (Gmax), s	7.5	21.5	15.5	57.5	6.5	22.5	6.5	66.5				
Max Q Clear Time (g_c+I1), s	7.0	17.6	8.7	42.6	3.8	4.2	5.6	2.0				
Green Ext Time (p_c), s	0.0	0.3	0.3	8.9	0.0	0.1	0.0	6.5				

Intersection Summary

HCM 7th Control Delay, s/veh	22.9
HCM 7th LOS	C

Notes

Unsignalized Delay for [WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

HCM 7th TWSC 3: Ward Road & Arborwalk Boulevard

Future (Year 2044) Traffic Volumes
PM Peak Hour

Intersection						
Int Delay, s/veh	9					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Vol, veh/h	106	80	56	631	795	162
Future Vol, veh/h	106	80	56	631	795	162
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	200	-	250	-	-	150
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	89	89	89	89	89	89
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	119	90	63	709	893	182

Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	1374	447	1075	0	-	0
Stage 1	893	-	-	-	-	-
Stage 2	480	-	-	-	-	-
Critical Hdwy	6.84	6.94	4.14	-	-	-
Critical Hdwy Stg 1	5.84	-	-	-	-	-
Critical Hdwy Stg 2	5.84	-	-	-	-	-
Follow-up Hdwy	3.52	3.32	2.22	-	-	-
Pot Cap-1 Maneuver	137	559	644	-	-	-
Stage 1	360	-	-	-	-	-
Stage 2	588	-	-	-	-	-
Platoon blocked, %				-	-	-
Mov Cap-1 Maneuver	123	559	644	-	-	-
Mov Cap-2 Maneuver	123	-	-	-	-	-
Stage 1	325	-	-	-	-	-
Stage 2	588	-	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s/v	84.83	0.91	0
HCM LOS	F		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	EBLn2	SBT	SBR
Capacity (veh/h)	644	-	123	559	-	-
HCM Lane V/C Ratio	0.098	-	0.966	0.161	-	-
HCM Control Delay (s/veh)	11.2	-	139.3	12.7	-	-
HCM Lane LOS	B	-	F	B	-	-
HCM 95th %tile Q(veh)	0.3	-	6.4	0.6	-	-

LANE SUMMARY

 **Site: 4 [Arborwalk Boulevard & Arborway Drive (Site Folder: General)]**

PM Peak Hour
Site Category: Future Conditions
Roundabout

Lane Use and Performance													
	DEMAND FLOWS		Cap.	Deg. Satn	Lane Util.	Aver. Delay	Level of Service	95% BACK OF QUEUE		Lane Config	Lane Length	Cap. Adj.	Prob. Block.
	[Total veh/h	HV] %						[Veh	Dist] ft				
South: Access B													
Lane 1 ^d	43	2.0	1066	0.041	100	2.7	LOS A	0.2	4.2	Full	1600	0.0	0.0
Approach	43	2.0		0.041		2.7	LOS A	0.2	4.2				
East: Arborwalk Boulevard													
Lane 1 ^d	238	2.0	1256	0.190	100	0.4	LOS A	0.9	23.7	Full	1600	0.0	0.0
Approach	238	2.0		0.190		0.4	LOS A	0.9	23.7				
North: Arborway Drive													
Lane 1 ^d	151	2.0	1189	0.127	100	3.2	LOS A	0.6	14.6	Full	1600	0.0	0.0
Approach	151	2.0		0.127		3.2	LOS A	0.6	14.6				
West: Arborwalk Boulevard													
Lane 1 ^d	139	2.0	1143	0.122	100	0.7	LOS A	0.5	13.8	Full	1600	0.0	0.0
Approach	139	2.0		0.122		0.7	LOS A	0.5	13.8				
Intersection	572	2.0		0.190		1.4	LOS A	0.9	23.7				

Site Level of Service (LOS) Method: Delay & v/c (HCM 6). Site LOS Method is specified in the Parameter Settings dialog (Site tab).
Roundabout LOS Method: Same as Sign Control.

Lane LOS values are based on average delay and v/c ratio (degree of saturation) per lane.

LOS F will result if v/c > 1 irrespective of lane delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all lanes (v/c not used as specified in HCM 6).

Roundabout Capacity Model: US HCM 6.

Delay Model: SIDRA Standard (Geometric Delay is included).

Queue Model: HCM Queue Formula.

Gap-Acceptance Capacity: Traditional M1.

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

^d Dominant lane on roundabout approach

Approach Lane Flows (veh/h)											
South: Access B											
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL	Ov. Lane	
From S To Exit:	W	N	E			Cap. veh/h	v/c	%	%	No.	
Lane 1	9	1	34	43	2.0	1066	0.041	100	NA	NA	
Approach	9	1	34	43	2.0		0.041				
East: Arborwalk Boulevard											
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL	Ov. Lane	
From E To Exit:	S	W	N			Cap. veh/h	v/c	%	%	No.	
Lane 1	57	59	123	238	2.0	1256	0.190	100	NA	NA	
Approach	57	59	123	238	2.0		0.190				
North: Arborway Drive											
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL	Ov. Lane	
From N						Cap. veh/h	v/c	%	%	No.	

To Exit:	E	S	W			veh/h	v/c	%	%	No.
Lane 1	104	1	46	151	2.0	1189	0.127	100	NA	NA
Approach	104	1	46	151	2.0		0.127			
West: Arborwalk Boulevard										
Mov.	L2	T1	R2	Total	%HV		Deg. Satn	Lane Util.	Prob. SL Ov.	Ov. Lane No.
From W To Exit:	N	E	S			Cap. veh/h	v/c	%	%	No.
Lane 1	62	63	14	139	2.0	1143	0.122	100	NA	NA
Approach	62	63	14	139	2.0		0.122			
Total %HV Deg. Satn (v/c)										
Intersection	572	2.0		0.190						

Lane flow rates given in this report are based on the arrival flow rates subject to upstream capacity constraint where applicable.

Merge Analysis												
	Exit Lane Number	Short Lane Length ft	Percent Opng in Lane %	Opposing Flow Rate veh/h	Critical Gap sec	Follow-up Headway sec	Lane Flow Rate veh/h	Capacity veh/h	Deg. Satn v/c	Min. Delay sec	Merge Delay sec	
South Exit: Access B												
Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.
East Exit: Arborwalk Boulevard												
Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.
North Exit: Arborway Drive												
Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.
West Exit: Arborwalk Boulevard												
Merge Type: Not Applied												
Full Length Lane	1											Merge Analysis not applied.

HCM 7th TWSC
5: Arborwalk Boulevard & Arbor Park Drive

Future (Year 2044) Traffic Volumes
PM Peak Hour

Intersection						
Int Delay, s/veh	1.1					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W			W	W	
Traffic Vol, veh/h	12	5	14	115	91	12
Future Vol, veh/h	12	5	14	115	91	12
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	89	89	89	89	89	89
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	13	6	16	129	102	13
Major/Minor	Minor2	Major1		Major2		
Conflicting Flow All	270	109	116	0	-	0
Stage 1	109	-	-	-	-	-
Stage 2	161	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	720	945	1473	-	-	-
Stage 1	916	-	-	-	-	-
Stage 2	868	-	-	-	-	-
Platoon blocked, %				-	-	-
Mov Cap-1 Maneuver	711	945	1473	-	-	-
Mov Cap-2 Maneuver	711	-	-	-	-	-
Stage 1	905	-	-	-	-	-
Stage 2	868	-	-	-	-	-
Approach	EB	NB		SB		
HCM Control Delay, s/v	9.81	0.81		0		
HCM LOS	A					
Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR	
Capacity (veh/h)	195	-	767	-	-	
HCM Lane V/C Ratio	0.011	-	0.025	-	-	
HCM Control Delay (s/veh)	7.5	0	9.8	-	-	
HCM Lane LOS	A	A	A	-	-	
HCM 95th %tile Q(veh)	0	-	0.1	-	-	

HCM 7th TWSC
6: Arborwalk Boulevard & Access A

Future (Year 2044) Traffic Volumes
PM Peak Hour

Intersection						
Int Delay, s/veh	0.8					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	W	W	T	T	T	T
Traffic Vol, veh/h	8	5	126	13	9	87
Future Vol, veh/h	8	5	126	13	9	87
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	89	89	89	89	89	89
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	9	6	142	15	10	98


Major/Minor	Minor1	Major1	Major2
Conflicting Flow All	267	149	0
Stage 1	149	-	-
Stage 2	118	-	-
Critical Hdwy	6.42	6.22	-
Critical Hdwy Stg 1	5.42	-	-
Critical Hdwy Stg 2	5.42	-	-
Follow-up Hdwy	3.518	3.318	-
Pot Cap-1 Maneuver	722	898	-
Stage 1	879	-	-
Stage 2	907	-	-
Platoon blocked, %		-	-
Mov Cap-1 Maneuver	717	898	-
Mov Cap-2 Maneuver	717	-	-
Stage 1	879	-	-
Stage 2	900	-	-

Approach	WB	NB	SB
HCM Control Delay, s/v	9.72	0	0.71
HCM LOS	A		

Minor Lane/Major Mvmt	NBT	NBRWBLn1	SBL	SBT
Capacity (veh/h)	-	-	777	169
HCM Lane V/C Ratio	-	-	0.019	0.007
HCM Control Delay (s/veh)	-	-	9.7	7.5
HCM Lane LOS	-	-	A	A
HCM 95th %tile Q(veh)	-	-	0.1	0

Appendix F: Signal Warrant Analysis





SIGNAL WARRANTS ANALYSIS

Ward Road and Arborwalk Boulevard
Existing (2024) Conditions

LOCATION: Lee's Summit
COUNTY: Jackson
REF. POINT:
DATE: 1/24/2025
OPERATOR: KH

Speed	Approach Description	Lanes
45	Major App1:	Northbound Ward Road
45	Major App3:	Southbound Ward Road
30	Minor App2:	Eastbound Arborwalk Boulevard
	Minor App4:	

0.70 FACTOR USED? yes
POPULATION < 10,000? no
EXISTING SIGNAL ? no
THRESHOLDS 1A/1B:

	420		630		140		70		140		70			
MAJOR APP. 1	MAJOR APP. 3	TOTAL 1+3	MAJOR 1A	MAJOR 1B	MINOR APP. 2	MINOR 2 1A	MINOR 2 1B	MINOR APP. 4	MINOR 4 1A	MINOR 4 1B	MAJ & MIN 1A	MAJ & MIN 1B		
0:00 - 1:00		0												
1:00 - 2:00		0												
2:00 - 3:00		0												
3:00 - 4:00		0												
4:00 - 5:00		0												
5:00 - 6:00		0												
6:00 - 7:00	248	104	352			66								
7:00 - 8:00	516	316	832	X	X	103		X						X
8:00 - 9:00	412	226	638	X	X	63								
9:00 - 10:00	267	206	473	X		35								
10:00 - 11:00	223	238	461	X		54								
11:00 - 12:00	234	236	470	X		45								
12:00 - 13:00	237	288	525	X		57								
13:00 - 14:00	247	293	540	X		41								
14:00 - 15:00	314	488	802	X	X	49								
15:00 - 16:00	337	504	841	X	X	63								
16:00 - 17:00	379	489	868	X	X	85		X						X
17:00 - 18:00	436	579	1015	X	X	76		X						X
18:00 - 19:00	270	388	658	X	X	60								
19:00 - 20:00			0											
20:00 - 21:00			0											
21:00 - 22:00			0											
22:00 - 23:00			0											
23:00 - 24:00			0											

	Met (Hr)	Required (Hr)	
Warrant 1a	0	8	Not satisfied
Warrant 1b	3	8	Not satisfied
Warrant 2	0	4	Not satisfied
Warrant 3	0	1	Not satisfied
Warrant 7	0	8	Not satisfied

LOCATION: Lee's Summit
COUNTY: Jackson
REF. POINT:
DATE: 1/24/2025

OPERATOR: KH

Speed	Approach Description	Lanes
45	Major App1:	Northbound Ward Road
45	Major App3:	Southbound Ward Road
30	Minor App2:	Eastbound Arborwalk Boulevard
	Minor App4:	

0.70 FACTOR USED? yes
POPULATION < 10,000? no
EXISTING SIGNAL ? no





Figure 1. Four Hour and Peak Hour Warrant Analysis

Note: For data points outside the graph range, check the minor street volume against the lower thresholds



SIGNAL WARRANTS ANALYSIS

Ward Road and Arborwalk Boulevard
Existing + Development Conditions

LOCATION: Lee's Summit
COUNTY: Jackson
REF. POINT:
DATE: 1/24/2025
OPERATOR: KH

Speed	Approach Description	Lanes
45	Major App1:	Northbound Ward Road
45	Major App3:	Southbound Ward Road
30	Minor App2:	Eastbound Arborwalk Boulevard
	Minor App4:	

0.70 FACTOR USED? yes
POPULATION < 10,000? no
EXISTING SIGNAL ? no
THRESHOLDS 1A/1B:

THRESHOLDS 1A/1B:			420	630	140	70	140	70				
MAJOR APP. 1	MAJOR APP. 3	TOTAL 1+3	MAJOR 1A	MAJOR 1B	MINOR APP. 2	MINOR 2 1A	MINOR 2 1B	MINOR APP. 4	MINOR 4 1A	MINOR 4 1B	MAJ & MIN 1A	MAJ & MIN 1B
0:00 - 1:00		0										
1:00 - 2:00		0										
2:00 - 3:00		0										
3:00 - 4:00		0										
4:00 - 5:00		0										
5:00 - 6:00		0										
6:00 - 7:00	253	109	361		110		X					
7:00 - 8:00	522	322	845	X	X	172	X	X			X	X
8:00 - 9:00	422	236	658	X	X	118		X				X
9:00 - 10:00	276	215	492	X	67							
10:00 - 11:00	231	246	476	X	85		X					
11:00 - 12:00	246	248	494	X	75		X					
12:00 - 13:00	251	302	554	X	83		X					
13:00 - 14:00	260	306	566	X	69							
14:00 - 15:00	332	506	838	X	X	81		X				X
15:00 - 16:00	359	526	885	X	X	97		X				X
16:00 - 17:00	411	521	933	X	X	121		X				X
17:00 - 18:00	473	616	1088	X	X	125		X				X
18:00 - 19:00	301	419	720	X	X	103		X				X
19:00 - 20:00		0										
20:00 - 21:00		0										
21:00 - 22:00		0										
22:00 - 23:00		0										
23:00 - 24:00		0										

	Met (Hr)	Required (Hr)	
Warrant 1a	1	8	Not satisfied
Warrant 1b	7	8	Not satisfied
Warrant 2	3	4	Not satisfied
Warrant 3	0	1	Not satisfied
Warrant 7	0	8	Not satisfied

LOCATION: Lee's Summit
COUNTY: Jackson
REF. POINT:
DATE: 1/24/2025
OPERATOR: KH

Speed	Approach Description	Lanes
45	Major App1:	Northbound Ward Road
45	Major App3:	Southbound Ward Road
30	Minor App2:	Eastbound Arborwalk Boulevard
	Minor App4:	

0.70 FACTOR USED? yes
POPULATION < 10,000? no
EXISTING SIGNAL ? no





Figure 1. Four Hour and Peak Hour Warrant Analysis

Note: For data points outside the graph range, check the minor street volume against the lower thresholds



SIGNAL WARRANTS ANALYSIS

Ward Road and Arborwalk Boulevard
Future Conditions

LOCATION: Lee's Summit
COUNTY: Jackson
REF. POINT:
DATE: 1/27/2025
OPERATOR: KH

Speed	Approach Description	Lanes
45	Major App1:	Northbound Ward Road
45	Major App3:	Southbound Ward Road
30	Minor App2:	Eastbound Arborwalk Boulevard
	Minor App4:	

0.70 FACTOR USED? yes
POPULATION < 10,000? no
EXISTING SIGNAL ? no

THRESHOLDS 1A/1B:			420	630	140	70	140	70				
MAJOR APP. 1	MAJOR APP. 3	TOTAL 1+3	MAJOR 1A	MAJOR 1B	MINOR APP. 2	MINOR 2 1A	MINOR 2 1B	MINOR APP. 4	MINOR 4 1A	MINOR 4 1B	MAJ & MIN 1A	MAJ & MIN 1B
0:00 - 1:00		0										
1:00 - 2:00		0										
2:00 - 3:00		0										
3:00 - 4:00		0										
4:00 - 5:00		0										
5:00 - 6:00		0										
6:00 - 7:00	366	156	522	X	141	X	X				X	
7:00 - 8:00	758	467	1225	X	X	220	X	X			X	X
8:00 - 9:00	610	339	949	X	X	146	X	X			X	X
9:00 - 10:00	398	309	708	X	X	83		X				X
10:00 - 11:00	333	354	687	X	X	110		X				X
11:00 - 12:00	353	356	709	X	X	96		X				X
12:00 - 13:00	360	434	794	X	X	109		X				X
13:00 - 14:00	373	440	812	X	X	88		X				X
14:00 - 15:00	475	729	1204	X	X	103		X				X
15:00 - 16:00	513	756	1270	X	X	126		X				X
16:00 - 17:00	585	745	1329	X	X	160	X	X			X	X
17:00 - 18:00	672	880	1552	X	X	160	X	X			X	X
18:00 - 19:00	425	596	1021	X	X	131		X				X
19:00 - 20:00		0										
20:00 - 21:00		0										
21:00 - 22:00		0										
22:00 - 23:00		0										
23:00 - 24:00		0										

	Met (Hr)	Required (Hr)	
Warrant 1a	5	8	Not satisfied
Warrant 1b	12	8	Satisfied
Warrant 2	7	4	Satisfied
Warrant 3	5	1	Satisfied
Warrant 7	0	8	Not satisfied

LOCATION: Lee's Summit
COUNTY: Jackson

REF. POINT:
DATE: 1/27/2025

OPERATOR: KH

Speed	Approach Description	Lanes
45	Major App1:	Northbound Ward Road
45	Major App3:	Southbound Ward Road
30	Minor App2:	Eastbound Arborwalk Boulevard
	Minor App4:	

0.70 FACTOR USED? yes
POPULATION < 10,000? no
EXISTING SIGNAL ? no




Figure 1. Four Hour and Peak Hour Warrant Analysis

Note: For data points outside the graph range, check the minor street volume against the lower thresholds