



**Lee's Summit**  
**Change Order Details**  
Water Main Replacement FY19

---

<b>Description</b>	Installation of 10,100 feet of water main, hydrants, valves, fittings, service lines, service connections, connections to existing water mains, surface restoration including all materials, labor, equipment, testing, supervision, and any and all other items necessary to complete the work. Vendor # 9661 Purchase Order #124092
<b>Prime Contractor</b>	Westland Construction INC 20510 163rd Street Basehor, KS 66007
<b>Change Order</b>	2
<b>Status</b>	Pending
<b>Date Created</b>	10/28/2019
<b>Type</b>	City Council Approval
<b>Summary</b>	Change Order 2
<b>Change Order Description</b>	A few changes needed to made to the designed plans, these changes were necessary in order to complete the project. The designed constructions methods also needed to be changed due to field conditions. All equipment and materials necessary to install these items in accordance with the contract requirements. This work is necessary to resolve a conflicts which came up during construction.
<b>Awarded Project Amount</b>	\$1,224,772.00
<b>Authorized Project Amount</b>	\$1,278,869.15
<b>Change Order Amount</b>	\$24,173.35

Revised Project Amount      \$1,303,042.50

**Increases/Decreases**

Line Number	Item ID	Unit	Unit Price	Current		Change		Revised	
				Quantity	Amount	Quantity	Amount	Quantity	Amount
<b>Section: 1 - FY19 Watermain Replacement</b>									
0050	30C	CY	\$105.000	61.500	\$6,457.50	18.000	\$1,890.00	79.500	\$8,347.50
Flowable Fill									
<b>Reason:</b> An abandoned storm box was discovered in Woods Chapel road. For safety we decided to fill the structure to prevent future problems.									
1 item			Totals		\$6,457.50		\$1,890.00		\$8,347.50

**New Items**

Line Number	Item ID	Unit	Quantity	Unit Price	Extension
<b>Section: 1 - FY19 Watermain Replacement</b>					
0060	31-C	CY	115.790	\$110.000	\$12,736.90
Rock Excavation					
<b>Reason:</b> A few portions on Woods Chapel called for pipe bursting. Because the original pipe was cut into rock, the pipe could not be bursted. The decision was made to open cut for the new watermain in an offset location, causing the contractor to excavate rock and supply bedding, which could not have been foreseen at the time of bid.					
0070	32-C	LF	779.000	\$8.050	\$6,270.95

Line Number	Item ID	Unit	Quantity	Unit Price	Extension
Gravel for Rock Excavation					
<b>Reason:</b> A few portions on Woods Chapel called for pipe bursting. Because the original pipe was cut into rock, the pipe could not be bursted. The decision was made to open cut for the new watermain in an offset location, causing the contractor to excavate rock and supply bedding, which could not have been foreseen at the time of bid.					
0090	33-C	EA	1.000	\$2,390.000	\$2,390.00
Removal and replacement of fire hydrant					
<b>Reason:</b> We made an adjustment to the original plan. After the water line was installed we decided if we installed one more valve future water shut downs would not disrupt this streets water service.					
0100	34-C	SY	11.000	\$80.500	\$885.50
Replace gravel driveway					
<b>Reason:</b> There was a gravel driveway missed on the plans.					
4 items					Total: \$22,283.35