

Exhibit A

WIEDENMANN, INC.

950 N. Scott / PO BOX 245
Belton, MO 64012
816-322-1125 / Fax 816-322-1126
general@wiedenmanninc.com

November 28, 2017

SCS Engineers
7311 W. 130th St
Suite 100
Overland Park, KS 66213

Attn: Anastasia Welch

RE: Leachate Cut-Off Trench

Dear Anastasia,

Pursuant to your request, we hereby submit the following budget price to install the leachate cut-off trench. Included in the budget price is 75cy of Cement - Bentonite Clay slurry, trench shoring, and site restoration. This budget price is based on plans sent to us on 11-10-17 and the on-site meeting with Anastasia Welch, Chris Bussen, and David Lohe on Monday 11-20-17 at 9:00AM. Our understanding of the project is with a track hoe excavate to rock along the line set by others. Excavated materials will be placed up hill to limit water shed. With the track hoe teeth roughen the rock surface. On approximately twenty-foot intervals survey the rock elevation for records. Furnish and place approved cement bentonite slurry, minimum two-foot thick. Allow the slurry to cure one week then build the trench out per the design. Transport spoils on site for owners use. Place straw, commercial seed and fertilizer on work area.

The total budget value of this work based on a time and material basis is:

Sixty Three Thousand Six Hundred and Eight One Dollars & No Cents

\$63,681.00

We understand that this is a budget price for the scope of work, and the actual work will be completed per instructions and MDNR plan approval.

We have excluded material testing, outside clay fill, disposal of spoils off site, and staking. We anticipated less than a one-mile haul trip for dump trucking. We understand that the power line near the work area can be deenergized.

We appreciate the opportunity to price and perform work for SCS Engineers and the City of Lee's Summit.

Please call with questions.

Sincerely
Wiedenmann Inc.
Daniel Forbes