## Opinion of Probable Cost (OPC) for Construction: Lee's Summit Logistics Public Street Improvments

## olsson

8/11/2021

QTY Unit **Unit Price** Cost Improvements \$100,000.00 Mobilization 1 Lump Sum \$ 100,000.00 Clearing and Grubbing 25 Acre \$ 7,000.00 \$175,000.00 Earthwork (67,000 CY or cut and 70,000 SY or fill for street improvments) 137600 CY \$ 8.00 \$1,100,800.00 Asphalt for Street Relocations (9.5" total) 13511 SY \$ 75.00 \$1,013,325.00 Street Agg Base (12") \$ \$450,660.00 15022 SY 30.00 Concrete Sidewalk (5' wide - 4" thick) 33,940 SF \$ 7.00 \$237,580.00 7204 \$180,100.00 Concrete Curb and Gutter LF \$25 \$15,000.00 ADA Sidewalk Ramps EA \$2,500 6 Pavement Markings 6800 LF \$2 \$13,600.00 1 Lump Sum \$ 773,500.00 \$773,500.00 Pubilc Street Storm Sewer 1 Lump Sum \$ 150,000.00 RCB Main Street Storm Crossing (double 12'x4') \$150,000.00 Public Street Lighting 3400 LF \$ 60.00 \$204,000.00 12" Public Water Main Relocation along Main Street 3200 LF \$ 60.00 \$192,000.00 Removal of Existing Public Streets 9500 SY \$ 30.00 \$285,000.00 Sod (within Public Right of Way) 3757 SY \$ 6.50 \$24,420.50 4840 Replace Topsoil (6") CY \$ 10.00 \$48,400.00 \$70,000.00 Seeding 20 Acre \$ 3,500.00 \$50,000.00 Erosion Control 1 Lump Sum \$ 50,000.00 **SUBTOTAL:** \$5,083,385.50 **CONCEPTUAL DESIGN CONTINGENCY (30%):** \$1,525,015.65 **TOTAL (BASE+CONTINGENCY):** \$6,608,401.15

Assumptions:

- 1. The OPC is based on a Concept. Revise OPC at Final Design. The OPC includes the removal of
- 2. The OPC does not include cost for overhead power line relocation. This amount will need to be determined by the electrical company.
- 3. Environmental/Historical Investigations and Permitting are not included.
- 4. Permitting and Bonding are not included.
- 5. Final design, Construction Inspection, and Testing is not included.
- 6. Rock excavation is not included.
- 7. It is assumed all work will be completed in 1 Phase.
- 8. Topsoil can be salvaged and reused.
- 9. Earthwork for public street improvements assumed gradeing 100 feet on each side of the Main Street centerline



